

Answers to Bidders Questions

Date: March 5, 2013

Project: Shaw Lane Lime Residual Disposal Facility Overall Site Plan

C.I.P. No. 8702.003

IFB Number: 6100 CLMC412

The following are answers to questions received by the City on the above project. These answers do not modify the Contract. Any modifications to the Contract will be through Addenda

Q: What date is the bid opening?

A: March 14, 2013 as indicated on Section 00020 issued with Addendum 3.

Q: Is Dillo Dirt required in topsoil?

A: Please refer to section 601S for specific topsoil requirements.

Q: Do the 29 acres of the West Pit, the nine (9) acres along the levee and the seven (7) acres of the riparian corridor along Onion Creek need irrigation for two (2) years as mentioned in section 00810 Supplemental General Conditions, 14.11.1 Final Payment and Acceptance?

A: No.

Q: For Shaw Lane Lime Residual Disposal Facility, the specifications manual doesn't have descriptions for line items 420S-A and 436S. The line item descriptions jump from 413S to 503S skipping 420S and 436S. Is the spec for missing items available online? If not, what is the best way to get it?

A: The referenced specifications were added to the contract in Addendum 2. Please refer to addendum 2 for the complete text of the specifications indicated.

Q: Will off-site soil be required for the construction of the levee in the far west pit? Will excavation of the borrow area be paid for directly?

A: Our calculations indicate that approximately three times the required amount of soil required for bid item 132S-A-4:1 (perimeter access road/levee embankment) is available in the borrow area indicated on

the plans in the far west pit. The proposed contours of the far west pit borrow area shall be considered maximum excavation limits. Contractor shall excavate as necessary to obtain sufficient suitable material for construction of the proposed levee. Unsuitable material that must be excavated in order to access suitable material shall be compacted at an acceptable alternative location on the project site and shall be paid for at the embankment (132S-A-4:1) bid price via change order if necessary. The final side slope of the borrow area shall match the final slope shown on the plans (combination of 3:1 and 25:1). Excavation will not be paid for directly.

Q: Is grading the West Pit up to and before the 1' clay and 1' topsoil a subsidiary of what Bid Item?

A: Bid Item 132S-A-Clay (Embankment of 12" thick clay fill for west pit, off-site materials).