

NOTES:

1.

CONTRACTOR SHALL NOTIFY THE PUBLIC WORKS DEPARTMENT 24 HOURS PRIOR TO STARTING CONSTRUCTION OR CLEARING OPERATIONS.
2.

CONTRACTOR SHALL CALL "ONE CALL" AT 1-800-344-8377 FOR UTILITY LOCATIONS AT LEAST 48 HOURS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET RIGHT OF WAYS.
3.

THIS PROJECT IS LOCATED WITHIN THE JOHNSON CREEK WATERSHED (CLASSIFIED AS WATER SUPPLY SUBURBAN) AND SHALL BE DEVELOPED, CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH CHAPTER 25 OF THE CODE OF THE CITY OF AUSTIN.
4.

NO PORTION OF THIS SITE IS LOCATED WITHIN PARKLAND OR LAND USED FOR PARK PURPOSES. (IF SUCH LAND IS INCLUDED, DOCUMENTATION OF PARKS AND RECREATION DEPT APPROVAL IS REQUIRED AT THE TIME OF SUBMITTAL FOR GENERAL PERMIT PROGRAM APPROVAL.)
5.

NO PORTION OF THIS SITE IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN, PER CITY OF AUSTIN AND FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS. PER FLOOD INSURANCE RATE MAP NO. 48453C0445J.
6.

THIS PROJECT NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS DEFINED BY THE CITY OF AUSTIN. THIS PROJECT NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS REGULATED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ).
7.

THERE ARE NO CRITICAL ENVIRONMENTAL FEATURES WITHIN 150' OF ANY PORTION OF THIS PROJECT A FIELD INVESTIGATION HAS NOT BEEN PERFORMED AS A PART OF THIS PROJECT AND IS NOT REQUIRED.
8.

THE STANDARD SHEETS INCLUDED IN THIS PLAN SET WERE PROVIDED BY THE GENERAL PERMIT PROGRAM OFFICE FOR USE ON GENERAL PERMIT PROJECTS ONLY. IF ANY MODIFICATIONS TO THE SHEETS WERE MADE, THEY ARE CLEARLY INDICATED ON THE SHEET ITSELF AND IN THE COVER SHEET INDEX.
9.

ADDITIONAL TRENCH E/S CONTROL: TRIANGULAR SEDIMENT FILTER DIKE WILL BE INSTALLED ACROSS FULL WIDTH OF TRAFFIC CLOSURE AND DOWNSTREAM OF CONSTRUCTION AREA, PERPENDICULAR TO CURB. FILTER DIKE TO FOLLOW ACTIVE CONSTRUCTION. REMOVING AND RE-SETTING FILTER DIKE IS CONSIDERED SUBSIDIARY TO BARRICADES AND TRAFFIC HANDLING.
10.

PROJECT SCHEDULE MUST BE APPROVED BY THE GENERAL PERMIT PROGRAM (GPP) COORDINATOR. INSTALLATION AND REMOVAL OF TEMPORARY AND PERMANENT EROSION/SEDIMENTATION CONTROLS MUST BE REFLECTED IN THE SCHEDULE, BY STATION NUMBER. GPP ARBORIST MUST BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE OF TRANSITION BETWEEN PHASES.
11.

APPROPRIATE EASEMENTS/APPROVALS MUST BE SECURED AND DOCUMENTED FOR PROJECT AREAS LOCATED OUTSIDE OF RIGHT OF WAYS. NO WORK SHALL BE PERFORMED WITHIN THESE AREAS UNTIL ASSOCIATED RIGHT OF ENTRY HAS BEEN SECURED. ADDITIONALLY, THIS PROJECT WILL NOT BE CONSIDERED COMPLETE UNTIL ALL RECORDED EASEMENT DOCUMENT NUMBERS HAVE BEEN OBTAINED AND SHOWN ON PLANS.
12.

COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
13.

ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
14.

UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.
15.

CONTRACTOR SHALL STAKE ALL PROPOSED SERVICE CONNECTIONS LOCATED WITHIN THE CRITICAL ROOT ZONE OF TREES 8" IN CALIPER AND LARGER AT LEAST 21 CALENDAR DAYS PRIOR TO CONSTRUCTION OF SUCH SERVICES. STAKING SHALL CONSIST OF A LATH WITH NAIL AND PAINT MARKINGS. IN CASES WHERE A STAKE CANNOT BE PLACED WITHOUT DAMAGING PROPERTY, CONTRACTOR MAY USE PAINT ONLY. ONCE STAKING IS COMPLETE ITS THE CONTRACTORS RESPONSIBILITY TO INFORM THE CITY OF AUSTIN CONSTRUCTION INSPECTOR WITHIN TWENTY-FOUR HOURS. THE CITY OF AUSTIN'S CONSTRUCTION INSPECTOR WILL THEN COORDINATE A FIELD REVIEW OF THE SERVICE LOCATIONS WITH THE GENERAL PERMIT PROGRAM COORDINATOR AND PROPERTY OWNERS. SERVICE LINE LOCATIONS MAY BE ADJUSTED BASED ON THE REVIEW AND WILL BE RESTAKED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL SERVICE LINE STAKING SHALL BE MAINTAINED UNTIL THE SERVICE IS INSTALLED.

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT

NOVEMBER 2020

IFBXXX CLMC643


C.I.P. NO. 2231.334

AWU PROJECT # 2231.334

ROW ID # 11903857

UC TRACKING # UUC-180412-04-02

AUSTIN WATER  
EXPIRATION DATE  
December 02, 2023



PROJECT INFORMATION:

STREET ADDRESS:  
BRYKER DRIVE AND W. 34TH STREET  
AUSTIN, TX 78724  
COA GRID: N25  
MAPSCO: MAP 554V

CLIENT/SPONSOR:  
CITY OF AUSTIN  
AUSTIN WATER UTILITY  
625 EAST 10TH STREET  
AUSTIN, TX 78701

PROJECT MANAGEMENT:  
CITY OF AUSTIN  
DEPARTMENT OF PUBLIC WORKS  
PROJECT MANAGEMENT DIVISION  
505 BARTON SPRINGS RD., STE. 900  
AUSTIN, TX 78704

CONTACT:  
AZARI HOUMAN, PE  
(512) 972-2049

CONTACT:  
SHOBANA ANGIA, PMP  
PHONE: (512) 974-1581

SUBMITTAL PREPARED BY:

**ARCADIS**  
1717 WEST 6TH STREET, SUITE 210  
AUSTIN, TX 78703  
TEXAS BOARD OF PROFESSIONAL ENGINEERS  
FIRM REGISTRATION NUMBER F-533

CONTACT:  
JEFFREY RECK, P.E.  
PH: (210) 469-3351  
EMAIL: JEFFREY.RECK@ARCADIS.COM



APPROVALS:

SUBMITTED FOR APPROVAL BY:

11-12-2020

PROJECT ENGINEER - JEFFREY RECK, P.E.

DATE

APPROVED BY:

December 03, 2020

GENERAL PERMIT PROGRAM COORDINATOR

DATE

GP-2020-0000.AWU

DEVELOPMENT PERMIT NUMBER

SUBMITTAL DATE

REVIEWED BY:

AUSTIN WATER UTILITY

DATE

PROJECT SPONSOR






















DATE


ANNUAL GENERAL PERMIT NUMBER

AULCC NUMBER

GENERAL PERMIT PROGRAM CORRECTIONS RECORD						
No.	DESCRIPTION	BY	CORRECT (C) ADD (A) VOID (V) SHEET Nos.	TOTAL No. SHEETS IN CORRECTION PLAN SET	CITY OF AUSTIN APPROVAL/DATE	DATE IMAGED



E	SHEET INDEX			CIVIL SYMBOLS			VALVE SYMBOLS			ABBREVIATIONS				<div><div></div><div>FIRM REGISTRATION NUMBER: F-533</div></div>
	SEQ. NO	SHEET NO	DESCRIPTION	EXISTING		PROPOSED			ABBREVIATION	DESCRIPTION	ABBREVIATION	DESCRIPTION		
	GENERAL													
	1	G-01	COVER SHEET		WATER VALVE		PROPOSED EXPOSED PIPELINE (4-INCHES AND LARGER)		FEMALE QUICK COUPLING CONNECTION	AFF	ABOVE FINISHED FLOOR	MH	MANHOLE	
	2	G-02	SHEET INDEX, SYMBOLS AND ABBREVIATIONS		WATER METER		PROPOSED BURIED PIPELINE (4-INCHES AND LARGER)		FLOW ELEMENT	ARV & APPROX @ AWWA	AIR RELEASE VALVE AND APPROXIMATE AT AMERICAN WATER WORKS ASSOCIATION AUTOMATIC SWITCHOVER AUSTIN WATER UTILITY	MAX. MECH. MIN. MIXER	MECHANICAL MECHANICAL JOINT MINIMUM MIXER MILLION GALLON	
	3	G-03	GENERAL NOTES		WATER MANHOLE		STEEL CASING (PLAN VIEW)		GATE VALVE (GV)	AS AWU		N	NORTH NUMBER	
	4	G-04	AUSTIN WATER GENERAL INFORMATION AND CONSTRUCTION NOTES		WASTEWATER MANHOLE		STEEL CASING (PROFILE VIEW)		PLUG VALVE (OPEN)	BP	BOOSTER PUMP	NPT	NATIONAL PIPE THREAD	
	5	G-05	SITE MILLING AND OVERLAY LAYOUT PLAN		STORM MANHOLE		CONSTRUCTION CONTROL POINT		PLUG VALVE (CLOSED)	BM	BENCH MARK	NPW	NON POTABLE WATER	
	6	G-06	EXISTING UTILITIES ABANDONMENT LAYOUT PLAN		TELEPHONE MANHOLE		BENCH MARK NUMBER DESIGNATION		CHECK VALVE (CKV)	BF	BLIND FLANGE	NTS	NOT TO SCALE	
D	7	G-07	DEPTH OF COVER CALCULATION DETAILS						BALL VALVE	BV	BALL VALVE	OC	ON CENTER	
	CIVIL								DRAIN	BWD	BARBED WIRE FENCE	OD	OUTSIDE DIAMETER	
	8	C-01	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 0+00 to 4+00							CG	CHLORINE GAS	P	PUMP	
	9	C-02	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 4+00 to 8+00							CO	CLEAN OUT	PVMT	PAVEMENT	
	10	C-03	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 8+00 to 12+00							COV	CONE VALVE	±	PLUS OR MINUS	
	11	C-04	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 12+00 to 16+60							CAV	COMBINATION AIR VALVE	PT. OR	POINT	
	12	C-05	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 19+75 to 24+00							CML	CEMENT MORTAR LINED	PNT	POINT OF CURVATURE	
	13	C-06	PROPOSED 8 IN WATERLINE PLAN AND PROFILE STA. 24+00 to 27+88.97							CMP	CORRUGATED METAL PIPE	PC	POINT OF INTERSECTION	
	14	C-07	PROPOSED 8IN WATERLINE PLAN AND PROFILE STA. 29+75 TO 31+50							CL	CENTERLINE	PI	POINT OF TANGENCY	
	15	C-08	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 0+75 to 5+00							CLD	CONCRETE	PT	POINT OF VERTICAL INTERSECTION	
	16	C-09	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 5+00 to 9+00							CCP	CONCRETE CYLINDER PIPE	PVI	PUMP STATION	
	17	C-10	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 9+00 to 13+00							CPLG	COUPLING	PS	POUNDS PER SQUARE INCH	
	C	18	C-11	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 13+00 to 17+85							C	CONSTRUCTION JOINT	PSI	PRECAST CONCRETE CYLINDER PIPE
19		C-12	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 19+75 to 24+00							CJ	CURVE	PCCP	OR PORTLAND CEMENT CONCRETE PAVEMENT	
20		C-13	PROPOSED 8 IN WASTEWATER LINE PLAN AND PROFILE STA. 24+00 to 28+50							CONST.	CONSTRUCTION	PG	PRESSURE GAUGE	
EROSION AND SEDIMENT CONTROL									CL	CHLORINE	PSF	POUND PER SQUARE FOOT		
21		L1.00	EROSION AND SEDIMENT CONTROL PLAN							CLF	CHAIN LINK FENCE	PL OR R	PROPERTY LINE	
22		L1.01	EROSION AND SEDIMENT CONTROL PLAN							CV	CHECK VALVE	PRC	POINT OF REVERSE CURVATURE	
23		L1.02	EROSION AND SEDIMENT CONTROL PLAN							CI	CORROSION INHIBITOR	PLMK	PIPELINE MARKER	
24		L1.10	EROSION AND SEDIMENT CONTROL DETAILS							CLD	CHLORINE LEAK DETECTOR	POLY	POLYMER	
25		L1.11	EROSION AND SEDIMENT CONTROL DETAILS							CNP	CONTROL CONSTRUCTION POINT	POB	POINT OF BEGIN	
TRAFFIC CONTROL									CP	CONTROL PANEL	PP	POWER POLE		
26		TC-01	MASTER TRAFFIC CONTROL PLAN							CSC	CONCRETE STEEL CYLINDER	PROP	PROPOSED	
27		TC-02	TRAFFIC CONTROL NOTES							COA	CITY OF AUSTIN	PVC	POLYVINYL CHLORIDE	
28		TC-03	BRYKER FROM 30TH TO 31ST DETOUR							CONN.	CONNECTIONS	PW	POTABLE WATER	
B	29	TC-04	31ST - BRYKER INTERSECTION DETOUR							D	DRAIN	PRV	PRESSURE REDUCING VALVE	
	30	TC-05	BRYKER FROM 31ST TO 32ND DETOUR							DAFTS	DISSOLVED AIR FLOATION TANKS	R	RADIUS	
	31	TC-06	32ND - BRYKER INTERSECTION DETOUR							DV	DENSE VEGETATION	RED	REDUCER	
	32	TC-07	32ND FROM BRYKER TO BEVERLY							DIA.	DIAMETER	RED'G	REDUCING	
	33	TC-08	BRYKER FROM 32ND TO 33RD DETOUR							DIM	DIMENSION	REINF	REINFORCE	
	34	TC-09	BRYKER FROM 33RD TO 34TH DETOUR							DWGS	DRAWINGS	RCCP	REINFORCED CONCRETE CYLINDER PIPE	
	35	TC-10	34TH FROM OAKMONT TO BEVERLY DETOUR							DI OR DIP	DUCTILE IRON PIPE	REQD	REQUIRED	
	36	TC-11	BEVERLY - 34TH INTERSECTION DETOUR							DGW	DISINFECTED GROUNDWATER	RJ	RESTRAINED JOINT	
	37	TC-12	34TH FROM BEVERLY TO BRYKER DETOUR							DR	DOS RIOS	ROW	RIGHT-OF-WAY	
	38	TC-13	BRYKER - 34TH INTERSECTION DETOUR							DCO	DOUBLE CLEAN OUT	RT.	RIGHT	
	39	TC-14	34TH FROM BRYKER TO JEFFERSON DETOUR							E	EAST	SA	SAMPLE	
	40	TC-15	JEFFERSON - 34TH INTERSECTION DETOUR							EAS	EXCESS ACTIVATED SLUDGE	S	SOUTH	
	A	41	TC-16	TRAFFIC CONTROL DETAILS							EXIST.	EXISTING	SBF	SLUDGE BLENDING FACILITIES
42		TC-17	TRAFFIC CONTROL DETAILS							EA	EACH	SNT	SLUBNATANT	
43		TC-18	TRAFFIC CONTROL DETAILS							E.W.	EACH WAY	SBT	SLUDGE BLENDING TANK	
44		TC-19	TRAFFIC CONTROL DETAILS							E.F.	EACH FACE	SHT	SHEET	
45		TC-20	TRAFFIC CONTROL DETAILS							ELEC.	ELECTRIC	SCB	SCRUBBER	
46		TC-21	TRAFFIC CONTROL DETAILS							EL. OR ELEV.	ELEVATION	SCV	SILENT CHECK VALVE	
47		TC-22	TRAFFIC CONTROL DETAILS							EP	EDGE OF PAVEMENT	SD	STORM DRAIN	
48		TC-23	TRAFFIC CONTROL DETAILS							ESMT OR ESMT.	EASEMENT	SF	SILT FENCE	
STANDARDS DETAIL SHEETS									FF	FINISHED FLOOR	SLG	SLUDGE		
49		SD-01	STANDARD DETAILS							FL	FLOOR LEVEL	SPEC.	SPECIFICATION	
50		SD-02	STANDARD DETAILS							FLG	FLANGE	SS, SST	STAINLESS STEEL	
51		SD-03	STANDARD DETAILS							FCA	FLANGED COUPLING ADAPTER	STD	STANDARD	
52		SD-04	STANDARD DETAILS							FLEX	FLEXIBLE	STA	STATION	
53	SD-05	STANDARD DETAILS							FT	FOOT OR FEET	STL	STEEL		
54	SD-06	STANDARD DETAILS							GB	GRADE BREAK	SP	STOCK PILE		
55	SD-07	STANDARD DETAILS							GV	GATE VALVE	SSK	SECONDARY SKIMMINGS		

CITY OF AUSTIN, TEXAS AUSTIN WATER UTILITY			
			
BRYKER ROAD WATER AND WASTEWATER REPLACEMENT PROJECT			
NO.	DATE	REVISION	BY



## WATER AND WASTEWATER CONSTRUCTION NOTES

1. ALL RESTORATION AND REPLACEMENT OF EXISTING IMPROVEMENTS WITHIN WATER AND WASTEWATER EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF AUSTIN STANDARD SPECIFICATION REQUIREMENTS.
2. CONSTRUCTION OPERATIONS SHALL BE CONDUCTED IN SUCH A MANNER AS TO PROTECT ROADWAY FACILITIES AT ALL TIMES.

## CONSTRUCTION PHASING

1. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL SUBMIT A DETAILED PROJECT CONSTRUCTION SCHEDULE IN EITHER MICROSOFT PROJECT OR SURE TRACK THAT DEMONSTRATES COMPLIANCE WITH THE TRAFFIC CONTROL PLAN AND THE PROPOSED CONSTRUCTION SEQUENCING.
2. PROJECT SEQUENCING SHALL BE IN ACCORDANCE WITH CITY OF AUSTIN STANDARD NOTES AND DETAILS: TREE PROTECTION AND ENVIRONMENTAL NOTES IN THIS PLAN SET, PROJECT SEQUENCING NOTES.

## GENERAL CONSTRUCTION NOTES

1. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE DESIGN ENGINEER FOR THE ADEQUACY OF THE WORK.
2. CONTRACTOR TO PROVIDE DUST CONTROL DURING CONSTRUCTION. ANY DAMAGE TO EXISTING PAVEMENT OR IMPROVEMENTS ON PROPERTY ADJACENT TO THE CONSTRUCTION AREA SHALL BE RESTORED BY THE CONTRACTOR TO PRE-CONSTRUCTION CONDITION.
3. WORK IS PERMITTED FROM 8AM TO 5PM, MONDAYS THROUGH FRIDAYS.
4. ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE STATE STATUTES AND U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS (O.S.H.A.). COPIES OF O.S.H.A STANDARDS MAY BE PURCHASED FROM THE U.S. GOVERNMENT PRINTING OFFICE. INFORMATION AND RELATED MATERIALS MAY BE OBTAINED FROM O.S.H.A. @ 611 EAST 6TH STREET. RPP, 303 AUSTIN, TEXAS.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION WITH OTHER CONTRACTORS AND UTILITIES IN THE VICINITY OF THIS PROJECT. IF THE CONTRACTOR BECOMES AWARE OF POSSIBLE CONFLICT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE PROJECT INSPECTOR AND THE PROJECT MANAGER WITHIN 24 HOURS.
6. CONTRACTOR WILL BE RESPONSIBLE FOR COSTS INCURRED AS A RESULT OF UTILITY RELOCATIONS PERFORMED FOR CONTRACTOR'S CONVENIENCE AND FOR UTILITIES DAMAGED BY THE CONTRACTOR. REPAIRS TO UTILITIES DAMAGED BY CONSTRUCTION SHALL BE AT CONTRACTOR'S EXPENSE.
7. ANY EXISTING SIDEWALKS, CURBS, OR DRIVEWAYS DAMAGED BY THE CONTRACTOR SHALL BE REMOVED AND RESTORED WITH MATERIALS EQUAL TO OR BETTER THAN THE ORIGINAL AND SHALL BE AT THE CONTRACTOR'S EXPENSE UNLESS OTHERWISE NOTED.
8. ANY EXISTING SITE ELEMENTS IMPACTED BY THE CONTRACTOR SHALL BE REMOVED AND RESTORED WITH MATERIALS EQUAL TO OR BETTER THAN THE ORIGINAL AND SHALL BE AT THE CONTRACTOR'S EXPENSE UNLESS OTHERWISE NOTED.
9. EQUIPMENT AND MATERIALS SHALL BE STORED AT LOCATIONS SHOWN ON PLANS AND APPROVED BY THE OWNER'S REPRESENTATIVE.
10. UTILITY SERVICES SHALL BE MAINTAINED TO RESIDENCES AND BUSINESSES AT ALL TIMES. BEFORE DISCONNECTING ANY WATER OR WASTEWATER LINE, THE CONTRACTOR MUST NOTIFY THE CITY IN WRITING REQUESTING APPROVAL AND PROVIDE A DETAILED PLAN AT LEAST 48 HOURS IN ADVANCE, DESCRIBING AN ALTERNATE MEANS OF WATER OR WASTEWATER CONVEYANCE FOR THE INTERRUPTED SECTION.
11. ANY EXISTING IMPROVEMENTS, INCLUDING DRAINAGE FACILITIES, DISTURBED BY CONSTRUCTION SHALL BE RESTORED BY THE CONTRACTOR AT HIS / HER EXPENSE TO A CONDITION EQUAL TO OR BETTER THAN PRECONSTRUCTION CONDITION.
12. ANY PORTION OF THIS PROJECT WHICH IS IMPROPERLY PLACED AND / OR CONFLICTS WITH ANY ROADWAY STRUCTURE SHALL BE REMOVED AND CORRECTLY PLACED. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL ASSOCIATED COSTS.
13. ALL ELEVATIONS ARE BASED ON USGS DATUM. HORIZONTAL DATUM IS TEXAS STATE PLANE COORDINATE SYSTEM. SEE PLANS FOR LOCATION OF BENCHMARKS.
14. SURVEY WAS COMPLETED BY MALDONADO-BURKETT INTELLIGENT TRANSPORTATION SYSTEMS, LLP ON JANUARY 17, 2018.
15. CONTRACTOR IS PERMITTED TO STORE FUEL ON SITE FOR THE SOLE PURPOSE OF OPERATING AND MAINTAINING THE TEMPORARY FLOW MANAGEMENT SYSTEM. THE CONTRACTOR SHALL UTILIZE TEMPORARY E/S CONTROLS, SECONDARY CONTAINMENT, AND SPILL PREVENTION FOR FUEL STORAGE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND CITY OF AUSTIN REQUIREMENTS. THESE ITEMS SHALL BE APPROVED BY THE GPP COORDINATOR.

## NOTES FOR CONSTRUCTION STAGING AREA

1. ALL CONSTRUCTION ACTIVITIES, INCLUDING MATERIAL STORAGE AND STAGING AREA, SHALL BE LOCATED WITHIN THE LIMITS OF CONSTRUCTION AS INDICATED ON THE DRAWINGS. ANY ADDITIONAL AREAS REQUIRED FOR CONSTRUCTION AT THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. REFER TO CITY OF AUSTIN STANDARD NOTES AND DETAILS: TREE PROTECTION AND ENVIRONMENTAL NOTES IN THIS PLAN SET, FOR FURTHER REQUIREMENTS.

## TEMPORARY SPOILS AREA NOTES

1. NO SPOILS STORAGE IS ALLOWED WITHIN A CRITICAL WATER QUALITY ZONE OR 100-YEAR FLOOD PLAIN.
2. LOCATION, SIZE, HEIGHT, CAPACITY AND DURATION OF TEMPORARY SPOILS AREAS SHALL BE DETERMINED BY THE CONTRACTOR PRIOR TO THE PRE CONSTRUCTION MEETING. CONTRACTOR SHALL HAVE PROPOSED LOCATIONS APPROVED BY OWNER'S REPRESENTATIVE AND CITY'S GENERAL PERMIT COORDINATOR WITHIN LIMITS OF CONSTRUCTION.
3. SPOILS ADJACENT TO TRENCHES SHALL BE USED FOR BACKFILL IMMEDIATELY UPON COMPLETION OF THE PIPE INSTALLATION AND ANY EXCESS BE REMOVED TO THE TEMPORARY SPOILS AREA DAILY.
4. SPOILS IN THE STOCKPILE AREAS SHALL HAVE SIDE SLOPES THAT DO NOT EXCEED 3:1. A SLOPE OF 1:1 IS ACCEPTABLE AS LIMITED BY AVAILABLE SPACE. POSITION SILT FENCE AT TOE OF SLOPE AS DICTATED BY SPACE REQUIREMENTS. CONTRACTOR TO COVER ALL SPOILS WITH A TARP TO RESTRICT SEDIMENT TRANSPORT DURING A RAIN EVENT. CONTRACTOR TO PROVIDE E/S CONTROLS IN ADDITION TO TARP.
5. ALL AREAS SHALL BE RESTORED TO ORIGINAL GRADE (AS IT EXISTED PRIOR TO CONSTRUCTION), UNLESS OTHERWISE INDICATED ON THE DRAWINGS.

## SEQUENCING OF CONSTRUCTION

THE SEQUENCE OF CONSTRUCTION IS INTENDED TO DEMONSTRATE A CONSTRUCTION APPROACH THAT MAINTAINS SANITARY SEWER SERVICE AND MINIMIZES IMPACTS. THIS SEQUENCE OF CONSTRUCTION DOES NOT IDENTIFY ALL CONSTRUCTION ITEMS OR STEPS, NOR IS THE ENGINEER RESPONSIBLE FOR THE ACTUAL CONSTRUCTION SEQUENCING UTILIZED. CONTRACTOR IS TO DEVELOP A DETAILED CONSTRUCTION SEQUENCING PLAN AND CONSTRUCTION SCHEDULE FOR THE PROJECT.

PRIOR TO COMMENCING SITE WORK, CONTRACTOR SHALL PERFORM THE FOLLOWING:

1. CONTRACTOR SHALL CONTACT RESIDENT PROJECT REPRESENTATIVE (RPR) AND CITY 48 HOURS PRIOR TO BEGINNING ANY WORK.
2. CONTRACTOR SHALL MARK LIMITS OF CONSTRUCTION BY FLAGGED LATHES OR SILT FENCE WHERE APPLICABLE.
3. CONTRACTOR SHALL ATTEND OFFICE PRECONSTRUCTION CONFERENCE WITH THE OWNER, GENERAL PERMIT PROGRAM COORDINATOR AND RPR. INCLUDE REPRESENTATIVES FROM COA AND UTILITY AS APPROPRIATE.
4. CONTRACTOR SHALL INSTALL TEMPORARY EROSION CONTROL MEASURES AND TREE PROTECTION PRIOR TO CLEARING, GRUBBING, GRADING, EXCAVATING, ETC. AS INDICATED ON THE PLANS IN ACCORDANCE WITH THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL. NOTIFY GENERAL PERMIT PROGRAM COORDINATOR AND RPR PRIOR TO INSTALLATION.
5. CONTRACTOR SHALL SUBMIT A PLAN FOR KEEPING EXISTING FACILITIES IN OPERATION WHILE CONSTRUCTING PROPOSED FACILITIES. EXISTING FACILITY ACTIVITIES SHALL NOT CEASE DURING CONSTRUCTION. CONTRACTOR SHALL DEFINE ANY PLANNED PHASING OF CONSTRUCTION ACTIVITY. ADDITIONAL PRE-CONFERENCES (FOR PHASES) MAY BE REQUIRED BY THE GENERAL PERMIT OFFICE. PHASING, IF PROPOSED BY THE CONTRACTOR, WILL BE DELINEATED AND THE INFORMATION PROVIDED TO THE GENERAL PERMIT OFFICE PRIOR TO THE FIELD PRECONSTRUCTION MEETING.
6. CONTRACTOR SHALL CONDUCT A SITE SURVEY AND LOCATE ALL EXISTING UTILITIES WITHIN LIMITS OF CONSTRUCTION INCLUDING, BUT NOT LIMITED TO, EXISTING MANHOLES, PIPELINES, DUCT BANKS, AND PIPE CASING.

DURING SITE WORK, CONTRACTOR SHALL PERFORM THE FOLLOWING:

1. CONTRACTOR SHALL CONSTRUCT NEW SEWER MAIN, MANHOLES AND SEWER SERVICES PRIOR TO CONSTRUCTION OF WATER MAINS AND WATER SERVICES. INSTALL SEWER MAIN IN DOWNSTREAM TO UPSTREAM DIRECTION. PRIOR TO STARTING CONSTRUCTION, CONTRACTOR SHALL VERIFY TIE-IN LOCATIONS AND ELEVATIONS WITH EXISTING SEWER MAINS AND NOTIFY ENGINEER OF ANY DISCREPANCIES WITH PLAN ELEVATIONS.
2. CONTRACTOR SHALL BEGIN CONSTRUCTION OF WATER MAIN AND WATER SERVICES AFTER NEW SEWER MAIN, MANHOLES AND SEWER SERVICES ARE INSTALLED. CONTRACTOR SHALL VERIFY LOCATION AND ELEVATIONS OF EXISTING WATER MAIN TIE-INS PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY DISCREPANCIES WITH PLANS.

## GENERAL PERMIT PROGRAM GENERAL CONSTRUCTION NOTES

1. CONTRACTOR MUST OBTAIN UTILITY EXCAVATION PERMITS, FOR EACH RIGHT-OF-WAY EXCAVATED, FROM THE CITY OF AUSTIN PUBLICS WORKS DEPARTMENT - CONSTRUCTION INSPECTION DIVISION (512-974-7265) PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL PROVIDE A ONE CALL CENTER CONFIRMATION NUMBER PRIOR TO ANY DIRECTIONAL DRILLING OR BORING, CONTRACTOR MUST CONTACT THE CITY OF AUSTIN PUBLICS WORKS DEPARTMENT - CONSTRUCTION INSPECTION DIVISION (512-974-7161) TO SCHEDULE A MANDATORY PRE-BORE INSPECTION.
2. CITY OF AUSTIN UTILITIES REQUIRE A MINIMUM 2' (FOOT) VERTICAL AND 5' (FOOT) HORIZONTAL SEPARATION DISTANCE, MEASURED FROM OUTER DIAMETER TO OUTER DIAMETER. ANY VARIANCE FROM CITY UTILITIES MUST BE OBTAINED IN WRITING AND SUBMITTED TO THE CITY OF AUSTIN PUBLICS WORKS DEPARTMENT - CONSTRUCTION INSPECTION DIVISION (512-974-7265). ALL STREET TRENCH REPAIRS ARE TO BE DONE IN ACCORDANCE WITH CITY OF AUSTIN STANDARD DETAILS FROM THE 1100 SERIES.
3. ALL TRENCH REPAIR IN UNFINISHED SURFACES TO BE DONE IN ACCORDANCE WITH CITY OF AUSTIN STANDARD DETAIL 510S-5.
4. FOR EXCAVATION WITHIN 100 FEET OF A MOONLIGHT TOWER OR WITHIN 100 FEET OF A GUY WIRE SUPPORTING A MOONLIGHT TOWER, EXCAVATION OR CONSTRUCTION PLANS AND SEQUENCING INFORMATION THAT DEMONSTRATES THAT THE MOONLIGHT TOWER WILL BE ADEQUATELY PROTECTED FROM DAMAGE DURING EXCAVATION OR CONSTRUCTION MUST BE SUBMITTED TO CITY OF AUSTIN - PUBLIC WORKS DEPARTMENT - AUSTIN ENERGY (512-505-7611).
5. VERIFY THE LOCATION OF UNDERGROUND UTILITIES AT LEAST 100' (FEET) IN ADVANCE OF ALL PROPOSED UTILITY CROSSINGS, AND ALSO LOCATIONS WHERE THE PROPOSED FACILITIES ARE DEPICTED TO RUN PARALLEL TO AND WITHIN FIVE FEET OF EXISTING FACILITIES.
6. CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS AT 974-7161 PRIOR TO THE INSTALLATION OF ANY FACILITY WITHIN A DRAINAGE EASEMENT OR STREET R.O.W. THE METHODS OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S R.O.W. MUST BE APPROVED PRIOR TO START OF THE BACKFILL OPERATION.
7. FOR SLOPES OR TRENCHES MORE THAN FIVE (5) FEET IN DEPTH, A NOTE MUST BE ADDED TO THE GENERAL CONSTRUCTION NOTES STATING THAT: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD SPECIFICATIONS ITEM NO. 509 AND APPLICATION REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)". COPIES OF THE OSHA STANDARDS MAY BE PURCHASED FROM THE U.S. GOVERNMENT PRINTING OFFICE, INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 E. 6TH STREET, AUSTIN, TEXAS.

## DEVELOPER INFORMATION

OWNER: \_\_\_\_\_ ADDRESS: \_\_\_\_\_


PHONE: \_\_\_\_\_

NAME \_\_\_\_\_ PHONE \_\_\_\_\_

OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS

NAME \_\_\_\_\_ PHONE \_\_\_\_\_ PERSON \_\_\_\_\_  
OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE.

NAME \_\_\_\_\_ PHONE \_\_\_\_\_ PERSON \_\_\_\_\_  
OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

[illegible]DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B.SCROGGINS

CHECKED BY: H. STEED

## SHEET TITLE

CIVIL

## GENERAL NOTES


SCALE: AS SHOWN

SHEET           G-03            
3                      OF                      55










LAYOUT FOR BRYKER DRIVE

NEW MILLING AND OVERLAY LIMITS


NOTES


- 1. MILLING AND OVERLAY LIMITS TO SERVE AS APPROX. LIMITS OF CONSTRUCTION.
- 2. DO NOT PAVE OVER ANY AUSTIN WATER SURFACE FEATURES (MANHOLES COVERS, VALVES, ETC.) WHICH WOULD HINDER LONG-TREM OPERATIONS & MAINTENANCE OF SAID FEATURES.
- 3. COMPLETE 11,500 SQ. YDS. OF MILLING AND OVERLAY AS PER CITY OF AUSTIN STANDARD SPECIFICATION ITEM NO 315S.

REVIEWED  
December 02, 2020  
Austin Water




LAYOUT FOR W 34TH STREET






FIRM REGISTRATION NUMBER: F-533



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

CIVIL


SITE MILLING AND  
OVERLAY LAYOUT  
PLAN

SCALE: AS SHOWN


SHEET **G-05**

5 OF 55






LAYOUT FOR BRYKER DRIVE




LAYOUT FOR W 34TH STREET

REVIEWED  
December 02, 2020  
*Amy Wilkins*  
Austin Water  
Type Name Here


60 0 60 120  
SCALE: 1" = 60'



FIRM REGISTRATION NUMBER: F-533



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

SHEET TITLE

CIVIL

EXISTING UTILITIES  
ABANDONMENT  
LAYOUT PLAN

SCALE: AS SHOWN

SHEET **G-06**

6 OF 55



Table 1


MAXIMUM RECOMMENDED  
DIAMETRIC DEFLECTION

PVC Pressure Pipes	5%
PVC Sewer / Drain Pipes	7½%
PVC Electrical Conduits	5%

(JM Eagle, 2009)

Figure 1

## FLEXIBLE PIPE DEFLECTION



(JM Eagle, 2009)

## Iowa Equation

$$\% \frac{\Delta Y}{D} = \frac{k(T_L W_E + W_L + W_S)}{0149PS + 0.061E'} (100)$$

where:

- $\% \frac{\Delta Y}{D}$  = vertical deflection, %
- $\Delta Y$  = vertical deflection or change in diameter, in.
- $D$  = diameter, in.
- $k$  = bedding constant, use 0.1
- $T_L$  = time-lag factor, use 1.0, 1.5, or 2.0
- $W_E$  = earth load pressure, psi
- $W_L$  = live load pressure, psi
- $W_S$  = surcharge pressure, psi
- $PS$  = pipe stiffness, lbf/in./in.
- $E'$  = modulus of soil reaction, psi

(AWWA M23, 2020)

## Selection of Factors

- $D = 8$  in. (see drawings)
- $k = 0.1$
- $T_L = 1.5$  (conservative estimate)
- $W_E = 24$  psi  
Calculated using AWWA M23 Equation 4-5

Prism Load:  $W_p = HwD$  (lb/lin ft)

(Eq 4-3)

where:

- $P$  = pressure caused by soil weight at depth H, lb/ft<sup>2</sup>
- $w$  = unit weight of soil, lb/ft<sup>3</sup>
- $H$  = depth at which soil pressure is desired, ft
- $D$  = pipe diameter

The prism load can be converted to lb/in<sup>2</sup> for  $W_E$  as follows:

$$\text{Earth Load Pressure: } W_E = \frac{W_p}{144}$$

(Eq 4-5)

(AWWA M23, 2020)

- $H = 3.6$  ft (see drawings)
- $w = 120$  pcf (see Geotechnical Report)
- $D = 8$  in (see drawings)

- $W_L = 6.36$  psi  
Interpolated from AWWA M23 Table 4-2; assuming HS20 maximum live load

- $W_S = 0$  psi  
NO SURCHARGE LOADS

- $PS = 815$  lbf/in/in  
From AWWA M23 Table 4-3  
PVC DR14 pipe (see drawings)

- $E' = 6,000$  psi  
From AWWA M23 Table 4-4  
Class 1 Crushed Rock Pipe Bedding (Specification 510.3)

$$\% \Delta Y = \frac{0.1 ( 1.5 \times 24.1 + 6.36 + 0 )}{(0.149 \times 815 + 0.061 \times 6000 )} \times 100 = 0.85\%$$

Table 4-2 AASHTO HS20, HS25, and Cooper E80 live loads (psi)

AASHTO Live Loads		HS20		HS25		Cooper E80 Live Loads			
Depth		$W_L$		$W_L$		Depth		$W_L$	
ft	m	psi	kPa	psi	kPa	ft	m	psi	kPa
2	0.6	13.4	92	16.8	116	3	0.9	16	110
2.5	0.8	9.7	67	12.2	84	4	1.2	14.1	97
3	0.9	7.4	51	9.2	63	5	1.5	12.2	84
4	1.2	4.7	32	5.9	41	6	1.8	10.5	72
5	1.5	3.4	23	4.2	29	7	2.1	9	62
6	1.8	2.6	18	3.2	22	8	2.4	7.7	53
8	2.4	1.6	11	2	14	10	3.0	5.7	39
10	3.0	1.1	7.6	1.4	10	12	3.7	4.6	32
12	3.7	0.8	5.5	1.1	7.6	15	4.6	3.4	23
15	4.6	0.6	4.1	0.7	4.8	20	6.1	2.2	15
20	6.1	0.4	2.8	0.5	3.4	25	7.6	1.5	10
28	8.5	0.2	1.4	0.25	1.8	30	9.1	1.1	7.6
40	12.2	0.1	0.7	0.1	0.7	40	12.2	0.6	4.1

Note: Cooper E80 as defined by AREMA (American Railway Engineering and Maintenance-of-Way Association) in its Manual of Railway Engineering.

(AWWA M23, 2020)

Table 4-3 PVC and PVCO pipe stiffness

PVC Stiffness		PVCO Stiffness	
Min. $E = 400,000$ psi		Min. $E = 500,000$ psi	
DR	lbfin./in.	Pressure Class	lbfin./in.
51	14	PR160, IPS	24
41	28	PR200, IPS	48
32.5	57	PR250, IPS	98
27.5	96	PR150, CIOD	21
26	115	PR200, CIOD	48
25	129	PR250, CIOD	98
21	224	PC165, CIOD	28
18	364	PC235, CIOD	81
14	815	PC305, CIOD	178

(AWWA M23, 2020)

Table 4-4 E' values, psi

Soil Group (USCS)	Uncompacted	Compacted	
		Moderate 85-90% compaction	High ≥95% compaction
Class I Crushed rock	1,000	6,000	
Class II GW GP SW SP	500	2,000	4,000
Class III GC GM SC SM CL ML CL ML	200	1,000	2,500
Class IV CL ML	100	400	1,500
Class V CH MH OH OL Pt	Do not use		

USCS: Unified Soil Classification System

Notes:

- Soil Classification in accordance with ASTM D2487.
- Percent compaction is based on ASTM D698.
- For information on soil classes, see Table 4-1.
- $E'$  values only valid for cover depths of 50 ft or less. The values must be used with a prism load. These values are only valid for estimating initial deflections. A time-lag factor must be used to predict long-term deflections.

(AWWA M23, 2020)

## References

Tables and equations referenced are from the following sources:

"Depth of Burial for PVC Pipe" JMEagle. (2017,12 3). Retrieved from [www.jmeagle.com/sites/default/files/TB06DepthofBurialforPVC.pdf](http://www.jmeagle.com/sites/default/files/TB06DepthofBurialforPVC.pdf)

"PVC Pipe – Design and Installation" AWWA Manual of Water Supply Practices – Third Edition (2020).

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITYBRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE:	NOVEMBER 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	J. RECK
DRAWN BY:	B.SCROGGINS
CHECKED BY:	H.STEED

SHEET TITLE


CIVIL

DEPTH OF COVER  
CALCULATION DETAILS


SCALE: AS SHOWN

SHEET G-07

7 OF 55










- GENERAL NOTES:**
- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
  - ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
  - UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

- WATER NOTES:**
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
  - CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
  - NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
  - THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
  - CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
  - REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
  - INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
  - WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.






FIRM REGISTRATION NUMBER: F-533



11-12-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

SHEET TITLE

CIVIL


PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 0+00 TO 4+00

SCALE: AS SHOWN

SHEET C-01

8 OF 55








GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

WATER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
- REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
- INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
- WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE

CIVIL


PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 4+00 TO 8+00

SCALE: AS SHOWN

SHEET C-02



9 OF 55







- GENERAL NOTES:**
- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
  - ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
  - UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

- WATER NOTES:**
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
  - CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
  - NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
  - THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
  - CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
  - REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
  - INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
  - WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.






FIRM REGISTRATION NUMBER: F-533



11-12-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

SHEET TITLE: CIVIL


PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 8+00 TO 12+00

SCALE: AS SHOWN

SHEET C-03



10 OF 55





File: I:\ACAD\PROJ\02908105-COA\2-SHEETS\04-C-CIVIL Date: 9/10/2020 4:19 PM Last Saved By: NCANDELAS







GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

WATER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
- REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
- INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
- WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED



SHEET TITLE

CIVIL  
PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 12+00 TO 16+60

SCALE: AS SHOWN

SHEET C-04  
11 OF 55






### GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

### WATER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
- REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
- INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
- WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY


DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE  
CIVIL

PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 19+75 TO 24+00

SCALE: AS SHOWN  
SHEET C-05  
12 OF 55







GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

WATER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
- REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
- INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
- WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED



SHEET TITLE  
CIVIL

PROPOSED 8-INCH WATER  
LINE PLAN AND PROFILE  
STA. 24+00 TO 27+88.97

SCALE: AS SHOWN

SHEET C-06  
13 OF 55





# PLAN AND PROFILE FOR W. 32ND STREET

GENERAL NOTES:


1. COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
2. ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
3. UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

WATER NOTES:

1. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING WATER SERVICE TO EXISTING WATER MAINS AND SERVICES AT ALL TIMES.
2. CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING WATER, SEWER OR GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
3. NO EXISTING VALVES TO BE OPERATED BY THE CONTRACTOR WITHOUT DIRECTION FROM CITY OF AUSTIN WATER UTILITY PERSONNEL.
4. THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
5. CONTRACTOR SHALL EXPOSE ALL PIPELINE AND UTILITY CROSSINGS PRIOR TO ORDERING MATERIALS. NOTIFY THE ENGINEER IMMEDIATELY IF A CONFLICT IS FOUND AND RECORD ALL NEEDED GRADE ADJUSTMENTS IN THE PROJECT SET OF AS-BUILT DRAWINGS.
6. REPLACE WATER SERVICE AND METER ASSEMBLY PER DETAIL 520-AW-02 ON SHT. SD-02 (INCLUDING METER, METER BOX, SERVICE, LINE, TAP AND APPURTENANCES).
7. INSTALL NEW FIRE ASSEMBLY PER DETAIL 511-AW 02 ON SHT. SD-01 (INCLUDING ALL APPURTENANCES)
8. WATER SERVICES LINE ELEVATIONS MAY BE ADJUSTED AS NEEDED IN THE FIELD.

- 

- 



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

[illegible]

DATE:	NOVEMBER 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	J. RECK
DRAWN BY:	B. SCROGGINS
CHECKED BY:	H. STEED

SHEET TITLE	
-------------	--



CIVIL

# PROPOSED 8-INCH WATER LINE PLAN AND PROFILE STA 29+75 TO 31+50

SCALE: AS SHOWN


SHEET C-07  
14 OF 55







- GENERAL NOTES:**
- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
  - ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
  - UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

- SEWER NOTES:**
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING SANITARY SEWER SERVICE TO EXISTING RESIDENCES.
  - CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING SEWER, WATER, AND GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
  - THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
  - ALL WASTEWATER SERVICES SHALL BE INSTALLED WITH MINIMUM 1% SLOPE AND A TWO-WAY CLEANOUT AT THE PROPERTY LINE.
  - LATERAL CONNECTIONS CROSSING WATER LINE TO BE CONSTRUCTED OF 150 PSI PRESSURE-RATED PIPING AND IN CEMENT STABILIZED SAND.
  - MANHOLES TO BE WATER TIGHT AND INSTALLED IN ACCORDANCE WITH DETAIL 506S-6.






FIRM REGISTRATION NUMBER: F-533



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

SHEET TITLE

CIVIL


PROPOSED 8-INCH  
WASTEWATER LINE  
PLAN AND PROFILE  
STA. 0+75 TO 5+00

SCALE: AS SHOWN

SHEET C-08

15 OF 55





GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

SEWER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING SANITARY SEWER SERVICE TO EXISTING RESIDENCES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING SEWER, WATER, AND GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- ALL WASTEWATER SERVICES SHALL BE INSTALLED WITH MINIMUM 1% SLOPE AND A TWO-WAY CLEANOUT AT THE PROPERTY LINE.
- LATERAL CONNECTIONS CROSSING WATER LINE TO BE CONSTRUCTED OF 150 PSI PRESSURE-RATED PIPING AND IN CEMENT STABILIZED SAND.
- MANHOLES TO BE WATER TIGHT AND INSTALLED IN ACCORDANCE WITH DETAIL 506S-6.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED





SHEET TITLE

CIVIL


PROPOSED 8-INCH  
WASTEWATER LINE  
PLAN AND PROFILE  
STA. 5+00 TO 9+00

SCALE: AS SHOWN

SHEET C-09  
16 OF 55










GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

SEWER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING SANITARY SEWER SERVICE TO EXISTING RESIDENCES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING SEWER, WATER, AND GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- ALL WASTEWATER SERVICES SHALL BE INSTALLED WITH MINIMUM 1% SLOPE AND A TWO-WAY CLEANOUT AT THE PROPERTY LINE.
- LATERAL CONNECTIONS CROSSING WATER LINE TO BE CONSTRUCTED OF 150 PSI PRESSURE-RATED PIPING AND IN CEMENT STABILIZED SAND.
- MANHOLES TO BE WATER TIGHT AND INSTALLED IN ACCORDANCE WITH DETAIL 506S-6.

REVIEWED  
December 02, 2020  
Austin Water  
Type Name Here



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY


DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE  
CIVIL

PROPOSED 8-INCH  
WASTEWATER LINE  
PLAN AND PROFILE  
STA. 9+00 TO 13+00

SCALE: AS SHOWN  
SHEET C-10  
17 OF 55








GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E6=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

SEWER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING SANITARY SEWER SERVICE TO EXISTING RESIDENCES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING SEWER, WATER, AND GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- ALL WASTEWATER SERVICES SHALL BE INSTALLED WITH MINIMUM 1% SLOPE AND A TWO-WAY CLEANOUT AT THE PROPERTY LINE.
- LATERAL CONNECTIONS CROSSING WATER LINE TO BE CONSTRUCTED OF 150 PSI PRESSURE-RATED PIPING AND IN CEMENT STABILIZED SAND.
- MANHOLES TO BE WATER TIGHT AND INSTALLED IN ACCORDANCE WITH DETAIL 506S-6.



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE



CIVIL

PROPOSED 8-INCH  
WASTEWATER LINE  
PLAN AND PROFILE  
STA. 13+00 TO 17+85

SCALE: AS SHOWN

SHEET C-11  
18 OF 55







GENERAL NOTES:

- COORDINATES SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE (4203), NAD83(CORS). PROJECT REFERENCE POINTS ARE CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING COORDINATE VALUES OF N=10,085,028.06, E=3,112,116.43 AND "H-24-1001" HAVING COORDINATE VALUES OF N=10,080,581.36, E=3,107,208.51. COMBINED SCALE FACTOR = 1.0001.
- ELEVATIONS AND CONTOURS SHOWN HEREON ARE BASED ON CITY OF AUSTIN MONUMENT "J-25-1001" (CB58) HAVING AN ELEVATION OF 579.64 FEET. NAVD88 VERTICAL DATUM.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON VISIBLE SURFACE FEATURES, PAINT MARKS AND RECORD UTILITY PLANS PREPARED BY OTHERS. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR FIELD VERIFYING THE LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES. PRIOR TO EXCAVATION OR DRILLING "ONE-CALL" TEXAS 811 SHOULD BE CONTACTED.

SEWER NOTES:

- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING SANITARY SEWER SERVICE TO EXISTING RESIDENCES.
- CONTRACTOR SHALL PROTECT AND REPAIR (IF DAMAGED) ANY EXISTING SEWER, WATER, AND GAS SERVICE LATERALS AND IRRIGATION SHOWN OR NOT SHOWN ON THE PLANS.
- THE UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND FOR INFORMATION ONLY. THE CONTRACTOR SHALL LOCATE ALL EXISTING UTILITIES (HORIZONTAL AND VERTICAL), AND SHALL BE RESPONSIBLE FOR DAMAGE TO THE UTILITIES CAUSED BY THE CONTRACTOR'S OPERATION.
- ALL WASTEWATER SERVICES SHALL BE INSTALLED WITH MINIMUM 1% SLOPE AND A TWO-WAY CLEANOUT AT THE PROPERTY LINE.
- LATERAL CONNECTIONS CROSSING WATER LINE TO BE CONSTRUCTED OF 150 PSI PRESSURE-RATED PIPING AND IN CEMENT STABILIZED SAND.
- MANHOLES TO BE WATER TIGHT AND INSTALLED IN ACCORDANCE WITH DETAIL 506S-6.

REVIEWED  
December 02, 2020  
Austin Water  
Type Name Here



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE

CIVIL

PROPOSED 8-INCH  
WASTEWATER LINE  
PLAN AND PROFILE  
STA. 19+75 TO 24+00

SCALE: AS SHOWN


SHEET C-12

19 OF 55









CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 12 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	MAM
DRAWN BY:	NAS
CHECKED BY:	MAM


SHEET TITLE  
LANDSCAPE ARCHITECTURE

EROSION AND  
SEDIMENT  
CONTROL PLAN

SCALE: 1" = 100'-0"

SHEET L1.00  
21 OF 55





**LEGEND:**

- LOC LIMIT OF CONSTRUCTION BOUNDARY
- SF SILT FENCE
- EXISTING TREE TO REMAIN  
CONTRACTOR SHALL PROVIDE TREE PROTECTION FENCING AS SHOWN PRIOR TO START OF CONSTRUCTION
- EXISTING TREE OUTSIDE LIMIT OF CONSTRUCTION
- TREE PROTECTION FENCING



08/12/2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 12 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	MAM
DRAWN BY:	NAS
CHECKED BY:	MAM

SHEET TITLE  
LANDSCAPE ARCHITECTURE

**EROSION AND  
SEDIMENT  
CONTROL PLAN**

SITE PLAN RELEASE

Sheet 22 of 54

FILE NUMBER: \_\_\_\_\_

EXPIRATION DATE: \_\_\_\_\_

CASE MANAGER: \_\_\_\_\_

APPLICATION DATE: \_\_\_\_\_

APPROVED ADMINISTRATIVELY ON: \_\_\_\_\_

APPROVED BY PLANNING COMMISSION ON: \_\_\_\_\_

APPROVED BY CITY COUNCIL ON: \_\_\_\_\_

Under Section \_\_\_\_\_ of Chapter \_\_\_\_\_ of the Austin City Code.

Signing For Director, Development Services Department


DATE OF RELEASE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_


Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_

Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_

RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA. INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.







**LEGEND:**

- LOC LIMIT OF CONSTRUCTION BOUNDARY
- SF SILT FENCE
- EXISTING TREE TO REMAIN  
CONTRACTOR SHALL PROVIDE TREE PROTECTION FENCING  
AS SHOWN PRIOR TO START OF CONSTRUCTION
- EXISTING TREE OUTSIDE LIMIT OF CONSTRUCTION
- TREE PROTECTION FENCING



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



**BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT**

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 12 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	MAM
DRAWN BY:	NAS
CHECKED BY:	MAM

SHEET TITLE  
**LANDSCAPE ARCHITECTURE**

**EROSION AND  
SEDIMENT  
CONTROL PLAN**

SITE PLAN RELEASE

Sheet 23 of 54

FILE NUMBER: \_\_\_\_\_

EXPIRATION DATE: \_\_\_\_\_

CASE MANAGER: \_\_\_\_\_

APPLICATION DATE: \_\_\_\_\_

APPROVED ADMINISTRATIVELY ON: \_\_\_\_\_

APPROVED BY PLANNING COMMISSION ON: \_\_\_\_\_

APPROVED BY CITY COUNCIL ON: \_\_\_\_\_

Under Section \_\_\_\_\_ of Chapter \_\_\_\_\_ of the Austin City Code.

Signing For Director, Development Services Department

DATE OF RELEASE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1 \_\_\_\_\_ Correction 1

Rev. 2 \_\_\_\_\_ Correction 2

Rev. 3 \_\_\_\_\_ Correction 3

RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION

OF ALL DATA. INFORMATION AND CALCULATIONS SUPPLIED BY THE

APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR

THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER

SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR

CODE COMPLIANCE BY CITY ENGINEERS.



APPENDIX P-1 - EROSION CONTROL NOTES

1. The contractor shall install erosion/sedimentation controls, tree/natural area protective fencing, and conduct "Pre-Construction" tree fertilization (if applicable) prior to any site preparation work (clearing, grubbing or excavation).
2. The placement of erosion/sedimentation controls shall be in accordance with the Environmental Criteria Manual and the approved Erosion and Sedimentation Control Plan. The COA ESC Plan shall be consulted and used as the basis for a TPDES required SWPPP. If a SWPPP is required, it shall be available for review by the City of Austin Environmental Inspector at all times during construction, including at the Pre-Construction meeting. The checklist below contains the basic elements that shall be reviewed for permit approval by COA EV Plan Reviewers as well as COA EV Inspectors.

- Plan sheets submitted to the City of Austin MUST show the following:
- ✓ Direction of flow during grading operations.
  - ✓ Location, description, and calculations for off-site flow diversion structures.
  - ✓ Areas that will not be disturbed; natural features to be preserved.
  - ✓ Delineation of contributing drainage area to each proposed BMP (e.g., silt fence, sediment basin, etc.).
  - ✓ Location and type of E&S BMPs for each phase of disturbance.
  - ✓ Calculations for BMPs as required.
  - ✓ Location and description of temporary stabilization measures.
  - ✓ Location of on-site spoils, description of handling and disposal of borrow materials, and description of on-site permanent spoils disposal areas, including size, depth of fill and revegetation procedures.
  - ✓ Describe sequence of construction as it pertains to ESC including the following elements:

- Installation sequences of controls (e.g. perimeter controls, then sediment basins, then temporary stabilization, then permanent, etc.)
- Project phasing if required (LOC greater than 25 acres)
- Sequence of grading operations and notation of temporary stabilization measures to be used
- Schedule for converting temporary basins to permanent WQ controls
- Schedule for removal of temporary controls
- Anticipated maintenance schedule for temporary controls
- Categorize each BMP under one of the following areas of BMP activity as described below:

- 2.1 Minimize disturbed area and protect natural features and soil
- 2.2 Control Stormwater flowing onto and through the project
- 2.3 Stabilize Soils
- 2.4 Protect Slopes
- 2.5 Protect Storm Drain Inlets
- 2.6 Establish Perimeter Controls and Sediment Barriers
- 2.7 Retain Sediment On-Site and Control Dewatering Practices
- 2.8 Establish Stabilized Construction Exits
- 2.9 Any Additional BMPs
- Note the location of each BMP on your site map(s).
- For any structural BMPs, you should provide design specifications and details and refer to them.
- For more information, see City of Austin Environmental Criteria Manual 1.4.
3. The Placement of tree/natural area protective fencing shall be in accordance with the City of Austin standard Notes for Tree and Natural Area Protection and the approved Grading/Tree and Natural Area Plan.
4. A pre-construction conference shall be held on-site with the contractor, design Engineer/permit applicant and Environmental Inspector after installation of the erosion/sedimentation controls, tree/natural area protection measures and "Pre-Construction" tree fertilization (if applicable) prior to beginning any site preparation work. The owner or owner's representative shall notify the Development Services Department, 512-974-2278 or by email at environmental.inspections@austintexas.gov, at least three days prior to the meeting date. COA approved ESC Plan and TPDES SWPPP (if required) must be reviewed by COA EV Inspector at this time.
5. Any major variation in materials or locations of controls or fences from those shown on the approved plans will require a revision and must be approved by the reviewing Engineer, Environmental Specialist or City Arborist as appropriate. Major revisions must be approved by authorized COA staff. Minor changes to be made as field revisions to the Erosion and Sedimentation Control Plan may be required by the Environmental Inspector during the course of construction to correct control inadequacies.
6. The contractor is required to provide a certified inspector that is either a licensed engineer (or person directly supervised by the licensed engineer) or Certified Professional in Erosion and Sediment Control (CPESC or CPESC - IT), Certified Erosion, Sediment, and Stormwater - Inspector (CESSWI or CESSWI - IT) or Certified Inspector of Sedimentation and Erosion Controls (CISEC or CISEC - IT) certification to inspect the controls and fences at weekly or bi-weekly intervals and after one-half (½) inch or greater rainfall events to insure that they are functioning properly. The person(s) responsible for maintenance of controls and fences shall immediately make any necessary repairs to damaged areas. Silt accumulation at controls must be removed when the depth reaches six (6) inches or one-third (⅓) of the installed height of the control whichever is less.
7. Prior to final acceptance by the City, haul roads and roadway crossings constructed for temporary contractor access must be removed, accumulated sediment removed from the roadway and the area restored to the original grade and revegetated. All land clearing debris shall be disposed of in approved spoil disposal sites.
8. All work must stop if a void in the rock substrate is discovered which is; one square foot in total area; blows air from within the substrate and/or consistently receives water during any rain event. At this time it is the responsibility of the Project Manager to immediately contact a City of Austin Environmental Inspector for further investigation.
9. Temporary and Permanent Erosion Control: All disturbed areas shall be restored as noted below:
- A. All disturbed areas to be revegetated are required to place a minimum of six (6) inches of topsoil [see Standard Specification Item No. 601S.3(A)]. Do not add topsoil within the critical root zone of existing trees.
- Topsoil salvaged from the existing site is encouraged for use, but it should meet the standards set forth in 601S.
- An owner/engineer may propose use of onsite salvaged topsoil which does not meet the criteria of Standard Specification 601S by providing a soil analysis and a written statement from a qualified professional in soils, landscape architecture, or agronomy indicating the onsite topsoil will provide an equivalent growth media and specifying what, if any, soil amendments are required.
- Soil amendments shall be worked into the existing onsite topsoil with a disc or tiller to create a well-blended material.
- The vegetative stabilization of areas disturbed by construction shall be as follows:

TEMPORARY VEGETATIVE STABILIZATION:

- 10.From September 15 to March 1, seeding shall be with or include a cool season cover crop: (Western Wheatgrass ( *Pascopyrum smithii* ) at 5.6 pounds per acre, Oats ( *Avena sativa* ) at 4.0 pounds per acre, Cereal Rye Grain ( *Secale cereale* ) at 45 pounds per acre. Contractor must ensure that any seed application requiring a cool season cover crop does not utilize annual ryegrass ( *Lolium multiflorum* ) or perennial ryegrass ( *Lolium perenne* ). Cool season cover crops are not permanent erosion control.
- 11.From March 2 to September 14, seeding shall be with hulled Bermuda at a rate of 45 pounds per acre or a native plant seed mix conforming to Item 604S or 609S.
- A. Fertilizer shall be applied only if warranted by a soil test and shall conform to Item No. 608S, Fertilizer. Fertilization should not occur when rainfall is expected or during slow plant growth or dormancy. Chemical fertilizer may not be applied in the Critical Water Quality Zone.
- B. Hydromulch shall comply with Table 1, below.
- C. Temporary erosion control shall be acceptable when the grass has grown at least 1½ inches high with a minimum of 95% total coverage so that all areas of a site that rely on vegetation for temporary stabilization are uniformly vegetated, and provided there are no bare spots larger than 10 square feet.
- D. When required, native plant seeding shall comply with requirements of the City of Austin Environmental Criteria Manual, and Standard Specification 604S or 609S.

Table 1: Hydromulching for Temporary Vegetative Stabilization

Material	Description	Longevity	Typical Applications	Application Rates
100% or any blend of wood, cellulose, straw, and/or cotton plant material (except no mulch shall exceed 30% paper)	70% or greater	0—3 months	Moderate slopes; from flat to 3:1	1,500 to 2,000 lbs per acre
	Wood/Straw 30% or less Paper or Natural Fibers			

PERMANENT VEGETATIVE STABILIZATION:


12. From September 15 to March 1, seeding is considered to be temporary stabilization only. If cool season cover crops exist where permanent vegetative stabilization is desired, the grasses shall be mowed to a height of less than one-half (½) inch and the area shall be re-seeded in accordance with Table 2 below. Alternatively, the cool season cover crop can be mixed with Bermudagrass or native seed and installed together, understanding that germination of warm-season seed typically requires soil temperatures of 60 to 70 degrees.
13. From March 2 to September 14, seeding shall be with hulled Bermuda at a rate of 45 pounds per acre with a purity of 95% and a minimum pure live seed (PLS) of 0.83. Bermuda grass is a warm season grass and is considered permanent erosion control. Permanent vegetative stabilization can also be accomplished with a native plant seed mix conforming to Item 604S or 609S.
- A. Fertilizer use shall follow the recommendation of a soil test. See Item 606S, Fertilizer. Applications of fertilizer (and pesticide) on City-owned and managed property requires the yearly submittal of a Pesticide and Fertilizer Application Record, along with a current copy of the applicator's license. For current copy of the record template contact the City of Austin's IPM Coordinator.
- B. Hydromulch shall comply with Table 2, below.
- C. Water the seeded areas immediately after installation to achieve germination and a healthy stand of plants that can ultimately survive without supplemental water. Apply the water uniformly to the planted areas without causing displacement or erosion of the materials or soil. Maintain the seeded in a moist condition favorable for plant growth. All watering shall comply with City Code Chapter 6-4 (Water Conservation), at rates and frequencies determined by a licensed irrigator or other qualified professional, and as allowed by the Austin Water Utility and current water restrictions and water conservation initiatives.
- D. Permanent erosion control shall be acceptable when the grass has grown at least 1½ inches high with a minimum of 95 percent for the non-native mix, and 95 percent coverage for the native mix so that all areas of a site that rely on vegetation for stability must be uniformly vegetated, and provided there are no bare spots larger than 10 square feet.
- E. When required, native plant seeding shall comply with requirements of the City of Austin Environmental Criteria Manual, Items 604S and 609S.

Table 2: Hydromulching for Permanent Vegetative Stabilization


Material	Description	Longevity	Typical Applications	Application Rates
Bonded Fiber Matrix (BFM)	80% Organic defibrated fibers			
10% Tackifier	6 months	On slopes up to 2:1 and erosive soil conditions	2,500 to 4,000 lbs per acre (see manufacturers recommendations)	
Fiber Reinforced Matrix (FRM)	65% Organic defibrated fibers 25% Reinforcing Fibers or less 10% Tackifier	Up to 12 months	On slopes up to 1:1 and erosive soil conditions	3,000 to 4,500 lbs per acre (see manufacturers recommendations)

14. The contractor shall not dispose of surplus excavated material from the site without notifying the Development Services Department at 512-974-2278 at least 48 hours prior with the location and a copy of the permit issued to receive the material.


Source: Rule No. R161-15.13, 1-4-2016 ; Rule No. R161-17.03 , 3-2-2017.




CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	MULCH SOCK
RECORD COPY SIGNED BY MORGAN BYARS 08/24/2010 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. STANDARD NO. 648S-1




SILT FENCE PLACEMENT FOR PERIMETER CONTROL  
ECM FIGURE 1.4.5.G.3  
NOT TO SCALE




CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	SILT FENCE
RECORD COPY SIGNED BY MORGAN BYARS 08/01/2011 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. STANDARD NO. 642S-1



SILT FENCE J-HOOK DETAIL  
ECM FIGURE 1.4.5.G.4  
NOT TO SCALE



CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	TRIANGULAR SEDIMENT FILTER DIKE
RECORD COPY SIGNED BY J. PATRICK MURPHY 3/27/00 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. STANDARD NO. 628S



STABILIZED CONSTRUCTION ENTRANCE  
ECM FIGURE 1.4.5.G.5  
NOT TO SCALE



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 12 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	MAM
DRAWN BY:	NAS
CHECKED BY:	MAM

SHEET TITLE  
LANDSCAPE ARCHITECTURE

EROSION AND  
SEDIMENT  
CONTROL DETAILS

FILE NUMBER: \_\_\_\_\_ SITE PLAN RELEASE Sheet 24 of 54  
CASE MANAGER: \_\_\_\_\_ EXPIRATION DATE: \_\_\_\_\_  
APPROVED ADMINISTRATIVELY ON: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
APPROVED BY PLANNING COMMISSION ON: \_\_\_\_\_  
APPROVED BY CITY COUNCIL ON: \_\_\_\_\_  
Under Section \_\_\_\_\_ of Chapter \_\_\_\_\_ of the Austin City Code.



Signing For Director, Development Services Department

DATE OF RELEASE: \_\_\_\_\_ ZONING: \_\_\_\_\_  
Rev. 1 \_\_\_\_\_ Correction 1  
Rev. 2 \_\_\_\_\_ Correction 2  
Rev. 3 \_\_\_\_\_ Correction 3

RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.

SHEET **L1.10**  
24 OF 55





08/12/2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

[illegible]

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 12 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	MAM
DRAWN BY:	NAS
CHECKED BY:	MAM

SHEET TITLE
LANDSCAPE ARCHITECTURE

## EROSION AND SEDIMENT CONTROL DETAILS

SHEET   L1.11    
25 OF 55

SITE PLAN RELEASE

Sheet 26 of 54

FILE NUMBER: \_\_\_\_\_ EXPIRATION DATE: \_\_\_\_\_

CASE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_

APPROVED ADMINISTRATIVELY ON: \_\_\_\_\_

APPROVED BY PLANNING COMMISSION ON: \_\_\_\_\_

APPROVED BY CITY COUNCIL ON: \_\_\_\_\_

Under Section \_\_\_\_\_ of Chapter \_\_\_\_\_ of the Austin City Code.

Signing For Director, Development Services Department

DATE OF RELEASE: \_\_\_\_\_ ZONING: \_\_\_\_\_


Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_

Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_

Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_

RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION  
OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE  
APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR  
THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER  
SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR  
CODE COMPLIANCE BY CITY ENGINEERS.





SPEED LIMITS:  
35 MPH – 35TH  
30 MPH – 30TH  
25 MPH – BRYKER, JEFFERSON, 34TH, BEVERLY,  
OAKMONT, 31ST, 32ND, 33RD

PARKING NOTE:  
POST "NO PARKING" SIGNS ON BOTH SIDES OF  
STREET TO BE CLOSED 48 HOURS PRIOR TO  
CONSTRUCTION WORK ON A BLOCK BY BLOCK  
BASIS.

TRAFFIC CONTROL PLAN LEGEND

INTERSECTIONS – USE 3-WAY OR 4-WAY FLAGGER SET-UP PER DETAILS, SHEET TC-22

INTERSECTIONS – USE FULL CLOSURE PER DETAILS, SHEET TC-02

DETOUR REQUIRED

NO

DETOUR REQUIRED

YES

FULL CLOSURE – USE STREET DETOUR BOTH DIRECTIONS PER STD. DETAIL 804S-2 (6 OF 8)

SINGLE LANE CLOSURE – USE COLLECTOR/RESIDENTIAL STREET FLAGGING OPERATIONS PER STD. DETAIL 804S-2 (1 OF 8).

DETOUR REQUIRED

YES

DETOUR REQUIRED

NO

SCALE IN FEET

FIRM REGISTRATION NUMBER: F-533

CIVIL ENGINEERING | PROGRAM MANAGEMENT | CONSTRUCTION MANAGEMENT  
7908 Cameron Road | Austin, TX 78754 | REG. NO. F-003572  
Main: 512.836.2388 | Fax: 512.836.4515

Michael Meriwether  
08-21-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY

BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:

ARCADIS U.S., INC.

DATE:

AUGUST 2020

PROJECT NO.:

02908105.0000

DESIGNED BY:

M. Meriwether

DRAWN BY:

J. Willig

CHECKED BY:

M. Meriwether

SHEET TITLE

TRAFFIC CONTROL

MASTER TRAFFIC  
CONTROL PLAN

SCALE:

1" = 200'

SHEET



TC-01

26 OF 55









LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

BRYKER FROM  
30TH TO 31ST  
DETOUR

SCALE:  
1" = 100'

SHEET  
TC-03  
28 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE

TRAFFIC CONTROL



31ST - BRYKER  
INTERSECTION  
DETOUR

SCALE: 1" = 100'

SHEET TC-04

29 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

BRYKER FROM  
31ST TO 32ND  
DETOUR

SCALE:  
1" = 100'

SHEET  
TC-05  
30 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

1. ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
2. SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
3. ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
4. NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
5. INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
6. PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
7. CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY





BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE
TRAFFIC CONTROL
32ND - BRYKER INTERSECTION DETOUR
SCALE:
1" = 100'
SHEET
TC-06
31 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

32ND FROM  
BRYKER TO  
BEVERLY

SCALE:  
1" = 100'

SHEET  
TC-07  
32 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

1. ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
2. SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
3. ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
4. NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
5. INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
6. PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
7. CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY





BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE	
TRAFFIC CONTROL	
BRYKER FROM 32ND TO 33RD DETOUR	
SCALE:	1" = 100'
SHEET	TC-08
33	OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

BRYKER FROM  
33RD TO 34TH  
DETOUR

SCALE:  
1" = 100'

SHEET  
TC-09  
34 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

1. ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
2. SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
3. ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
4. NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
5. INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
6. PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
7. CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

34TH FROM  
OAKMONT TO  
BEVERLY DETOUR

SCALE:  
1" = 100'

SHEET  
TC-10  
35 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

1. ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
2. SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
3. ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
4. NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
5. INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
6. PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
7. CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



Michael Meriwether  
08-21-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE
TRAFFIC CONTROL

BEVERLY - 34TH  
INTERSECTION  
DETOUR

SCALE:	1" = 100'
--------	-----------

SHEET	TC-11
36	OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

1. ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
2. SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
3. ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
4. NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
5. INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
6. PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
7. CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether



SHEET TITLE  
TRAFFIC CONTROL

34TH FROM  
BEVERLY TO  
BRYKER DETOUR

SCALE: 1" = 100'

SHEET TC-12  
37 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY





BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE	
TRAFFIC CONTROL	
BRYKER - 34TH INTERSECTION DETOUR	
SCALE:	1" = 100'
SHEET	TC-13
38	OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY





BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE
TRAFFIC CONTROL
34TH FROM BRYKER TO JEFFERSON DETOUR
SCALE:
1" = 100'
SHEET
TC-14
39 OF 55





LEGEND

- SIGN
- TYPE III BARRICADE
- WORK ZONE
- CHANNELIZING DEVICES

NOTES:

- ALL TRAFFIC CONTROL DEVICES TO MOVE WITH WORK AREA.
- SPEED LIMITS FOR ALL CITY STREETS ARE SHOWN ON SHEET TC-01.
- ROLLING CLOSURE OF WORK AREA LIMITED TO 300 L.F. AT A TIME WITH EXCAVATION LIMITED TO 100 L.F.
- NOTIFY RESIDENTS 48 HOURS PRIOR TO CLOSURE.
- INSTALL "NO PARKING" SIGNS ON BOTH SIDES OF STREET 48 HOURS PRIOR TO CLOSURE.
- PUBLIC NOTIFICATION MUST OCCUR PRIOR TO CONSTRUCTION AND ACCOMMODATIONS FOR AFFECTED DRIVEWAYS MUST BE MADE. ALL EXCAVATIONS BLOCKING DRIVEWAY ACCESS MUST BE BACKFILLED/PLATED AFTER WORK HOURS.
- CONTRACTOR SHALL MAINTAIN A 5' MINIMUM WIDTH SHARED USE PATH THROUGH THE WORK AREA. PATH SHALL BE SEPARATED FROM WORK AREA WITH PORTABLE SAFETY FENCING PER STANDARD DETAIL 804S-4 (1 OF 9).



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether


SHEET TITLE  
TRAFFIC CONTROL

JEFFERSON - 34TH  
INTERSECTION  
DETOUR

SCALE:  
1" = 100'

SHEET  
TC-15  
40 OF 55





NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether


SHEET TITLE
TRAFFIC CONTROL

TRAFFIC CONTROL  
DETAILS

SCALE:	AS SHOWN
--------	----------

SHEET	TC-16
41	OF 55





- 3
- 4
1. ALL SETUPS SHALL BE IN ACCORDANCE WITH THE CURRENT ADDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND THE CITY OF AUSTIN TRANSPORTATION CRITERIA MANUAL.
2. TO DETERMINE APPROPRIATE DEVICES AND SIGN SIZES TO BE USED, REFER TO STANDARD 804S-3 SHEETS 5, 6 AND 7 OF 11.
3. FOR INTERMEDIATE-TERM SITUATIONS, WHEN IT IS NOT FEASIBLE TO REMOVE AND RESTORE PAVEMENT MARKINGS, THE CHANNELIZATION MUST BE MADE DOMINANT BY USING A VERY CLOSE DEVICE SPACING. THIS IS ESPECIALLY IMPORTANT IN LOCATIONS OF CONFLICTING INFORMATION, SUCH AS WHERE TRAFFIC IS DIRECTED OVER A DOUBLE YELLOW CENTERLINE. IN SUCH LOCATIONS, A MAXIMUM CHANNELIZING DEVICE SPACING OF 3 m (10') IS REQUIRED.
4. FOR LONG TERM STATIONARY WORK, ALL CONFLICTING PAVEMENT MARKINGS MUST BE REMOVED AND CENTERLINE STRIPING PROVIDED WHERE TWO WAY TRAFFIC IS IN ADJACENT LANES.
5. FOR TEMPORARY PAVEMENT MARKING REQUIREMENTS SEE STANDARD 804S-3.
6. FOR ONE-WAY AND MULTI-LANE ROADWAYS THE "LANE BLOCKED" SIGN MAY BE USED IN LIEU OF THE "LANE CLOSED AHEAD" SIGN. THE NUMBER OF DIGITS ON THE SIGN SHALL NOT BE GREATER THAN THE NUMBER OF LANES PRESENT ON THE ROADWAY. THE "X" SHALL BE PLACED UNDER THE NUMBER OF LANE(S) BLOCKED.
7. FOR FLAGGING OPERATION REQUIREMENTS SEE STANDARD 804S-2.
8. CONTRACTOR SHALL PROVIDE SIDEWALK CLOSURES, CROSSWALK CLOSURES OR WALKWAY BYPASS WHEREVER PEDESTRIAN MOVEMENTS ARE AFFECTED BY CONSTRUCTION ACTIVITIES. ALL SIDEWALKS AND CROSSWALKS SHALL BE ACCESSIBLE. WHEN CONTRACTOR IS NOT WORKING UNLESS APPROVED BY THE TRANSPORTATION DIVISION.
9. FOR EXCAVATION PROTECTION AND SAFETY FENCE REQUIREMENTS SEE STANDARD 804S-4.
10. THE USE OF ARROW DISPLAYS ARE REQUIRED ON ALL LANE CLOSURES. THE CONTRACTOR SHALL PROVIDE ONE (1) STAND-BY UNIT IN GOOD WORKING CONDITION AT THE JOB SITE, READY FOR USE IF THE OPERATION REQUIRES 24 HOUR A DAY LANE CLOSURE SET-UPS.
- CITY OF AUSTIN  
DEPARTMENT OF PUBLIC WORKS
- RECORD COPY SIGNED BY KERY JUAREZ
- 01/04/11  
ADOPTED
- THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.
- STANDARD NO. 804S-1  
8 OF 9
- GENERAL NOTES

5

6

Typical Transition Lengths and Suggested Maximum Spacing of Devices

Speed KMPH	Posted Speed MPH	Formula	Minimum Desirable Taper Lengths (L) Meters (Feet)			Suggested Max. Device Spacing		Suggested Sign Spacing Meters (Feet)
			3.0(10) Offset Meters (feet)	3.3(11) Offset Meters (feet)	3.6(12) Offset Meters (feet)	On a taper Meters (feet)	On a tangent Meters (feet)	
50	30	L=WS/2	45 (150)	50 (165)	55 (180)	9 (30)	15-30 (50-75)	40 (120)
55	35	60	65 (205)	70 (225)	75 (245)	10 (35)	25-25 (70-90)	50 (160)
65	40		80 (265)	90 (295)	100 (320)	12 (40)	25-30 (80-100)	75 (240)
70	45		130 (450)	150 (495)	165 (540)	13 (45)	25-30 (90-110)	100 (320)
80	50		150 (500)	165 (550)	180 (600)	15 (50)	30-35 (100-125)	120 (400)
90	55	L=WS	165 (550)	180 (600)	200 (660)	16 (55)	35-40 (110-140)	150 (500)
95	60		180 (600)	200 (660)	220 (720)	18 (60)	40-45 (120-150)	180 (600)
105	65		195 (650)	215 (710)	235 (770)	19 (65)	40-50 (130-165)	210 (700)
115	70		215 (700)	235 (770)	255 (840)	21 (70)	45-55 (140-175)	240 (800)

LEGEND

- Channelizing devices
- Trailer mounted flashing arrow board
- Flagger

CITY OF AUSTIN  
DEPARTMENT OF PUBLIC WORKS


RECORD COPY SIGNED BY KERY JUAREZ

01/04/11  
ADOPTED


THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.

STANDARD NO. 804S-1  
9 OF 9

DEVICE SPACING



- Notes for Standard 804S-1, 10 of 13
- Bike Lane Closure and Bike Lane Closure with Adjacent Traffic Lane Closure; 35 mph or Less
- Definition:
- Bicycle Lane:** A portion of a roadway that has been designated by signs and pavement markings for preferential or exclusive use by bicycles.
- Standard:
1. This standard detail shall apply on roadways with a posted speed of 35mph or less.
- Guidance:
2. Bicycle lane transitions should be no less than 40 ft.
- Standard:
3. A bike lane closure shall be used anytime work activity encroaches into a portion of or closes a bicycle lane on a roadway with a posted speed limit of 35 mph or less.
4. The adjacent traffic lane closure shall be used only on roadways where traffic flow is in multiple traffic lanes in the same direction.
5. Advance warning signs for a bicycle lane closure shall consist of a Road Work/Utility Work Ahead sign a Bike Lane Closed sign with a Shoulder Road (CW16-1P) sign. Additional signs shall be placed when the adjacent traffic lane is closed.
6. Vertical mounting height and lateral placement shall be as specified in 804S-5, 6 & 7 of 13.
7. Warning sign size shall be as shown for conventional roads in 804S-5, 6 & 7 of 13.
8. A type-I barricade shall be set at the end of the bike lane transition area to physically close the bike lane to prevent bicyclist's entry into the work zone.
9. A Bike Lane (R3-17) sign and a Closed (R3-17cP) plate shall be mounted directly behind the type-I Barricade in the bike lane.
- Guidance:
10. Where work activity is expected to block a traffic lane of a roadway with a bicycle lane, a Bike Lane Closure should be set prior to the traffic lane closure.
- CITY OF AUSTIN  
AUSTIN TRANSPORTATION DEPARTMENT, ROW MANAGEMENT DIVISION
- RECORD COPY SIGNED BY LEE AUSTIN
- 6/22/2016  
ADOPTED
- THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.
- STANDARD NO. 804S-1  
11 OF 13
- BIKE LANE CLOSURE 35 MPH OR LESS



NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE

TRAFFIC CONTROL

TRAFFIC CONTROL  
DETAILS

SCALE: AS SHOWN

SHEET TC-17  
42 OF 55



















E

D

C

B

A





- ALL TRAFFIC CONTROL DEVICES, SIGNS, BARRICADES AND WARNING SIGNS SHALL BE FURNISHED, PLACED, CONSTRUCTED AND MAINTAINED IN THE APPROPRIATE TYPES AND SIZES AND FLAGGER OPERATIONS EXECUTED IN ACCORDANCE WITH THE CURRENT EDITION OF THE TEXAS MANUAL ON UNIFORM CONTROL DEVICES (TMUTCD), THE CITY OF AUSTIN STANDARD SPECIFICATIONS SERIES 800 AND THE CITY OF AUSTIN TRANSPORTATION CRITERIA MANUAL, OR AS DIRECTED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE. IF A CONFLICT ARISES THEN THE CITY OF AUSTIN TRANSPORTATION CRITERIA MANUAL SHALL CONTROL UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.
- THE CONTRACTOR SHALL NOTIFY THE TRANSPORTATION DIVISION OF THE DEPARTMENT OF PUBLIC WORKS AT 974-7024 NO LATER THAN THE MONDAY OF THE WEEK DURING WHICH THE CONTRACTOR INTENDS TO SET UP BARRICADES TO START CONSTRUCTION.
- PROPOSED CONSTRUCTION TRAFFIC MOVEMENTS MAY REQUIRE EXISTING SIGNAL HEADS TO BE RELOCATED. THE CITY OF AUSTIN WILL REVIEW SIGNAL HEAD LOCATIONS DURING CONSTRUCTION AND PERFORM THE REQUIRED ADJUSTMENTS. THE CONTRACTOR SHALL CONTACT THE TRANSPORTATION DIVISION OF THE DEPARTMENT OF PUBLIC WORKS AT 974-7024, THREE (3) DAYS PRIOR TO PLACEMENT ANY TRAFFIC CONTROLS WHICH MAY REQUIRE SIGNAL HEAD ADJUSTMENTS/RELOCATION.
- THE CONTRACTOR SHALL PROVIDE ONE (1) FULL-TIME OFF-DUTY, UNIFORMED AUSTIN POLICE DEPARTMENT CERTIFIED PEACE OFFICER AND ONE (1) VEHICLE OF THE TYPE APPROVED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE FOR TEMPORARY LANE CLOSURES WHEN UNDERSEALING, MILLING, PAVING AND WHEN WORKING IN INTERSECTIONS AS PART OF THE TRAFFIC CONTROL OPERATIONS. THE PEACE OFFICER SHALL BE ABLE TO SHOW PROOF OF CERTIFICATION BY THE TEXAS COMMISSION ON LAW ENFORCEMENT OFFICER STANDARDS. THE CONTRACTOR SHALL NOTIFY ALL OTHER GOVERNMENTAL AGENCIES WHOSE RIGHTS-OF-WAY ARE AFFECTED BY HIS WORK ACTIVITIES. THE CONTRACTOR SHALL PROVIDE ANY ADDITIONAL TRAFFIC CONTROL DEVICES THAT THEY MAY NEED.
- THE CONTRACTOR SHALL MAINTAIN ONE (1) DUST-FREE LANE OF TRAFFIC IN EACH DIRECTION AT ALL TIMES, UNLESS OTHERWISE NOTED IN THE DRAWINGS OR APPROVED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.
- THERE SHALL BE A MINIMUM OF THREE (3) METERS (10 FEET) CLEAR WIDTH FOR EACH LANE OF TRAFFIC IN CHANNELIZED AREAS, UNLESS OTHERWISE NOTED ON THE DRAWINGS OR APPROVED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.
- THE CONTRACTOR SHALL MAINTAIN DRIVEWAY ACCESS AT ALL TIMES. IF ACCESS CANNOT BE MAINTAINED, THE CONTRACTOR WITH THE APPROVAL OF THE ENGINEER OR DESIGNATED REPRESENTATIVE SHALL PROVIDE AT LEAST 24 HOUR WRITTEN NOTICE OF LIMITED ACCESS TO AFFECTED PROPERTY OWNERS. THE CONTRACTOR SHALL PROVIDE BUSINESS ACCESS SIGNS AS NEEDED TO INFORM DRIVERS OF THE LOCATIONS OF ALL DRIVEWAYS.
- TEMPORARY LANE CLOSURES IN THE CENTRAL BUSINESS DISTRICT (CBD) OR ON ARTERIAL STREETS SHALL NOT BE PERMITTED DURING THE HOURS OF 7 AM TO 9 AM AND 4 PM TO 6 PM MONDAY THROUGH FRIDAY UNLESS PRIOR APPROVAL HAS BEEN OBTAINED FROM THE TRANSPORTATION DIVISION.
- TRAFFIC CONTROL SHOWN ON STANDARD DETAILS IS TYPICAL. ADDITIONAL SIGNING AND/OR BARRICADING, AS WELL AS TEMPORARY PAVEMENT MARKINGS AND OBLITERATION/RESTORATION OF EXISTING PAVEMENT MARKINGS, MAY BE REQUIRED DEPENDING ON FIELD CONDITIONS. FIELD ADJUSTMENTS TO TRAFFIC CONTROLS WILL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED SUBSIDIARY TO ITEM NO. 803S "BARRICADES, SIGNS AND TRAFFIC HANDLING".
- THE CONTRACTOR SHALL DESIGNATE A COMPETENT PERSON FOR TRAFFIC CONTROL. THE COMPETENT PERSON SHALL MAKE INSPECTIONS OF THE TRAFFIC CONTROL DEVICES AT LEAST TWO (2) TIMES A DAY (ONCE AT THE BEGINNING OF THE DAY AND ONCE AT THE END OF THE DAY), INCLUDING NON-WORKING DAYS, ENSURING THAT ALL DEVICES ARE IN THEIR PROPER PLACE AND ARE IN WORKING ORDER.
- ALL DEVICES SHALL BE MADE USING MATERIALS LISTED ON THE TxDOT APPROVED PRODUCTS LIST.

CITY OF AUSTIN DEPARTMENT OF PUBLIC WORKS		GENERAL TRAFFIC CONTROL NOTES	
RECORD COPY SIGNED BY SAM ANGOORI	01/04/10 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. <b>804S-5</b> 12 OF 13

- ALL PERSONS WORKING WITHIN THE RIGHT-OF-WAY SHALL WEAR A BRIGHTLY COLORED SAFETY VEST. FOR NIGHTTIME WORK THE VEST SHALL BE RETROREFLECTIVE.
  - WHEN AN INTERSECTION IS CLOSED FOR CONSTRUCTION, THE CONTRACTOR SHALL PROCEED WITH CONSTRUCTION IN SUCH A MANNER THAT THE CLOSURE TIME IS MINIMIZED.
  - THE CONTRACTOR SHALL NOTIFY THE CAPITAL METRO DISPATCHER AT 385-4295 ONE (1) WEEK PRIOR TO LANE CLOSURES ADJACENT TO BUS STOPS.
- DURATION OF WORK  
WORK DURATION IS A MAJOR FACTOR IN DETERMINING THE NUMBER AND TYPES OF DEVICES USED IN TEMPORARY TRAFFIC ZONES. THE FIVE (5) CATEGORIES OF WORK DURATION AND THEIR TIME AT A LOCATION ARE AS FOLLOWS:
- LONG-TERM STATIONARY-WORK THAT OCCUPIES A LOCATION FOR MORE THAN 3 DAYS.
  - INTERMEDIATE-TERM STATIONARY-WORK THAT OCCUPIES A LOCATION FROM OVERNIGHT TO 3 DAYS.
  - SHORT-TERM STATIONARY-DAYTIME WORK THAT OCCUPIES A LOCATION FROM 1 TO 12 HOURS.
  - SHORT-DURATION WORK THAT OCCUPIES A LOCATION UP TO 1 HOUR.
  - MOBILE-WORK THAT MOVES INTERMITTENTLY OR CONTINUOUSLY.

Typical Transition Lengths and Suggested Maximum Spacing of Devices						
Posted Speed KPH (MPH)	Formula	Minimum Desirable Taper Lengths (L) Meters (Feet)			Suggested Max. Device Spacing	
		3.0(10) Offset Meters (feet)	3.3(11) Offset Meters (feet)	3.6(12) Offset Meters (feet)	On a taper Meters (feet)	On a tangent Meters (feet)
50 (30)	L=WS <sup>2</sup> 60	45 (150)	50 (165)	55 (180)	9 (30)	15-20 (60-75)
55 (35)		65 (205)	70 (225)	75 (245)	10 (35)	25-25 (70-90)
65 (40)		80 (265)	90 (295)	100 (320)	12 (40)	25-30 (80-100)
70 (45)		135 (450)	165 (540)	165 (540)	13 (45)	25-30 (90-110)
80 (50)		150 (500)	165 (550)	180 (600)	15 (50)	30-35 (100-125)
90 (55)	L=WS	165 (550)	185 (605)	200 (660)	16 (55)	35-40 (110-140)
100 (60)		180 (600)	200 (660)	220 (720)	18 (60)	40-45 (120-150)
105 (65)		195 (650)	215 (715)	235 (780)	19 (65)	40-50 (130-165)
115 (70)		215 (700)	235 (770)	255 (840)	21 (70)	45-55 (140-175)

CITY OF AUSTIN DEPARTMENT OF PUBLIC WORKS		GENERAL TRAFFIC CONTROL NOTES	
RECORD COPY SIGNED BY SAM ANGOORI	01/04/10 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. <b>804S-5</b> 13 OF 13



CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether


SHEET TITLE  
**TRAFFIC CONTROL**

**TRAFFIC CONTROL  
DETAILS**

SCALE:  
AS SHOWN

SHEET **TC-22**  
47 OF 55





Michael Meriwether  
12-01-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

COPYRIGHT:	ARCADIS U.S., INC.
DATE:	AUGUST 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	M. Meriwether
DRAWN BY:	J. Willig
CHECKED BY:	M. Meriwether

SHEET TITLE

TRAFFIC CONTROL

TRAFFIC CONTROL  
DETAILS

SCALE: AS SHOWN

SHEET TC-23  
48 OF 55















E

D

C

B

A



FIRM REGISTRATION NUMBER: F-533

12-3-2020

REVIEWED

December 03, 2020

Austin Water

Type Name Here

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY

BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020

PROJECT NO.: 02908105.0000

DESIGNED BY: J. RECK

DRAWN BY: B. SCROGGINS

CHECKED BY: H. STEED

SHEET TITLE

CIVIL

STANDARD DETAILS

SCALE: AS SHOWN

SHEET SD-02

50 OF 55











E

D

C

B

A



NO.	DATE	REVISION	BY

DATE:	NOVEMBER 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	J. RECK
DRAWN BY:	B. SCROGGINS
CHECKED BY:	H. STEED

SHEET TITLE

CIVIL

STANDARD DETAILS


SCALE: AS SHOWN

SHEET SD-03  
51 OF 55










1  
SD-05

# DETAIL



2  
SD-05


DETAIL



3  
SD-05


DETAIL

**REVIEWED**  
December 03, 2020  
*Austin Water*  
Austin Water  
Type Name Here




4  
SD-05

DETAIL




5  
SD-05

# DETAIL




6  
SD-05

DETAIL



7  
SD-05



12-3-2020

CITY OF AUSTIN, TEXAS  
AUSTIN WATER UTILITY



BRYKER ROAD  
WATER AND WASTEWATER  
REPLACEMENT PROJECT

[illegible]

DATE:	NOVEMBER 2020
PROJECT NO.:	02908105.0000
DESIGNED BY:	J. RECK
DRAWN BY:	B. SCROGGINS
CHECKED BY:	H. STEED

SHEET TITLE

CIVIL









## STANDARD DETAILS

SCALE: AS SHOWN

SHEET SD-05  
53 OF 55



E  
D  
C  
B  
A



NO.	DATE	REVISION	BY

DATE: NOVEMBER 2020  
PROJECT NO.: 02908105.0000  
DESIGNED BY: J. RECK  
DRAWN BY: B. SCROGGINS  
CHECKED BY: H. STEED

SHEET TITLE

CIVIL

STANDARD DETAILS

SCALE: AS SHOWN

SHEET SD-06

54 OF 55



