CITY OF AUSTIN, TEXAS ECONOMIC DEVELOPMENT DEPT.

12/22/2020

NOTES:

- CONTRACTOR SHALL NOTIFY THE PUBLIC WORKS DEPARTMENT 24 HOURS PRIOR TO STARTING CONSTRUCTION OR
- 2. CONTRACTOR SHALL CALL "ONE CALL" AT 811 FOR UTILITY LOCATIONS AT LEAST 48 HOURS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET RIGHT OF WAYS.
- 3. THIS PROJECT IS LOCATED WITHIN THE WALLER CREEK WATERSHED (CLASSIFIED AS URBAN) AND SHALL BE DEVELOPED, CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH CHAPTER 25 OF THE CODE OF THE CITY OF
- 4. NO PORTION OF THIS SITE IS LOCATED WITHIN PARKLAND OR LAND USED FOR PARK PURPOSES. (IF SUCH LAND IS INCLUDED, DOCUMENTATION OF PARKS AND RECREATION DEPT APPROVAL IS REQUIRED AT THE TIME OF SUBMITTAL FOR GENERAL PERMIT PROGRAM APPROVAL.)
- 5. NO PORTION OF THIS SITE IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN, PER CITY OF AUSTIN AND FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP(S) NO _____, DATED __
- 6. THIS PROJECT IS NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS DEFINED BY THE CITY OF AUSTIN. THIS PROJECT IS NOT WITHIN THE EDWARDS AQUIFER RECHARGE ZONE AS REGULATED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ).
- 7. THERE ARE NO CRITICAL ENVIRONMENTAL FEATURES WITHIN 150' OF ANY PORTION OF THIS PROJECT. A FIELD INVESTIGATION HAS NOT BEEN PERFORMED AS A PART OF THIS PROJECT. (A FIELD INVESTIGATION HAS NOT BEEN PERFORMED AS A PART OF THIS PROJECT AND IS NOT REQUIRED.)
- 8. THE STANDARD SHEETS INCLUDED IN THIS PLAN SET WERE PROVIDED BY THE GENERAL PERMIT PROGRAM OFFICE FOR USE ON GENERAL PERMIT PROJECTS ONLY. IF ANY MODIFICATIONS TO THE SHEETS WERE MADE, THEY ARE CLEARLY INDICATED ON THE SHEET ITSELF AND IN THE COVER SHEET INDEX.
- ADDITIONAL TRENCH E/S CONTROL: TRIANGULAR SEDIMENT FILTER DIKE WILL BE INSTALLED ACROSS FULL WIDTH OF TRAFFIC CLOSURE AND DOWNSTREAM OF CONSTRUCTION AREA, PERPENDICULAR TO CURB. FILTER DIKE TO FOLLOW ACTIVE CONSTRUCTION. REMOVING AND RE-SETTING FILTER DIKE IS CONSIDERED SUBSIDIARY TO BARRICADES AND TRAFFIC HANDLING.
- 10. PROJECT SCHEDULE MUST BE APPROVED BY THE GENERAL PERMIT PROGRAM (GPP) COORDINATOR. INSTALLATION AND REMOVAL OF TEMPORARY AND PERMANENT EROSION/SEDIMENTATION CONTROLS MUST BE REFLECTED IN THE SCHEDULE, BY STATION NUMBER. GPP INSPECTOR MUST BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE OF
- 11. APPROPRIATE EASEMENTS/APPROVALS MUST BE SECURED AND DOCUMENTED FOR PROJECT AREAS LOCATED OUTSIDE OF RIGHT OF WAYS. NO WORK SHALL BE PERFORMED WITHIN THESE AREAS UNTIL ASSOCIATED RIGHT OF ENTRY HAS BEEN SECURED. ADDITIONALLY, THIS PROJECT WILL NOT BE CONSIDERED COMPLETE UNTIL ALL RECORDED EASEMENT DOCUMENT NUMBERS HAVE BEEN OBTAINED AND SHOWN ON PLANS.
- 12. CONTRACTOR SHALL STAKE ALL PROPOSED SERVICE CONNECTIONS LOCATED WITHIN THE CRITICAL ROOT ZONE OF TREES 8" IN CALIPER AND LARGER AT LEAST 21 CALENDAR DAYS PRIOR TO CONSTRUCTION OF SUCH SERVICES. STAKING SHALL CONSIST OF A LATH WITH NAIL AND PAINT MARKINGS. IN CASES WHERE A STAKE CANNOT BE PLACED WITHOUT DAMAGING PROPERTY, CONTRACTOR MAY USE PAINT ONLY. ONCE STAKING IS COMPLETED, IT IS THE CONTRACTOR'S RESPONSIBILITY TO INFORM THE CITY OF AUSTIN'S CONSTRUCTION INSPECTOR WITHIN TWENTY-FOUR HOURS. THE CITY OF AUSTIN'S CONSTRUCTION INSPECTOR WILL THEN COORDINATE A FIELD REVIEW OF THE SERVICE LOCATIONS WITH THE GENERAL PERMIT PROGRAM COORDINATOR AND PROPERTY OWNERS. SERVICE LINE LOCATIONS MAY BE ADJUSTED BASED ON THE REVIEW AND WILL BE RESTAKED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL SERVICE LINE STAKING SHALL BE MAINTAINED UNTIL THE SERVICE IS INSTALLED.

GENERAL PERMIT PROGRAM APPROVAL DOES NOT CONSTITUTE UTILITY ALIGNMENT/ASSIGNMENT APPROVAL RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY, AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.

GENERAL PERMIT PROGRAM CORRECTIONS RECORD


FOR USE BY GENERAL PERMIT OFFICE ONLY

| NC | DESCRIPTION | BY | CORRECT (C) ADD (D) VOID (V) SHEET NO.'s | TOTAL # SHEETS IN CORRECTION PLAN SET | GENERAL PERMIT PROGRAM APPROVAL | APPROVAL DATE |
|----|-------------|----|--|--|--|------------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |



RED RIVER ENHANCEMENT

SUB PROJECT ID: 7327.053



| WATER PRESSURE ZONE | : LOCATION | | |
|---------------------|------------|------|------|
| LOCATION | MIN. | TYP. | MAX. |
| | | | |
| | | | |

AULCC NUMBER

PROJECT INFORMATION:

STREET ADDRESS: RED RIVER ST. FROM 6TH TO 10TH ST. AUSTIN, TX 78701

CLIENT/SPONSOR: CITY OF AUSTIN

ECONOMIC DEVELOPMENT DEPARTMENT AUSTIN, TX 78701

CONTACT: NICOLE KLEPADLO PHONE: (512) 974-7739 EMAIL: NICOLE.KLEPADLO@austintexas.gov

PROJECT MANAGEMENT:

CITY OF AUSTIN PUBLIC WORKS DEPARTMENT PROJECT MANAGEMENT DIVISION 505 BARTON SPRINGS RD., STE. 900 AUSTIN, TEXAS 78704

CONTACT: JOSE IBARRA, P.E. PHONE: (512) 974-7195 EMAIL: JOSE.IBARRA@austintexas.gov

SUBMITTAL PREPARED BY:



DOCUMENT WAS AUTHORIZED BY

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL



PUBLIC WORKS DEPARTMENT ENGINEERING SERVICES DIVISION 505 BARTON SPRINGS RD., STE. 900 AUSTIN, TEXAS 78704

KEVIN SWEAT, P.E. PHONE: (512) 974-7017 EMAIL: KEVIN.SWEAT@austintexas.gov

APPROVED BY GENERAL PERMIT HOLDER:

FOR GENERAL PERMIT HOLDER

GP-2020-0000.PWD ANNUAL GENERAL PERMIT NUMBER

REVIEWED BY:

[SUBMITTAL DATE] SUBMITTAL DATE

AUSTIN FIRE DEPARTMENT DATE


AUSTIN TRANSPORTATION DEPARTMENT

APPROVAL FOR SITE DEVELOPMENT PERMIT:

GENERAL PERMIT PROGRAM COORDINATOR DEVELOPMENT SERVICES DEPARTMENT GP-2020- .PWD GENERAL PERMIT NUMBER DATE

G001 1 of 46

| | 1 | | |
|---|---|---|--|
| NO. ID DESCRIPTION | | 4_ | |
| 1 G001 COVER SHEET | | | |
| 2 G002 INDEX SHEET | | | |
| 3 G003 LEGEND SHEET | | | |
| 4 G004 GENERAL CONSTRUCTION NOTES | | | |
| 5 G101 PROJECT OVERVIEW PLAN | | | |
| 6 CE001 EROSION AND SEDIMENTATION CONTROL | | | |
| 7 CE002 TREE PROTECTION AND ENVIRONMENTAL NOTES | | | |
| 8 VA101 EXISTING SITE PLAN (SHEET 1 OF 5) | | ▋╙║╎╽ | |
| 9 VA102 EXISTING SITE PLAN (SHEET 2 OF 5) | | | |
| 10 VA103 EXISTING SITE PLAN (SHEET 3 OF 5) | | <u> </u> | |
| 11 VA104 EXISTING SITE PLAN (SHEET 4 OF 5) | | | |
| 12 VA105 EXISTING SITE PLAN (SHEET 5 OF 5) | | N N N N N N N N N N N N N N N N N N N | |
| 13 CD101 DEMOLITION PLAN (SHEET 1 OF 6) | | ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ ~ | TE OF TEXTON |
| 14 CD102 DEMOLITION PLAN (SHEET 2 OF 6) | | | CE OF TEXT |
| 15 CD103 DEMOLITION PLAN (SHEET 3 OF 6) | | | VIN SWEAT |
| 16 CD104 DEMOLITION PLAN (SHEET 4 OF 6) | | P | 92023 CENSE |
| 17 CD105 DEMOLITION PLAN (SHEET 5 OF 6) | | | SONAL ENGLA |
| 18 CD106 DEMOLITION PLAN (SHEET 6 OF 6) | | | |
| 19 CS101 PROPOSED SITE PLAN (SHEET 1 OF 6) | | THE SEAL A | APPEARING ON THIS WAS AUTHORIZED BY EVIN SWEAT LIC. # 92023 |
| 20 CS102 PROPOSED SITE PLAN (SHEET 2 OF 6) | | | |
| 21 CS103 PROPOSED SITE PLAN (SHEET 3 OF 6) | | I CERTIFY THAT COMPLETE, ACC | T THESE DRAWINGS ARE CURATE AND ADEQUATE |
| 22 CS104 PROPOSED SITE PLAN (SHEET 4 OF 6) | | FOR THEIR INCLUDING CONS | CURATE AND ADEQUATE INTENDED PURPOSES STRUCTION, BUT ARE NOT |
| 23 CS105 PROPOSED SITE PLAN (SHEET 5 OF 6) | | AUTHORIZED FOI FORMAL | OR CONSTRUCTION UNTIL L CITY APPROVAL |
| 24 CS106 PROPOSED SITE PLAN (SHEET 6 OF 6) | | | |
| 25 C501 GENERAL CONSTRUCTION DETAILS (SHEET 1 OF 3) | | 1 | |
| 26 C502 GENERAL CONSTRUCTION DETAILS (SHEET 2 OF 3) | | 1 | |
| 27 SHEET GENERAL CONSTRUCTION DETAILS (SHEET 3 OF 3) | | 1 | |
| 28 CM101 PAVEMENT MARKING & SIGNING PLAN (SHEET 1 OF 2) | | 1 | |
| | | _ | |
| 29 CM102 PAVEMENT MARKING & SIGNING PLAN (SHEET 2 OF 2) | | z | |
| 30 CT001 TRAFFIC CONTROL NOTES | | 날의 | |
| 31 CT501 TRAFFIC CONTROL DETAILS (SHEET 1 OF 10) | | | |
| 32 CT502 TRAFFIC CONTROL DETAILS (SHEET 2 OF 10) | | | 上 |
| 33 CT503 TRAFFIC CONTROL DETAILS (SHEET 3 OF 10) | | A A B I | |
| 34 CT504 TRAFFIC CONTROL DETAILS (SHEET 4 OF 10) | | | |
| 35 CT505 TRAFFIC CONTROL DETAILS (SHEET 5 OF 10) | | TY OF AUSTIN, TEXAS C WORKS DEPARTMENT ERING SERVICES DIVISIO | NCEMENT NCEMENT X SHEET |
| 36 CT506 TRAFFIC CONTROL DETAILS (SHEET 6 OF 10) | | | |
| 37 CT507 TRAFFIC CONTROL DETAILS (SHEET 7 OF 10) | | | |
| 38 CT508 TRAFFIC CONTROL DETAILS (SHEET 8 OF 10) | | | RED ENHAN INDEX |
| 39 CT509 TRAFFIC CONTROL DETAILS (SHEET 9 OF 10) | | CITY BLIC NEER | ш — |
| 40 CT510 TRAFFIC CONTROL DETAILS (SHEET 10 OF 10) | | | |
| 41 LI001 LANDSCAPE AND IRRIGATION NOTES | | PU | |
| 42 L101 LANDSCAPE PLAN (SHEET 1 OF 2) | | Ш | |
| 43 L102 LANDSCAPE PLAN (SHEET 2 OF 2) | | | |
| 44 L501 LANDSCAPE DETAILS | | | |
| 45 L601 LANDSCAPE SCHEDULE (SHEET 1 OF 2) | | | |
| 46 L602 LANDSCAPE SCHEDULE (SHEET 2 OF 2) | | | |
| | | | |
| | | | |
| | | | DF AM |
| | | | |
| | | | |
| | | | |
| | | | |
| | | TO UK | ND Fm 169 |
| | | | ا ع ساع س |
| | | NOTES | NAME DATE |
| | | SURVEY BY | , |
| | | DRAWN BY | DS |
| | | DESIGNED BY | Y CN |
| | | CHECKED BY | Y ESD |
| | | REVIEWED BY | |
| | | | |
| | | _ (| (ESD) |
| | | | |
| | | LNGINEER | RING SERVICES |
| | | V Ι V | 1 3 1 U N |
| | | 00.000 | 20 5145 |
| | | GP-202 | 20PWD |
| | | 0000 | 0 = 40 |
| | | G002 | \(\text{OF } \frac{40}{\text{40}} \) |



CITY OF AUSTIN PUBLIC WORKS DEPARTMENT **ENGINEERING SERVICES DIVISION**

GENERAL CONSTRUCTION NOTES:

- 1. THE PROJECT MANUAL CONTAINS IMPORTANT INFORMATION THAT IS NOT REPEATED IN THE PLAN SET. THE CONTRACTOR SHALL KEEP THE PROJECT MANUAL ON SITE AND IMMEDIATELY AVAILABLE TO THOSE PERSONS PERFORMING THE WORK. UPON REQUEST, THE CONTRACTOR SHALL PRESENT THIS COPY OF THE PROJECT MANUAL TO THE CONSTRUCTION INSPECTOR, ENGINEER OR PROJECT MANAGER.
- 2. THE CONTRACTOR WILL NOTIFY THE OWNER'S REPRESENTATIVE FORTY-EIGHT (48) HOURS IN ADVANCE OF BEGINNING ANY CONSTRUCTION IN THE RIGHT OF WAY OR EASEMENTS.
- CONTRACTOR AND SUB-CONTRACTORS MUST BE LICENSED BY THE CITY OF AUSTIN FOR CONDUCTING WORK WITHIN THE STREET RIGHT OF WAY, ALLEYS, OR EASEMENTS.
- 4. CONTRACTOR MUST OBTAIN RIGHT OF WAY EXCAVATION PERMITS, FOR EACH PROJECT LOCATION, FROM ROW MANAGEMENT DIVISION (512-974-7180) PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL PROVIDE A ONE CALL CENTER CONFIRMATION NUMBER BEFORE BEING ISSUED AN EXCAVATION PERMIT. "ONE CALL" PHONE NUMBER: 811.
- PRE-CONSTRUCTION MEETINGS: THERE ARE TWO ENTITIES THAT HOLD PRE-CONSTRUCTION MEETINGS. THESE MEETINGS TYPICALLY DO NOT OCCUR AT THE SAME TIME. FOR PRE-CONSTRUCTION MEETING HELD BY CONSTRUCTION INSPECTION DIVISION, SEE PROJECT MANUAL SECTION 01200; FOR ENVIRONMENTAL PRE-CONSTRUCTION MEETING, SEE ENVIRONMENTAL NOTES.
- THE CONTRACTOR SHALL NOTIFY EACH OF THE FOLLOWING ENTITIES OF THE CONSTRUCTION SCHEDULE AT LEAST TWO WEEKS IN ADVANCE OF PROPOSED CONSTRUCTION OPERATIONS AND PROVIDE PERTINENT INFORMATION ABOUT LANE CLOSURES AND DETOURS.

| AUSTIN FIRE DEPARTMENT | 512-974-0130 |
|------------------------------------|--------------|
| AUSTIN POLICE DEPARTMENT | 512-974-5000 |
| EMERGENCY MEDICAL SERVICES | 512-978-0440 |
| AUSTIN INDEPENDENT SCHOOL DISTRICT | 512-414-9832 |
| CAPITAL METRO TRANSIT AUTHORITY | 512-389-7400 |
| U.S. POSTAL SERVICE | 512-342-1236 |
| UNIVERSITY OF TEXAS | |
| (Facilities Services) | 512-471-4110 |
| (Parking and Trans) | 512-471-7275 |
| (Utilities and Energy Mgmt) | 512-471-1600 |
| (University Police) | 512-471-4441 |
| (Project Mgmt & Const. Svcs) | 512-471-3042 |
| STATE OF TEXAS | |
| | |

DPS TEXAS HWY PATROL (Region 7 Austin Capitol).....512-463-3473


- 7. THE INFORMATION SHOWN ON THESE DRAWINGS INDICATING TYPE AND LOCATION OF SURFACE, SUBSURFACE, AND AERIAL UTILITIES IS NOT GUARANTEED TO BE EXACT OR COMPLETE. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXACT TYPE AND LOCATION OF ALL UTILITIES AFFECTED BY THE CONSTRUCTION IN ORDER TO AVOID DAMAGING THOSE UTILITIES.
- 8. THE CONTRACTOR SHALL COORDINATE WITH OTHER CONTRACTORS AND UTILITIES IN THE VICINITY OF THIS PROJECT. THIS INCLUDES, BUT IS NOT LIMITED TO, GAS, WATER. WASTEWATER ELECTRIC, TELEPHONE, CABLE TELEVISION, PETROLEUM PIPELINES, FIBER OPTIC, STREET, DRAINAGE, AND ANY OTHER WORK OCCURRING IN OR NEAR THE PROJECT SITE. ONCE THE CONTRACTOR BECOMES AWARE OF A POSSIBLE CONFLICT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE OWNER'S REPRESENTATIVE IMMEDIATELY, BUT NO LATER THAN TWENTY-FOUR (24) HOURS AFTER DISCOVERY.
- 9. SHOULD THE CONTRACTOR DAMAGE A UTILITY DURING THE COURSE OF THE WORK, THE CONTRACTOR SHALL IMMEDIATELY ARRANGE FOR REPAIR AND RESTORATION OF THE DAMAGED UTILITY. THE EXPENSE FOR THESE REPAIRS WILL BE AT THE CONTRACTOR'S SOLE EXPENSE.
- 10. ALL EXISTING STRUCTURES, FACILITIES, AND UTILITIES DAMAGED BY CONSTRUCTION SHALL BE REMOVED AND RESTORED WITH MATERIALS EQUAL TO OR BETTER THAN THE ORIGINAL AND TO CONDITIONS EQUAL TO OR BETTER THAN THE ORIGINAL. UNLESS OTHERWISE NOTED IN THE PLANS, THIS WILL NOT BE MEASURED AND PAID FOR DIRECTLY, BUT SHALL BE AT THE CONTRACTOR'S SOLE EXPENSE.
- 11. SLOPES OF ROADWAY CUTS AND EMBANKMENTS DAMAGED BY ANY OPERATION OF THE CONTRACTOR DURING THE EXECUTION OF THIS PROJECT SHALL BE REPAIRED AND RESTORED TO THE ORIGINAL PRE-CONSTRUCTION CONDITION. BACKFILL AND FILL PLACED DURING REMEDIAL GRADING SHALL BE COMPACTED TO AT LEAST 95% COMPACTION AND TO THE SATISFACTION OF THE ENGINEER AND GOVERNING AUTHORITIES.
- 12. GEOTECHNICAL INFORMATION IS PROVIDED IN THE PROJECT MANUAL SECTION 00220.
- 13. SEE PROJECT MANUAL SECTION 01300 FOR RECORD DRAWINGS INFORMATION.


STREET AND BRIDGE SPECIAL NOTE:


ALL DAMAGE CAUSED DIRECTLY OR INDIRECTLY TO THE STREET SURFACE, SIDEWALK, DRIVEWAY, CURB & GUTTER, OR SUBSURFACE OUTSIDE OF THE PAVEMENT CUT AREA SHALL BE REGARDED AS A PART OF THE STREET CUT REPAIR. THIS INCLUDES ANY SCRAPES, GOUGES, CUTS, CRACKING, DEPRESSIONS, AND/OR ANY OTHER DAMAGE CAUSED BY THE CONTRACTOR DURING THE EXECUTION OF THE WORK. THESE REPAIR AREAS WILL BE INCLUDED IN THE TOTAL AREA OF RESTORATION. THESE AREAS SHALL BE SAW CUT IN STRAIGHT, NEAT LINES PARALLEL TO THE EXCAVATION OR UTILITY TRENCH AND TO THE NEXT EXISTING JOINT FOR SIDEWALKS AND CURB & GUTTER. ALL SUCH REPAIRS SHALL BE AT THE CONTRACTOR'S EXPENSE AND SHALL MEET ALL CITY TESTING REQUIREMENTS, STANDARDS, AND SPECIFICATIONS.

SEQUENCE OF CONSTRUCTION

- SEE ENVIRONMENTAL NOTES FOR SEQUENCE OF CONSTRUCTION AND NECESSARY PRE- AND POST-INSPECTIONS BY ENVIRONMENTAL INSPECTOR.
- 2. DEMOLITION SHOULD ONLY INCLUDE AREAS THAT WILL BE RE-CONSTRUCTED WITHIN TWO WEEKS UNLESS OTHERWISE APPROVED BY OWNER'S REPRESENTATIVE.







CITY OF AUSTIN - STANDARD NOTES EROSION AND SEDIMENTATION CONTROL (MODIFIED FOR USE ON GENERAL PERMIT PROJECTS)

- 1. THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING, OR EXCAVATION).
- 2. THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENVIRONMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN.
- 3. THE PLACEMENT OF TREE/NATURAL AREA PROTECTIVE FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL AREA PLAN.
- 4. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD ON-SITE WITH THE CONTRACTOR, DESIGN ENGINEER, PERMIT APPLICANT, AND GENERAL PERMIT PROGRAM REPRESENTATIVE AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS AND THE TREE/NATURAL AREA PROTECTION MEASURES AND PRIOR TO BEGINNING ANY SITE PREPARATION WORK. THE CONTRACTOR SHALL NOTIFY THE GENERAL PERMIT PROGRAM OFFICE AT 512/974-6330, AT LEAST 3 DAYS PRIOR TO THE MEETING DATE.
- ANY SIGNIFICANT VARIATION IN MATERIALS OR LOCATIONS OF CONTROLS OR FENCES FROM THOSE SHOWN ON THE APPROVED PLANS MUST BE APPROVED BY THE REVIEWING ENGINEER AND THE GENERAL PERMIT PROGRAM REPRESENTATIVE.
- THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AND FENCES AT DAILY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO INSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES. SILT ACCUMULATION AT INLET DEVICES SHOULD BE REMOVED WHEN THE DEPTH REACHES TWO (2) INCHES.
- PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED, ACCUMULATED SEDIMENT REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES.
- ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS ONE SQUARE FOOT OR LARGER IN TOTAL AREA, BLOWS AIR FROM WITHIN THE SUBSTRATE, AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME, IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT THE GENERAL PERMIT PROGRAM REPRESENTATIVE FOR FURTHER INVESTIGATION.
- FIELD REVISIONS TO THE EROSION/SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES. ANY REVISIONS TO THE PERMITTED PLAN MUST BE APPROVED BY THE GENERAL PERMIT PROGRAM OFFICE OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT.
- 10. PERMANENT EROSION/SEDIMENTATION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. WHERE THE CRITERIA MANUAL AND CONTRACT DOCUMENTS DIFFER THE MOST ENVIRONMENTALLY BENEFICIAL MATERIALS/METHOD SHALL BE REQUIRED UNLESS OTHERWISE APPROVED BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE.
- 11. DEVELOPER INFORMATION:

COMPANY: CITY OF AUSTIN CONTACT: ADDRESS:

PHONE: E-MAIL:

OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: COMPANY:

CONTACT: ADDRESS:


PHONE:

E-MAIL:

PARTY RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE: COMPANY: CONTRACTOR

PARTY RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE: COMPANY: CONTRACTOR

- 12. THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT NOTIFYING THE GENERAL PERMIT PROGRAM REPRESENTATIVE, AT 974-6330, AT LEAST 48 HOURS PRIOR TO THE SPOILS REMOVAL. THIS NOTIFICATION SHALL INCLUDE THE DISPOSAL LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL.
- 13. INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY PRIOR TO STREET WORK, AND WILL BE REMOVED AS SOON AS THE GENERAL PERMIT PROGRAM REPRESENTATIVE AGREES THAT THERE IS NO POTENTIAL FOR SEDIMENTATION.



STANDARD SYMBOL

FOR ROCK BERM (RB)

____ <u>RB__</u> ___

CONSTRUCTION TRAFFIC DAMAGE, ETC

USE ONLY OPEN GRADED ROCK, 4-8 INCH DIAMETER, FOR STREAM FLOW CONDITION. JSE OPEN GRADED ROCK, 3-5 INCH DIAMETER, FOR OTHER CONDITIONS.

- ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 1 INCH
- OPENING AND MINIMUM WIRE DIAMETER OF 20 GAUGE. ROCK BERM SHALL BE INSPECTED WEEKLY OR AFTER EACH RAIN, AND THE STONE AND/OR FABRIC CORE-WOVEN WIRE SHEATHING SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO
- WHEN SILT REACHES A DEPTH FOLIAL TO ONE-THIRD THE HEIGHT OF THE BERM OR ONE FOOT WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED SITE AND IN A MANNER AS TO NOT CREATE A SILTATION PROBLEM.

FUNCTION AS INTENDED, DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT

- DAILY INSPECTION SHALL BE MADE ON SEVERE SERVICE ROCK BERMS: SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES 6 INCHES
- WHEN SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED

| D DISPOSED OF IN AN APPROVED MANNER. | | HALL BE KEMOVED | CONTRIBUTE TO ADDITIO | | | JH A WANNE | EK IHAI V |
|---|---|---------------------|---|--|--|------------|--------------|
| | FABRIC COVERED (SEVERE S BERM | SERVICE) ROCK | CITY OF AUSTIN WATERSHED PROTECTION DE | | SIL | _T FENCE | |
| GENERAL PERMIT PROGRAM N/A APPROVED | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | STANDARD NO. N / A | RECORD COPY SIGNED BY MORGAN BYARS | 09/01/2011 ADOPTED | THE ARCHITECT/ENGINEER RESPONSIBILITY FOR APP USE OF THIS STAND | PROPRIATE | STAND 642 |
| 600 mm (2') MIN. 450 mm (18") MIN. WOVEN WIRE SHEAR | ATHING (24") MIN. FLOW 2 1 | 1 | BETWEEN S | 15 m (50') MI GRADE TO F FROM LEAV PROF APPROPRIATE TABILIZED CON AND PUBLIC RIG (50') M | N. PREVENT RUNOFF ING SITE 200 mm (8") MIN. FILE TRANSITION STRUCTION CHT-OF-WAY IN. | F O W | ROADWAY |

1. USE ONLY OPEN GRADED ROCK 75 to 125 mm (3 to 5") DIAMETER FOR ALL CONDITIONS.

- 2. THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 25 mm (1") OPENING AND MINIMUM WIRE DIAMETER OF 12.9 mm (20 GAUGE
- THE ROCK BERM SHALL BE INSPECTED DAILY OR AFTER EACH RAIN, AND THE STONE AND/OR FABRIC CORE-WOVEN SHEATHING SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED, DUE TO SEDIMENT ACCUMULATION AMONG THE ROCKS, WASHOUT CONSTRUCTION TRAFFIC DAMAGE, ETC
- . IF SEDIMENT REACHES A DEPTH EQUAL TO ONE-THIRD THE HEIGHT OF THE BERM OR 150 mm (6"), WHICHEVER IS LESS, THE SEDIMENT SHALL BE REMOVED AND DISPOSED OF ON AN
- APPROVED SITE AND IN A MANNER THAT WILL NOT CREATE A SEDIMENTION PROBLEM.
- 5. WHEN THE SITE IS COMPLETELY STABILIZED. THE BERM AND ACCUMULATED SEDIMENT SHALL

| 5. WHEN THE SITE IS COMP BE REMOVED AND DISPOS | | LIZED,THE BERM AND ACCUMULATED PROVED MANNER. | SEDIMENT SHALL | 7. DRAINAGE: ENTRANCE MU PREVENT RUNOFF FROM L | | RLY GRADED OR INCORPORATE A DR CONSTRUCTION SITE. | AINAGE SWALE TO |
|---|----------------------|---|---------------------|---|--------------------|---|------------------------|
| CITY OF AUSTIN WATERSHED PROTECTION DEF | | ROCK BERM | | CITY OF AUSTIN WATERSHED PROTECTION DEF | | STABILIZED CONSTRUCTIO | N ENTRANCE |
| RECORD COPY SIGNED BY MORGAN BYARS | 8/24/2010 ADOPTED | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | STANDARD NO. 639S-1 | RECORD COPY SIGNED BY J. PATRICK MURPHY | 5/23/00 ADOPTED | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | STANDARD NO. 641S-1 |

- EXISTING CURB AND GUTTER

CROSS SECTION

| EDGE OF PROPOSEI | D EXCAVATION | ⊗ ⊗ ⊗ | |
|-----------------------------------|------------------------------|-------------|--|
| TEMPORARY SPOILS AND/OR STOCKPILE | RUN-OFF FLOW 20 LB SANDBAGS | ⊗ ⊗ ⊗ ⊗ ⊗ | TRIANGULAR FILTER DIKE (CoA STD. 628S) |

THE TEMPORARY SPOILS/STOCKPILE STORAGE AREA AND STAGING AREA MAY BE LOCATED

- DIRECTLY ADJACENT TO THE EXCAVATION AND ON THE PAVEMENT. ANY SPOIL NOT INTENDED TO BE REUSED WILL BE HAULED TO AN APPROVED OR PERMITTED
- INSTALL TRIANGULAR SEDIMENT FILTER DIKE (DETAIL 628S) ACROSS FULL WIDTH OF TRAFFIC CLOSURE AND DOWNSTREAM OF CONSTRUCTION AREA. PERPENDICULAR TO CURB AND PLACED TO EFFECTIVELY CATCH AND CONTAIN SEDIMENT LADEN RUNOFF FROM THE EXCAVATED AREA. FILTER DIKE TO FOLLOW ACTIVE CONSTRUCTION. REMOVING AND RE-SETTING FILTER DIKE IS CONSIDERED SUBSIDIARY TO BARRICADES AND TRAFFIC HANDLING.
- ADDITIONAL EROSION/SEDIMENTATION CONTROL FOR WORK IN PAVED AREAS FOR GENERAL PERMIT PROGRAM PROJECTS

NOTES: MATERIAL- THE FABRIC MUST CORRESPOND TO THE FOLLOWING TRENCH CROSS SECTION

UIREMENTS: **PROPERTY** REQUIREMENTS FABRIC WEIGHT D 3776 UNCES / SQUARE YARD ULTRAVIOLET (UV) RADIATION STRENGTH RETAINED MIN., AFTER D 4355 HOURS IN XENON ARC DEVICE STABILITY MUUEN BURST STRENGTH ≥ 120 POUND PER SQUARE INCH WATER FLOW RATE ≥ 275 GALLONS / MINUTE / SQUARE FEET

ADJACENT AREAS

COVERAGE -THE FABRIC / WIRE

WORKER, OR PEDESTRIAN

OVERLAP AT LEAST THRE

THE INLET FILTER SHAL

NOT SECURED OR AT

BE REPAIRED IMME

DAILY INSPECTION

THE INLET

SILTATION

CONTRAC

RAINFALL

THIS MATERIAL SHOULD HAVE A MAXI

- 300 mm (12 INCHES). IF WOOD POSTS CANNOT ACHIEVE 300 mm (12 inches) DEPTH, USE STEEL EIGHTEEN (18) MONTHS. THE INLET PROT MANNER THAT WILL FACILITATE CLEAN MINIMIZING INTERFERENCE WITH Q NSTRUCTION ACTIVITIES. THEY SHOULD ALSO BE THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL CONSTRUCTED SUCH THAT ANY PO TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO R.O.W. FLOODING (I.E.< 4 INCHES STANDING WATER) OR DAMAGE TO THE STRUCTURE OR
- THE TRENCH MUST BE A MINIMUM OF 150 mm (6 inches) DEEP AND 150 mm (6 inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH
- SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL OR WOOD FENCE
- INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.
- SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

PLAN VIEW

WIDTH: NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS/EGRESS.

WASHING: WHEN NECESSARY, VEHICLE WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE

DONE ON AN AREA STABILIZED WITH CRUSHED STONE AND DRAINS INTO AN APPROVED TRAP

OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM

MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT

TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAY. THIS MAY REQUIRE PERIODIC

TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AS WELL AS REPAIR AND

CLEAN OUT OF ANY MEASURE DEVICES USED TO TRAP SEDIMENT ALL SEDIMENTS THAT IS

SPILLED. DROPPED. WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED.

STONE SIZE: 75-125 mm (3-5") OPEN GRADED ROCK.

THICKNESS: NOT LESS THAN 200 mm (8").

LENGTH: AS EFFECTIVE BUT NOT LESS THAN 15 m (50').

DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.

ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT

| | ACP EVED FINAL STABILIZA | TION CONDIT | ions. | |
|----------------------|--|---------------------|---|---------------|
| | CITY OF AUSTIN WE TERSHED PROTECTION DEP | ARTMENT | FILTER DIKE CURB INLET F | PROTECTI |
| RD NO. S-1 | RECORD COPY SIGNED BY MAPI VIGIL | 10/30/09 ADOPTED | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | STANDA 628 |
| | STANDARD SYMBOL | 7.50. 125 | NOTE: | |

OVERTOP THE CURB.

INEER ASSUMES 628S-2 R APPROPRIATE TANDARD FILTER FABRIC SHALL ENTIRELY - 150 mm X 150 mm COVER DIKE AND SKIRT. (6" X 6") WIRE MESH STRUCTURE **INSTALLATION DETAIL OPTIONS:** GEOTEXTILE FABRIC TOE-IN 150 mm (6") MINIMUM WEIGHTED WITH 75 mm-125 mm (3"-5") OPFN TRENCHED IN 100 mm (4"). CONTINUOUS BACKING/PLANKS ON IMPERVIOUS SURFACES.

CUT AWAY OF

FILTER FABRIC

ON DEVICES SHOULD BE CONSTRUCTED IN A

HOULD COMPLETELY COVER THE OPENING OF THE INLET AND

ATTACHED IN A WAY THAT THEY CALLEASILY BE REMOVED AND ARE

HED BY THE USE OF SAND BAGS. THE INLET FILTER MUST BE REMOMD

OAT, AND DISPOSED OF IN A MANNER WHICH WILL NOT CAUSE ADDITIONAL

SHALL MONITOR THE PERFORMANCE OF INLET PROTECTION DURING EACH

EVENT AND IMMEDIATELY REMOVE THE INLET PROTECTIONS IF THE STORMWATER

DEVICES SHOULD BE INSTALLED WITHOUT PROTRUDING PARTS THAT COULD BE A TRAFFIC,

UPON COMPLETION WORK. IF REMOVAL DAMAGES THE CONCRITE CURB, THE CURB MUST

ZARD. WHERE SECTIONS OF

SHALL BE MADE BY THE CONTRACTOR AND SILT


PROTECTIONS SHALL BE REMOVED AS SOON AS THE SOURCE OF

THE DEPTH REACHES 50 MM (2 INCHES) INCHES OR ONL T

D DISPOSAL OF TRAPPED SEDIMENT WILE


RM WATER WILL NOT CAUSE EXCESSIVE

HE FABRIC OVERLAP. THEY SHALL



- DIKES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT DIKE. THE FABRIC COVER AND SKIRT SHALL BE A CONTINUOUS WRAPPING OF GEOTEXTILE. THE SKIRT
- SHALL BE A CONTINUOUS EXTENSION OF THE FABRIC ON THE UPSTREAM FACE. THE SKIRT SHALL BE WEIGHTED WITH A CONTINUOUS LAYER OF 75-125 mm (3-5") OPEN GRADED ROCK OR TOED-IN 150 mm (6") WITH MECHANICALLY COMPACTED MATERIAL OTHERWISE. THE
- ENTIRE STRUCTURE SHALL BE TRENCHED IN 100 mm (4"). DIKES AND SKIRT SHALL BE SECURELY ANCHORED IN PLACE USING 150 mm (6") WIRE STAPLES ON 600 mm (2') CENTERS ON BOTH EDGES AND SKIRT, OR STAKE USING 10M (%") DIAMETER RE-BAR WITH TEE ENDS.
- FILTER MATERIAL SHALL BE LAPPED OVER ENDS 150 mm (6") TO COVER DIKE TO DIKE JOINTS. JOINTS SHALL BE FASTENED WITH GALVANIZED SHOAT RINGS
- THE DIKE STRUCTURE SHALL BE MW40-150 mmX150 mm (6 GA. 6"X6") WIRE MESH, 450 mm (18") ON
- INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6") ANI DISPOSED OF IN A MANNER WHICH WILL NOT CAUSE ADDITIONAL SILTATION.
- AFTER THE DEVELOPMENT SITE IS COMPLETLY STABILIZED, THE DIKES AND ANY REMAINING SILT SHALL BE REMOVED. SILT SHALL BE DISPOSED OF AS INDICATED IN GENERAL NOTE 8

TRIANGULAR SEDIMENT FILTER DIKE RECORD COPY SIGNED HE ARCHITECT/ENGINEER ASSUMES ESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.



- STEEL OR WOOD POSTS WHICH SUPPORT THE MULCH SOCK SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 600mm (24 inches). IF WOOD POSTS CANNOT ACHIEVE 600mm (24 inches) DEPTH, USE STEEL POSTS. EARTH ANCHORS ARE ALSO ACCEPTABLE.
- THE TOE OF THE MULCH SOCK SHALL BE PLACED SO THAT THE MULCH SOCK IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. IN ORDER TO PREVENT WATER FROM FLOWING BETWEEN THE JOINTS OF ADJACENT ENDS OFMULCH SOCKS, LAP THE ENDS OF ADJACENT MULCH SOCKS A MINIMUM OF 300mm (12 inches)
- MULCH MATERIAL MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH; IT IS NOT ACCEPTABLE FOR THE MULCH MATERIAL TO CONTAIN GROUND CONSTRUCTION DEBRIS, BIOSOLIDS, OR MANURE.
- SOCK MATERIAL WILL BE 100% BIODEGRADABLE PHOTODEGRADABLE OR RECYCLABLE SLICE AS BURLAP, TWINE, UV PHOTOBIODEGRADABLE PLASTIC, POLYESTER, OR ANY OTHER ACCEPTABLE MATERIAL MULCH SOCKS SHOULD BE USED AT THE BASE OF SLOPES NO STEEPER THAN 2:1 AND SHOULD
- NOT EXCEED THE MAXIMUM SPACING CRITERIA PROVIDED IN CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL TABLE 1.4.5.F.1 FOR A GIVEN SLOPE CATEGORY. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150mm (6 inches). THE
- SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

| MULCH SOCK | | CITY OF AUSTIN |
|---|------------|---------------------------------------|
| WIDECITSOCK | ARTMENT | WATERSHED PROTECTION DEP |
| THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE | 08/24/2010 | RECORD COPY SIGNED BY MORGAN BYARS |
| USE OF THIS STANDARD. | ADOPTED | |





GP-2020-

GENERAL PERMIT PROGRAM (GPP) STANDARD ENVIRONMENTAL NOTES:

ADDITIONAL AREAS:

- ANY ADDITIONAL AREAS REQUIRED FOR CONSTRUCTION OF THIS PROJECT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR MUST SECURE CITY OF AUSTIN APPROVAL OF PROPOSED ADDITIONAL AREAS PRIOR TO USE. APPROVAL OF "CORRECTION REQUEST" MUST BE SECURED FROM THE GENERAL PERMIT PROGRAM OFFICE OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT
- 2. ALL ASSOCIATED PERMITS AND FEES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- IN ORDER TO SECURE APPROVAL FOR USE OF ADDITIONAL AREAS, CONTRACTOR MUST PROVIDE COMPLETE "CORRECTION REQUEST" SUBMITTAL TO GENERAL PERMIT PROGRAM OFFICE AND ALLOW A ONE WEEK COMMENT PERIOD FOR EACH REVIEW. CONTRACTOR SHOULD REQUEST INFORMATION ON THE ELEMENTS REQUIRED TO BE INCLUDED IN THE SUBMITTAL FROM THE OWNER'S REPRESENTATIVE OR THE GENERAL PERMIT PROGRAM OFFICE.
- CONTRACTOR MUST INSTALL AND MAINTAIN EROSION/SEDIMENTATION CONTROLS AND TREE PROTECTION FOR ALL SUCH AREAS IN ACCORDANCE WITH THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL AND AS INCLUDED IN THE APPROVED SUBMITTAL OR DIRECTED IN THE FIELD BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE.
- 5. A SIGNED COPY OF THE PLANS PERMITTED THROUGH THE GENERAL PERMIT PROGRAM MUST BE KEPT ON SITE AND ACCESSIBLE AT ALL TIMES DURING PROJECT CONSTRUCTION.

DEWATERING:

CONTRACTOR IS RESPONSIBLE FOR DEWATERING OF WORK AREA. CONTRACTOR MUST SECURE CITY OF AUSTIN APPROVAL OF PROPOSED DEWATERING PROCEDURES PRIOR TO INSTALLATION OR USE. APPROVAL MUST BE SECURED FROM THE GENERAL PERMIT PROGRAM (GPP) OFFICE OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT CONTRACTOR MUST PROVIDE COMPLETE SUBMITTAL TO GPP OFFICE AND ALLOW AN ONE WEEK (MIN.) COMMENT PERIOD FOR EACH REVIEW. CONTACT THE GPP OFFICE FOR SUBMITTAL REQUIREMENTS.

FUEL STORAGE:

FUEL STORAGE IS PROHIBITED ON THIS PROJECT. ADDITIONALLY, THE CONTRACTOR IS REQUIRED TO NOTIFY THE GENERAL PERMIT PROGRAM OFFICE IMMEDIATELY FOLLOWING ANY SPILL OF FUEL OR OTHER TOXIC MATERIAL. CONTRACTOR IS REQUIRED TO FOLLOW-UP WITH WRITTEN DOCUMENTATION, INCLUDING A COMPLETE DESCRIPTION OF THE INCIDENT, MATERIAL SPILLED, AND ACTIONS TAKEN TO CONTAIN AND CLEAN-UP MATERIAL

FUGITIVE DUST CONTROL:

ALL PROJECTS APPROVED THROUGH THE GENERAL PERMIT PROGRAM (GPP) MUST COMPLY WITH THE CODE OF THE CITY OF AUSTIN AND THE ENVIRONMENTAL CRITERIA MANUAL REQUIREMENTS TO CONTROL AIRBORNE DUST. COMPLIANCE IS REQUIRED FOR ENTIRE PROJECT SITE AS WELL AS ASSOCIATED OPERATIONS. CONTACT THE GPP OFFICE FOR RECOMMENDED CONTROL METHODS.

SPOILS STORAGE:

NO SPOILS STORAGE IS ALLOWED WITHIN A CRITICAL WATER QUALITY ZONE, A 100-YEAR FLOODPLAIN, OR ON A SLOPE WITH A GRADIENT OF MORE THAN 15 PERCENT

E/S CONTROLS FOR BORE / RECEIVING PIT LOCATIONS:

TEMPORARY E/S CONTROLS MUST SURROUND THE ENTIRETY OF BORING OPERATIONS. INCLUDING PIT, EQUIPMENT, ETC. FOR LOCATIONS WITHIN IMPERVIOUS AREAS, TEMPORARY CONTROL WILL BE TRIANGULAR FILTER DIKE (COA STANDARD DETAIL #628S). DIKE FLAP WILL BE CONTINUOUSLY WEIGHTED DOWN THROUGH THE USE OF 1" BY 4" WOOD STRIPS NAILED TO THE PAVEMENT, EXCEPT FOR THE ACCESS POINT. PLACEMENT OF TEMPORARY E/S CONTROLS ACROSS ACCESS POINT WILL BE REQUIRED WHENEVER THE SITE IS NOT ACTIVELY USED. FOR LOCATIONS WITHIN PERVIOUS AREAS, TEMPORARY CONTROL WILL BE SILT FENCE (COA STANDARD DETAIL #642S-1) OR MULCH SOCKS (COA STANDARD DETAIL #648S-1), AS INDICATED ON APPROVED PLANS.

SOIL RETENTION BLANKET:

UNLESS OTHERWISE INDICATED IN THE PROJECT DOCUMENTS, INSTALLATION OF SOIL RETENTION BLANKET WILL BE REQUIRED FOR ALL IMPACTED SLOPES GREATER THAN 3:1 AND ALL IMPACTED AREAS WITHIN DRAINAGE CONVEYANCES. (CITY OF AUSTIN STANDARD SPECIFICATION ITEM 605S) SOIL RETENTION BLANKET SUBMITTAL MUST BE APPROVED BY PROJECT ENGINEER AND GENERAL PERMIT PROGRAM (GPP) REPRESENTATIVE PRIOR TO USE AND MUST INCLUDE PRODUCT AND INSTALLATION DETAILS PROVIDED BY MANUFACTURER. FINISH GRADING MUST BE INSPECTED AND APPROVED BY GPP INSPECTOR PRIOR TO BLANKET INSTALLATION. INSTALLATION MUST BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND MUST BE INSPECTED AND APPROVED BY GPP REPRESENTATIVE PRIOR TO ACCEPTANCE.

SOD INSTALLATION:

REVEGETATION WITHIN MANAGED TURF AREAS MUST BE ACCOMPLISHED THROUGH THE INSTALLATION OF SOLID BLOCK GRASS SOD. SOD TYPE MUST MATCH ADJACENT GRASS TYPE. QUESTIONS REGARDING SOD TYPE WILL BE RESOLVED BY THE GENERAL PROGRAM PERMIT REPRESENTATIVE. REFER TO CITY OF AUSTIN STANDARD SPECIFICATION ITEM NO. 602S: SODDING FOR EROSION CONTROL, UNLESS OTHERWISE NOTED ON THE APPROVED

TxDOT RIGHTS-OF-WAY:

TOPSOIL (TxDOT ITEM NO. 160), SOIL RETENTION BLANKET (TxDOT ITEM NO. 169), AND REVEGETATION (TXDOT ITEM NO. 164) INSTALLED WITHIN TEXAS DEPARTMENT OF TRANSPORTATION (TxDOT) RIGHT-OF-WAY SHALL COMPLY WITH "REQUIREMENTS FOR INSTALLATION OF UTILITIES WITHIN THE STATE RIGHT-OF-WAY, AUSTIN DISTRICT".

PROJECT SEQUENCE:

(REFER TO FULL PLAN SET FOR PROJECT-SPECIFIC ADDITIONS, IF APPLICABLE.)

PRIOR TO CONSTRUCTION:

- SECURE APPLICABLE COA PERMITS, INCLUDING APPROVAL UNDER GENERAL PERMIT PROGRAM AND RIGHT-OF-WAY EXCAVATION PERMIT.
- NOTIFY GENERAL PERMIT PROGRAM REPRESENTATIVE PRIOR TO PLACEMENT OF E/S CONTROLS AND TREE PROTECTION FENCING. ALL PROPOSED PHASING OF CONTROLS MUST BE SUBMITTED TO AND APPROVED BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE PRIOR TO THE FIELD PRE-CONSTRUCTION CONFERENCE.
- NOTIFY COA TEMPORARY TRAFFIC CONTROL REPRESENTATIVE PRIOR TO PLACEMENT OF 7. TEMPORARY TRAFFIC CONTROLS. ALL PROPOSED PHASING OF CONTROLS MUST BE INDICATED ON APPROVED TEMPORARY TRAFFIC CONTROL PLAN AND SEALED BY PROFESSIONAL ENGINEER.
- PLACE TEMPORARY E/S CONTROLS AND TREE PROTECTION FENCING PRIOR TO BEGINNING ANY EXCAVATION. INSTALL C.I.P. SIGN, IF APPLICABLE.
- HOLD ENVIRONMENTAL PRE-CONSTRUCTION CONFERENCE ON SITE WITH THE CONTRACTOR, OWNER'S REPRESENTATIVE, AND GENERAL PERMIT PROGRAM REPRESENTATIVE AFTER INSTALLATION OF E/S CONTROLS AND TREE PROTECTION FENCING AND PRIOR TO ANY TRENCHING OPERATIONS.

6. PLACE TEMPORARY TRAFFIC CONTROL DEVICES.

PROJECT CONSTRUCTION:

- 1. BEGIN CONSTRUCTION. NOTIFY GENERAL PERMIT PROGRAM REPRESENTATIVE A MINIMUM OF 48 HOURS IN ADVANCE OF TRANSITION BETWEEN PHASES.
- CONTACT GENERAL PERMIT OFFICE TO SCHEDULE FIELD INSPECTION PRIOR TO BEGINNING INSTALLATION OF PERMANENT E/S CONTROLS.
- COMPLETE RESTORATION OF ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES FOR THIS PROJECT. (PERMANENT E/S CONTROLS)
- 4. REMOVE TEMPORARY TRAFFIC CONTROL DEVICES RELATED TO WORK AREAS OUTSIDE OF 12. ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE
- 5. HOLD ENVIRONMENTAL POST-CONSTRUCTION CONFERENCE ON SITE WITH THE 13. NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN CONTRACTOR, OWNER'S REPRESENTATIVE, AND GENERAL PERMIT PROGRAM REPRESENTATIVE. ALL PERMANENT E/S CONTROLS MUST BE ACCEPTED BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE. PERMANENT CONTROLS SHALL CONSIST OF REVEGETATION PER DETAILS 602, 604S, AND 609S AS INDICATED ON APPROVED PLANS.
- 6. FOLLOWING FINAL ACCEPTANCE OF PERMANENT E/S CONTROLS BY THE GENERAL PERMIT PROGRAM REPRESENTATIVE, REMOVE TEMPORARY E/S CONTROLS. CLEAN EXISTING STORM DRAINAGE SYSTEMS AS NECESSARY DUE TO CONSTRUCTION OPERATIONS.
- 7. DRESS-UP AND RESTORE ANY AREAS DISTURBED BY REMOVAL OF TEMPORARY E/S CONTROLS DESCRIBED ABOVE.

REQUIRED SUBMITTALS:

SUBMITTALS REQUIRED TO BE APPROVED BY GENERAL PERMIT PROGRAM REPRESENTATIVE INCLUDE: SUBMITTALS TRIGGERED BY CITY OF AUSTIN SERIES 600 SPECIFICATIONS AND RELATED SPECIAL PROVISIONS/SPECIFICATIONS, CONSTRUCTION SCHEDULE, TREE PROTECTION, P-6 AND OTHER ROOT ZONE PROTECTION/MITIGATION MEASURES, DEWATERING PLAN, WATERING SCHEDULE FOR REVEGETATION AREAS, AND ANY VEGETATIVE REPLACEMENT PROPOSALS, IF NOT ALREADY PART OF THE PERMITTED PLAN SET.

CITY OF AUSTIN - STANDARD NOTES TREE AND NATURAL AREA PROTECTION (MODIFIED FOR USE ON GENERAL PERMIT PROJECTS)

LIMITS OF THE PERMEABLE PAVING AREA;

- ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE 2. TYPE AND LOCATION OF ALL TREE PROTECTION MUST BE APPROVED IN THE FIELD BY THE PROTECTED DURING CONSTRUCTION WITH TEMPORARY MEASURES.
- 2. PROTECTIVE MEASURES SHALL BE INSTALLED ACCORDING TO CITY OF AUSTIN STANDARDS 3. FOR TREE PROTECTION
- PROTECTIVE MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR GRADING), AND SHALL BE MAINTAINED THROUGHOUT ALL PHASES OF THE PROJECT.
- EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILD-UP, COMPACTION OR CUTTING OF 4. CRITICAL ROOT ZONE WITHIN TREE DRIP LINES.
- TREE PROTECTION SHALL COMPLETELY SURROUND THE TREES OR GROUP OF TREES AND WILL BE LOCATED AT THE OUTERMOST LIMIT OF BRANCHES (DRIP LINE). FOR NATURAL AREAS, PROTECTIVE MEASURES SHALL FOLLOW THE LIMIT OF CONSTRUCTION LINE, IN 5. ORDER TO PREVENT THE FOLLOWING:
- A. SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC 6. ALL PRUNING SHALL PRESERVE THE NATURAL CHARACTER OF THE TREE. OR STORAGE OF EQUIPMENT OR MATERIALS;
- B. ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN 6 INCHES CUT 7. OR FILL) OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE GENERAL PERMIT PROGRAM OFFICE OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT; C. WOUNDS TO EXPOSED ROOTS, TRUNK OR LIMBS BY MECHANICAL EQUIPMENT;
- D. OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING. AND FIRES.
- EXCEPTIONS TO INSTALLING PROTECTIVE FENCES AT CRITICAL ROOT ZONES MAY BE PERMITTED IN THE FOLLOWING CASES:

A. WHERE THERE IS TO BE AN APPROVED GRADE CHANGE, IMPERMEABLE PAVING

- SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE 10. ANY TREE ROOTS THAT ARE EXPOSED, CUT, OR TORN DURING CONSTRUCTION ACTIVITY APPROXIMATELY 2 FEET BEYOND THE AREA DISTURBED;
- B. WHERE PERMEABLE PAVING IS TO BE INSTALLED, ERECT THE FENCE AT THE OUTER

- C. WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE NO CLOSER THAN 6 FEET TO THE BUILDING;
- WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE, OR OTHER SPECIAL REQUIREMENTS, CONTACT THE GENERAL PERMIT PROGRAM OFFICE AT


SPECIAL NOTE: FOR THE PROTECTION OF NATURAL AREAS, NO EXCEPTIONS TO INSTALLING FENCES AT THE LIMIT OF CONSTRUCTION LINE WILL BE PERMITTED.

WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE 5 FEET OR CLOSER TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF 8 FEET (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING.

- WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN AREAS OF UNPROTECTED ROOT ZONES THOSE AREAS SHOULD BE COVERED WITH 12 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION DURING CONSTRUCTION. FILTER FABRIC UNDERLAYMENT MAY BE REQUIRED AT DIRECTION OF GENERAL PERMIT PROGRAM REPRESENTATIVE BASED ON SITE CONDITIONS AND CONSTRUCTION ACTIVITIES. MAXIMUM FOUR (4) INCHES DEPTH MAY BE LEFT IN PLACE AFTER CONSTRUCTION WITH APPROVAL FROM THE GENERAL PERMIT PROGRAM REPRESENTATIVE.
- ALL GRADING WITHIN PROTECTED ROOT ZONE AREAS SHALL BE DONE BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE. PRIOR TO GRADING, RELOCATE PROTECTIVE FENCES TO 2 FEET BEHIND THE GRADE CHANGE AREA.
- ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT AREAS WITH GOOD QUALITY TOP SOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN 2 DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
- 10. PRIOR TO EXCAVATION OR GRADE CUTTING WITHIN TREE DRIPLINES, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT TO MINIMIZE DAMAGE TO REMAINING ROOTS.
- 11. TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES SHOULD BE WATERED DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. TREE CROWNS SHOULD BE SPRAYED WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE.
- THE DRIPLINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
- 14. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE CONSTRUCTION BEGINS. SEE NOTE FOUR (4) OF SUPPLEMENTAL TREE PROTECTION NOTES FOR ADDITIONAL REQUIREMENTS.
- 15. ALL FINISHED PRUNING MUST BE DONE ACCORDING TO RECOGNIZED, APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES AVAILABLE ON REQUEST FROM THE GENERAL PERMIT PROGRAM OFFICE).
- 16. DEVIATIONS FROM THE ABOVE NOTES MAY BE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NONCOMPLIANCE OR IF A TREE SUSTAINS DAMAGE AS A RESULT.
- 17. TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.

SUPPLEMENTAL TREE PROTECTION NOTES

- 1. ALL TREE PROTECTION MUST COMPLY WITH CITY OF AUSTIN REQUIREMENTS AS OUTLINED IN THE ENVIRONMENTAL CRITERIA MANUAL AND AS INDICATED BY STANDARD COA NOTES AND DETAILS INCLUDED WITHIN THIS DOCUMENT SET.CONTRACTOR SHALL INSTALL PROTECTION PRIOR TO PRE-CONSTRUCTION CONFERENCE, MAKE ADJUSTMENTS TO PROTECTION AS DIRECTED BY THE GPP REPRESENTATIVE, AND MAINTAIN PROTECTION UNTIL PROJECT IS COMPLETE.
- GENERAL PERMIT PROGRAM (GPP) REPRESENTATIVE PRIOR TO CONSTRUCTION.
- WALK-THROUGH: CONTRACTOR SHALL CONDUCT WALK-THROUGH MEETING WITH GENERAL PERMIT PROGRAM REPRESENTATIVE PRIOR TO PERFORMING ANY PRUNING ACTIVITIES ON TREES IN PROJECT AREA. PURPOSE OF WALK-THROUGH WILL BE TWOFOLD. ONE PURPOSE WILL BE TO DETERMINE THE MINIMUM AMOUNT OF PRUNING NECESSARY TO ALLOW CONSTRUCTION WORK TO BE COMPLETED. SECOND PURPOSE WILL BE TO DETERMINE AREAS OF PROJECT IN WHICH EXHAUST DIVERTERS WILL BE REQUIRED ON CONSTRUCTION EQUIPMENT TO PREVENT SCORCHING OF EXISTING TREES.
- ALL PRUNING MUST BE PERFORMED IN ACCORDANCE WITH ANSI A300 (PART 1) 2001 AMERICAN NATIONAL STANDARD FOR TREE CARE OPERATIONS (PRUNING), OR LATEST APPROVED VERSION. THIS DOCUMENT MAY BE OBTAINED ONLINE FOR A FEE AT WWW.ANSI.ORG.
- PRUNING SHALL BE DONE WITH CLEAN, SHARP TOOLS. TO PREVENT BARK TEARS, THE WEIGHT OF THE BRANCH SHALL BE REMOVED BEFORE MAKING FINAL PRUNING CUT.
- ONLY COLLAR CUTS ARE ACCEPTABLE. NO FLUSH CUTS OR STUB CUTS WILL BE ALLOWED.
- ALL BRANCHES THAT ARE BROKEN OR DAMAGED DURING CONSTRUCTION SHALL BE
- PRUNING CUTS OR DAMAGED AREAS ON AN OAK TREE SHALL BE PAINTED WITHIN FIVE MINUTES WITH A STANDARD TREE WOUND DRESSING. TREE WOUND DRESSING SHALL BE EITHER TREEKOTE AEROSOL OR TANGLEFOOT PRUNING SEALER (OR APPROVED EQUAL). THIS ALSO APPLIES TO WOUNDS CREATED BY CONSTRUCTION VEHICLES OR EQUIPMENT. ALL PRUNING MUST BE IN ACCORDANCE WITH COA OAK WILT PREVENTION POLICY.
- SHALL BE PRUNED FLUSH WITH THE SURROUNDING SOIL. (REFER ALSO TO NUMBER 9 OF THE TREE AND NATURAL AREA PROTECTION NOTES INCLUDED IN THIS PLAN SET.)
- 11. ALL TRENCHING WITHIN THE CRITICAL ROOT ZONE OF A TREE TO BE PRESERVED WILL BE SAW CUT OR EXCAVATED BY HAND, AS APPROVED BY THE GENERAL PERMIT PROGRAM
- 12. REFER TO ENVIRONMENTAL CRITERIA MANUAL APPENDIX P-6 FOR FURTHER REMEDIAL TREE CARE REQUIREMENTS. P-6 REMEDIAL TREE CARE WILL BE COORDINATED WITH AND APPROVED BY THE GENERAL PERMIT PROGRAM ARBORIST FOR PROJECTS PERMITTED THROUGH THE GENERAL PERMIT PROGRAM.



DRIPLINE

100 mm-150 mm

CITY OF AUSTIN

WATERSHED PROTECTION DEPARTMENT

(4"-6") DEPTH

RECORD COPY SIGNED

BY J. PATRICK MURPHY

- WOOD CHIP MULCH AREA

TREE PROTECTION FENCE

610S-4

MODIFIED TYPE A - CHAIN LINK

THE ARCHITECT/ENGINEER ASSUMES $oldsymbol{\mathsf{I}}$

RESPONSIBILITY FOR APPROPRIATE

USE OF THIS STANDARD.





TREE NVIR



GP-2020- .PWD







| | PED 16 | |
|--|--------|---|
| | | _ |

CIT PUBLIC ENGINEE EXISTING SITE PLAN
(SHEET 1 OF 5)


IVER_IMPROVEMENTSICADIPRODUCTION_FILESIDWGNRF


| NOTES NAME DATE SURVEY BY DRAWN BY DS DESIGNED BY CN CHECKED BY ESD REVIEWED BY KS | | | |
|---|-------------|------|------|
| DRAWN BY DS DESIGNED BY CN CHECKED BY ESD | NOTES | NAME | DATE |
| DESIGNED BY CN CHECKED BY ESD | SURVEY BY | | |
| CHECKED BY ESD | DRAWN BY | DS | |
| | DESIGNED BY | CN | |
| REVIEWED BY KS | CHECKED BY | ESD | |
| 1121121121 | REVIEWED BY | KS | |

| • | |
|-------------|----------------|
| | |
| _ | |
| HODIZONITAL | L SCALE IN FEE |

| GP-202 | 20 | PWD | (EVIN |
|--------|----|--------------|----------|
| VA101 | 8 | of <u>46</u> | SWEAT, K |








| | E D 103 | |
|--|---------|---|
| | | 1 |

| NOTES NAME DATE SURVEY BY DRAWN BY DS DESIGNED BY CHECKED BY ESD | | | |
|--|-------------|------|------|
| DRAWN BY DS DESIGNED BY CN | NOTES | NAME | DATE |
| DESIGNED BY CN | SURVEY BY | | |
| | DRAWN BY | DS | |
| CHECKED BY ESD | DESIGNED BY | CN | |
| | CHECKED BY | ESD | |
| REVIEWED BY KS | REVIEWED BY | KS | |

| 0 | 20 | 40 |
|------------|--------------|----|
| | | |
| HORIZONTAL | SCALE IN FEE | T |

| GP-202 | 20 | PWD | KEVIN |
|--------|----|--------------|----------|
| VA102 | 9 | of <u>46</u> | SWEAT, K |








I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023

KEVIN SWEAT

CITY OF AUSTIN, TEXAS
PUBLIC WORKS DEPARTMENT
ENGINEERING SERVICES DIVISION
RED RIVER
ENHANCEMENT
EXISTING SITE PLAN
(SHEET 3 OF 5)
REDRIVER_IMPROVEMENTS\(CARREVORMERTS\(CARrevormerts\(C





| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |

HORIZONTAL SCALE IN FEET

GP-2020-___.PWD

VA103 <u>10</u> of <u>46</u>






THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023

KEVIN SWEAT

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

CITY OF AUSTIN, TEXAS
PUBLIC WORKS DEPARTMENT
ENGINEERING SERVICES DIVISION
RED RIVER
ENHANCEMENT
EXISTING SITE PLAN
(SHEET 4 OF 5)
REDRIVER_IMPROVEMENTS/CAD/PRODUCTION_FILES/DWG/RRDI-VA-SI-P




| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |

HORIZONTAL SCALE IN FEET

GP-2020-___.PWD

/A104 <u>11</u> of <u>46</u>



REV. BY DATE REVISION DESCRIPTION

KEVIN SWEAT

92023

CENSE

ON SONAL ENGINEER


2020-12-2

THE SEAL APPEARING ON THIS
DOCUMENT WAS AUTHORIZED BY
KEVIN SWEAT
LIC. # 92023

CERTIFY THAT THESE DRAWINGS ARE
OMPLETE, ACCURATE AND ADEQUATE
OR THEIR INTENDED PURPOSES
ICLUDING CONSTRUCTION, BUT ARE NOT

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

CITY OF AUSTIN, TEXAS
PUBLIC WORKS DEPARTMENT
ENGINEERING SERVICES DIVISION
RED RIVER
ENHANCEMENT
EXISTING SITE PLAN
(SHEET 5 OF 5)
(SHEET 5 OF 5)





| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |


HORIZONTAL SCALE IN FEET


GP-2020-___.PWD


VA105 <u>12</u> of <u>46</u>



































*

KEVIN SWEAT

92023

KEVIN SWEAT

RIVE

NAME DATE

DS

CN

ESD

KS

.PWD

Engineering Services

DIVISION

SURVEY BY

DRAWN BY


DESIGNED BY


REVIEWED BY

GP-2020-

CHECKED BY

TION F3)





1. ALL CONCRETE SHALL BE CLASS "A"

2. ALL REINFORCING STEEL SHALL BE GRADE 60

DIMENSIONS RELATING TO REINFORCING STEEL ARE TO CENTERS OF BARS. 4. VERTICAL STEEL MAY BE SPLICED (380 mm or 15" MIN. LAP) IN THE LOWER ONE-HALF OF ALL INLET WALLS.5. IN AREAS OF CONFLICT BETWEEN REINFORCING STEEL, PIPES AND MANHOLE FRAME, THE REINFORCEMENT SHALL BE BENT OR ADJUSTED TO CLEAR AS DIRECTED BY THE ENGINEER.

6. QUANTITIES SHOWN HEREON ARE FOR THE CONTRACTOR'S INFORMATION ONLY. PAYMENT WILL BE MADE FOR EACH INLET OF THE TYPE SPECIFIED, COMPLETE IN PLACE INCLUDING MANHOLE FRAME AND OVER.

7. CHAMFER ALL EXPOSED EDGES 20 mm (3/4 "). 8. MANHOLE FRAME AND COVER SHALL BE IN ACCORDANCE WITH CITY OF

AUSTIN STANDARD 503S-1. 9. THE CONTRACTOR MAY PROPOSE ALTERNATE PROCEDURES FOR THE CONSTRUCTION OF INLETS, INCLUDING PRECAST UNITS. PLANS FOR SUCH

PROPOSED ALTERNATES SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL BEFORE CONSTRUCTION. 10. ALL INLET WALLS SHALL BE FORMED EXCEPT WHERE THE NATURE OF THE SURROUNDING MATERIAL IS SUCH THAT IT CAN BE TRIMMED TO A SMOOTH VERTICAL FACE. WHEN INLET WALLS ARE PLACED TO NEAT EXCAVATION LINES

THE WALL THICKNESS SHALL NOT EXCEED 10 INCHES. 11. PAYMENT FOR INLET AT THE CONTRACT PRICE SHALL INCLUDE THE TRANSITION CURB.


12. INVERT OF INLET SHALL BE SLOPED 1:20 WITH FILL CONCRETE, SHAPED AS "V" SECTION

13. NO SPLICING OF REINFORCING STEEL SHALL BE PERMITTED UNLESS OTHERWISE NOTED ON THE PLANS OR PERMITTED IN WRITING BY THE ENGINEER.


REFERENCES:

FOR EXPANSION JOINT DOWEL AND DOWEL LOCATION DETAILS SEE STD. 430S-3, "CURB EXPANSION JOINT DOWEL DETAIL". FOR 18" MANHOLE FRAME AND COVER DETAILS SEE STD. 503S-1, "18" COVER AND FRAME".


| CITY OF AUSTIN department of public wo | TYPICAL DETAILS FOR (| CURB INLET |
|---|---|---------------------------|
| RECORD COPY SIGNED BY BILL GARDNER | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | standard no. 5085— 4 of 4 |



GP-2020-___.PWD




THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023 I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL. CONSTRUCTION DETAILS (SHEET 3 OF 3)




| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |



Engineering Services
D | V | S | O N





BARRICADING SUMMARY TABLE

| | STREETS | | | | | | | | |
|---------------|----------------|------------|---------------|---------------|-------------------------|--|---------------------------|--------------|----------|
| STREET | CLASSIFICATION | PROTECTION | STREET FROM | STREET TO | PLANNED IMPROVEMENTS | TRAFFIC CONTROL PLAN SHEET / DETAIL | ALLOWED BARRICADING HOURS | DURATION (*) | COMMENTS |
| RED RIVER ST. | COLLECTOR | | E. 6TH ST. | E. 7TH ST. | SIDEWALK IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| RED RIVER ST. | COLLECTOR | | E. 7TH ST. | E. 8TH ST. | SIDEWALK IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| RED RIVER ST. | COLLECTOR | | E. 8TH ST. | E. 9TH ST. | SIDEWALK IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| RED RIVER ST. | COLLECTOR | | E. 9TH ST. | E 10TH ST. | SIDEWALK IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| E. 9TH ST. | COLLECTOR | | RED RIVER ST. | NECHES ST. | SIDEWALK IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| E. 7TH ST. | ARTERIAL | | SABINE ST. | RED RIVER ST. | DRIVEWAY RECONSTRUCTION | | 7 AM 7 P.M. 7 DAYS | | |
| | | | | | | | | | |

(*) PRIOR TO APPROVAL OF ROW PERMIT CONTRACTOR SHALL COMPLETE THE DURATION COLUMN OF THIS TABLE BASED UPON THE PROJECT SEQUENCING REQUIREMENTS AND PROPOSED MEANS AND METHODS FOR CONSTRUCTING THE PROJECT.

| | INTERSECTIONS | | | | |
|---|--|--|--|--------------|----------|
| STREET INTERSECTION | PLANNED IMPROVEMENTS | TRAFFIC CONTROL PLAN SHEET / DETAIL | ALLOWED BARRICADING HOURS | DURATION (*) | COMMENTS |
| RED RIVER ST. AT E. 7TH ST. | PEDESTRIAN SAFETY GEOMETRIC IMPROVEMENTS | | 9:00 A.M 3:00 P.M. M-F, 7 A.M 7 P.M. SAT-SUN | | |
| RED RIVER ST. AT E. 8TH ST. | PEDESTRIAN SAFETY GEOMETRIC IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| RED RIVER ST. AT E. 9TH ST. | PEDESTRIAN SAFETY GEOMETRIC IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| RED RIVER ST. AT E. 10TH ST. | PEDESTRIAN SAFETY GEOMETRIC IMPROVEMENTS | | 7 AM 7 P.M. 7 DAYS | | |
| | | | | | |
| | | | | | |
| | | | | | |
| (*) PRIOR TO APPROVAL OF ROW PERMIT CON | NTRACTOR SHALL COMPLETE THE DURATION COLUMN OF THIS TABLE BASED UPON THE PRO | JECT SEQUENCING REQUIREMENTS AND | PROPOSED MEANS AND METHODS FOR CONSTRUCTING THE PI | ROJECT. | |

RIGHT OF WAY MANAGEMENT STANDARD NOTES

- CONTRACTOR SHALL HAVE AN APPROVED RIGHT OF WAY (ROW) PERMIT AND TRAFFIC CONTROL PLAN (TCP) IN ELECTRONIC OR PAPER FORMATS ON SITE AT ALL TIMES WHEN WORKING IN THE ROW.
- CONTRACTOR SHALL PROVIDE NOTIFICATION, AS PER THE LATEST MOBILITY GUIDELINES (MG-04).
- 3. UNLESS OTHERWISE APPROVED BY THE ROW DIVISION OF AUSTIN TRANSPORTATION DEPARTMENT (ATD): A.) ONLY ONE PHASE OF A TCP MAY BE SET AT ANY ONE TIME, AND B.) INITIAL SETUP AND PHASE CHANGES OF LONG-TERM WORK ZONES SHALL BE INSTALLED ON WEEKENDS.
- ONCE TRAFFIC CONTROL HAS BEEN SET, THE AUTHORIZED AND COMPETENT REPRESENTATIVE FROM THE PROJECT TEAM/BARRICADE COMPANY WILL COMPLETE AND UPLOAD THE "CONTRACTOR'S SELF-INSPECTION CHECKLIST" FORM. SEE FORM AND DETAILED INSTRUCTIONS HERE
- HTTPS://WWW.AUSTINTEXAS.GOV/PAGE/RIGHT-WAY-TRAFFIC-CONTROL
- FOR ROW VIOLATIONS, AN INVESTIGATION FEE WILL BE ASSESSED FOR EACH OFFENSE UNTIL THE VIOLATION IS CORRECTED. SEE CURRENT FEE SCHEDULE HERE: HTTPS://WWW.AUSTINTEXAS.GOV/SITES/DEFAULT/FILES/FILES/TRANSPORTATION/ RIGHT_OF_WAY/APPROVED_ROW_FEES.PDF
- EXCAVATIONS SHALL BE BACKFILLED OR PLATED WHEN REQUIRED TO OPEN TO TRAFFIC. TEMPORARY PAVING SHALL BE DONE ACCORDING TO CITY OF AUSTIN (COA) STANDARD DETAIL 1100S-4 (FOR HMAC OR PCC PAVEMENTS). FOR EXCAVATIONS EXCEEDING A TRANSVERSE WIDTH OF 5 FEET, THE CONTRACTOR SHALL PROVIDE AN ENGINEERED PLATING PLAN FOR REVIEW BY THE CITY.
- 7. PEDESTRIAN ROUTES IN AND AROUND THE WORK ZONE, INCLUDING CONSTRUCTION ENTRANCES, TEMPORARY WALKING PATHS, BYPASSES, COVERED WALKWAYS, AND DETOURS. MUST REMAIN ACCESSIBLE AND ADA COMPLIANT THROUGHOUT THE
- 8. ALL APPLICABLE SAFEGUARDS SHALL BE IN PLACE PER CHAPTER 33 OF THE INTERNATIONAL BUILDING CODE, TO INCLUDE PEDESTRIAN PROTECTIONS PER SECTION
- "CONSTRUCTION ENTRANCE AHEAD" SIGNS MUST BE PLACED AT ALL APPROACHES TO CONSTRUCTION ENTRANCES, UNLESS OTHERWISE SHOWN ON THE APPROVED TCP.
- 10. EXISTING DRIVEWAYS SHALL NOT BE CLOSED EXCEPT WITH ADVANCE NOTICE TO THE AFFECTED BUSINESSES/RESIDENCES AND APPROVAL FROM THE ROW DIVISION OF ATD.
- 11. ALL TRAFFIC CONTROL DEVICES INCLUDING PROTECTIVE BARRIERS MUST BE CRASHWORTHY AND INSTALLED ACCORDING TO THE MANUFACTURER'S GUIDELINES. CRASHWORTHINESS SHALL BE DETERMINED PER MASH TESTING REQUIREMENTS.

- 12. OVERNIGHT PROTECTION OF WORK ZONES AND STORAGE OF MATERIAL/EQUIPMENT SHALL BE ACCORDING TO COA STANDARD DETAIL 804S-4.
- 13. THE NAME OF THE BARRICADE CONTRACTOR SHALL BE SHOWN ON THE NON-REFLECTIVE SURFACE OF ALL TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH COA STANDARD DETAIL 804S-5.
- 14. THE CITY'S TRAFFIC ENGINEER OR INSPECTOR MAY MAKE OR REQUIRE FIELD ADJUSTMENTS TO ADDRESS ISSUES OF SAFETY AND MOBILITY.
- 15. IF EXISTING CAPITAL METRO BUS STOPS ARE WITHIN THE TEMPORARY TRAFFIC CONTROL OR DETOUR AREA, THE CONTRACTOR SHALL CONTACT CAPITAL METRO (LAURIE MICHEL AT (512) 621-5713 (MOBILE) / (512) 369-7701 (WORK), LAURIE.MICHEL@CAPMETRO.ORG) OR SERVICE.IMPACTS@CAPMETRO.ORG, TWO (2) WEEKS PRIOR TO SETTING UP THE TRAFFIC CONTROL DEVICES IN ORDER TO COORDINATE POTENTIAL BUS-STOP RELOCATION OR ANY OTHER RELATED ISSUES.
- 16. IF EXISTING SIGNALIZED INTERSECTIONS ARE WITHIN THE TEMPORARY TRAFFIC CONTROL AREA, THE CONTRACTOR SHALL CONTACT ATD - SIGNALS DIVISION AT (512) 974-4075, ONE WEEK PRIOR TO SETTING TRAFFIC CONTROL DEVICES.
- 17. THE RIGHT OF WAY SHALL BE RETURNED TO FULL USE AT THE END OF THE APPROVED
- 18. CONTRACTORS SHALL ADHERE TO ALL ROW SPECIAL EVENT ACTIVITY RESTRICTIONS, AS PER THE LATEST MOBILITY GUIDELINES (MG-08).
- 19. PROJECTS THAT ARE ROUTED THROUGH THE DAPCZ PROCESS ARE REQUIRED TO COORDINATE WITH THE OFFICE OF SPECIAL EVENTS ((512) 974-1000 OR TRANSPORTATIONSPECIALEVENTS@AUSTINTEXAS.GOV), IN CONJUNCTION WITH THE ROW DIVISION OF ATD. VISIT <u>CITY STAGE</u> FOR SCHEDULED EVENTS FOR ALL OF AUSTIN.
- 20. PURSUANT TO CITY CODE 9-2-3, ROW WORK MUST NOT MAKE NOISE AUDIBLE TO AN ADJACENT BUSINESS OR RESIDENCE BETWEEN 10:30 PM AND 7:00 AM OR OPERATE A MACHINE THAT SEPARATES, GATHERS, GRADES, LOADS AND UNLOADS SAND, ROCK OR GRAVEL WITHIN 600 FEET OF A RESIDENCE, CHURCH, HOSPITAL, HOTEL OR MOTEL BETWEEN 7:00 PM AND 6:00 AM, EXCEPT FOR INSTALLATION OF CONCRETE AUTHORIZED BY A SEPARATE NON-PEAK HOUR CONCRETE POUR PERMIT ISSUED UNDER CITY CODE SECTION 9-2-21.

STREET PROTECTION & CLASSIFICATION:

STREET PROTECTION AND CLASSIFICATION ARE BASED ON PUBLIC WORKS PROTECTION STREETS LIST DATED OCTOBER 6^{1H}, 2020.

NOTES FOR CONTRACTOR:

- 1. CONTRACTOR TO MAINTAIN ACCESS TO ALL RESIDENT'S DRIVEWAYS DURING CONSTRUCTION.
- 2. ONE WEEK PRIOR TO CONSTRUCTION, PUBLIC OUTREACH IS REQUIRED AND CONTRACTOR TO CALL THE 311 SYSTEM.
- 3. EXISTING SIDEWALKS SHALL REMAIN ACCESSIBLE AT ALL TIMES. IF NEEDED, A CONSTRUCTION FENCE SHALL BE PLACED FOR PEDESTRIAN SAFETY.
- 4. CONTRACTOR MAY USE COA STANDARD DETAIL 804S-1, SHEET 9 OF 9 FOR SIGN SPACING.

MESSAGE BOARD TO READ AS FOLLOWS:

"UTILITY " "STARTING" "FOLLOW " "DETOUR _ _"

(# - THE MONTH AND DAY IN TWO DIGIT NUMBERS)

(MESSAGE BOARD ADVISES OF CONSTRUCTION PLACED A WEEK PRIOR TO CONSTRUCTION, INSTALL NOT TO BLOCK SIDEWALK)

SPECIAL PEDESTRIAN ACCOMMODATION NOTES:

- PEDESTRIAN TRAFFIC MUST BE MAINTAINED. SIDEWALK CLOSURES USING COA STANDARD 804S-1, 4 OF 9 ARE ACCEPTABLE ONLY IN SITUATIONS WHERE PEDESTRIANS CAN BE DETOURED AROUND THE CLOSURE WITHIN ONE BLOCK, AND/OR WITHIN A DISTANCE OF 1,000 FEET. PEDESTRIAN STREET CROSSINGS CAN BE MADE AT DESIGNATED CROSSWALKS
- 2. IF A PEDESTRIAN DETOUR IS NOT FEASIBLE, THE CONTRACTOR SHALL PROVIDE COMPETENT/TRAINED PERSONNEL TO ASSIST PEDESTRIANS AROUND THE ACTIVE WORK

CAPITAL METRO BUS STOP COORDINATION:

1. FOR ANY CONSTRUCTION THAT WILL POTENTIALLY IMPACT BUS ROUTES OR BUS STOPS FOR THE CAPITAL METRO SERVICE AREA, CONTACT MARK A. HERRERA (512) 369-6548 OR MARK.HERRERA@CAPMETRO.ORG AT LEAST 48 HOURS PRIOR TO TRAFFIC CONTROL SET

ALLEY CLOSURE COORDINATION:

1. ALLEY CLOSURES REQUIRE AUSTIN RESOURCE RECOVERY (ARR) COORDINATION WITH LORI SCOTT (512) 974-1028 OR LORI.SCOTT@AUSTINTEXAS.GOV AND AREA BUSINESSES, ONE WEEK IN ADVANCE.

NO PARKING SIGNS:


- 1. ALL NO PARKING SIGNS MUST BE PLACED AT 45 DEGREE ANGLE TO TRAFFIC, AT 50' MINIMUM / 75' MAXIMUM SPACING, NO MORE THAN 48 HOURS IN ADVANCE. CONTACT DAVID SMITH WITH COA METER SHOP AT (512) 974-1553 TO HOOD METERS.
- 2. THE SIGN CONFIGURATION LISTED BELOW SHALL APPLY AS IT IS REQUIRED EVERYWHERE WHERE "NO PARKING" IS NEEDED:











KEVIN SWEAT


THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT

CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

RIVE

E N N N

PUBI SGINE




Engineering Services DIVISION


.PWD


GP-2020-

EXCEPTIONS TABLE

| NOTE# | EXPLANATION OF EXCEPTION | | | |
|-------|--------------------------|--|--|--|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |







0

NO

Ö

NAME DATE

DS

CN

ESD

KS

Engineering Services

DIVISION

SURVEY BY


DRAWN BY


DESIGNED BY


CHECKED BY

REVIEWED BY

GP-2020-_







KEVIN SWEAT

92023

CENSE

2020-12-2

THE SEAL APPEARING ON THIS


I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT


S (SHEET 2 OF 10)

ENGINEERING SERVICES DIVISION RED RIVER
ENHANCEMENT

CON




| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |





Engineering Services D I V I S I O N

GP-2020-___.PWD

T502 32 OF <u>46</u>










GP-2020-

.PWD







CHECKED BY

REVIEWED BY

ESD


KS

.PWD

Engineering Services

DIVISION

GP-2020-



KEVIN SWEAT

KEVIN SWEAT

FORMAL CITY APPROVAL.

 \circ

5

NO

Ö

NAME DATE

DS

CN

ESD

KS

.PWD

Engineering Services

DIVISION

GP-2020-


SURVEY BY


DRAWN BY

DESIGNED BY

CHECKED BY

REVIEWED BY





C. WHITE RETRO-REFLECTIVE ARROW AND LETTERS D. WHITE RETRO-REFELCTIVE BUSINESS LOGO

ADOPTED

B. BLUE RETRO-REFLECTIVE BACKGROUND

RECORD COPY SIGNED

BY SAM ANGOORI

NOTES:

1. CONTRACTORS CAN MAKE BUSINESS NAMES REMOVABLE/CHANGEABLE AS AN OPTION. 2. BUSINESS LOGO ARE OPTIONAL. IF USED LETTERING MUST BE MINIMIZED.

CITY OF AUSTIN SPECIAL WORK ZONE SIGNS DEPARTMENT OF PUBLIC WORKS

THE ARCHITECT/ENGINEER ASSUMES

RESPONSIBILITY FOR APPROPRIATE

USE OF THIS STANDARD.

STANDARD NO.

804S-5

10 OF 13

| | <u> </u> | | • | | <u>ı</u> · |
|---|--|---|--|--|---|
| | C | ONSTRUCTION / | | | |
| | | EXISTING DRIVEWAY | 1 | | _ |
| DR | IVEWAY AC | CESS BARRICA | ADE DET | <u>AIL</u> | |
| () | NORK | CROSSROAD | × | END ROAD WORK TRAFFIC FINES DOUBLE | MAY BE MOUNTE! BACK OF CW20-1 WITH APPROVAL ENGINEER OR DESIGNATED REPRESENTATIVE |
| | | PROJECT | | | |
| BACK OF TMUTCD CW20-1 SIGN WITH APPROVAL OF ENGINEER OR DESIGNATED REPRESENTATIVE TMUTCD-TEXAS MANUAL FOR UNIFORM TRAFFIC | TRAFFIC X FINES DOUBLE END ROAD WORK CROSSRO | CROSSROAD | ND BARE | ROAD WORK AHEAD | |
| | | MAY BE MOUNTED ON BACK OF TMUTCD CW20-1 SIGN WITH APPROVAL OF ENGINEER OR DESIGNATED REPRESENTATIVE TMUTCD-TEXAS MANUAL FOR UNIFORM TRAFFIC CROSSRO | DRIVEWAY ACCESS BARRICA ROAD WORK AHEAD AHEAD WORK AHEAD ROAD WORK | DRIVEWAY ACCESS BARRICADE DET. PROJECT PROJECT | AREA EXISTING DRIVEWAY ACCESS BARRICADE DETAIL DRIVEWAY ACCESS BARRICADE DETAIL ROAD WORK AHEAD AREA TYPE I BARRICADES PROJECT PROJECT PROJECT PROJECT PROJECT ROAD WORK AHEAD APPROVAL OF ENGINEER OR DESIGNATED REPRESENTATIVE TMUTCD-TEXAS MANUAL FOR UNIFORM TRAFFIC CROSSPOAD SIGNING AND BARRICADING |

DEPARTMENT OF PUBLIC WORKS

ADOPTED

RECORD COPY SIGNED

BY SAM ANGOORI

BUSINESS ACCESS

ALL TRAFFIC CONTROL DEVICES, SIGNS, BARRICADES AND WARNING SIGNS SHALL BE FURNISHED, PLACED, CONSTRUCTED AND MAINTAINED IN THE APPROPRIATE TYPES AND SIZES AND FLAGGER OPERATIONS EXECUTED IN ACCORDANCE WITH THE CURRENT EDITION OF THE TEXAS MANUAL ON UNIFORM CONTROL SHALL CONTROL UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.

CROSSROAD & DRIVEWAY

THE ARCHITECT/ENGINEER ASSUMES

RESPONSIBILITY FOR APPROPRIATE

USE OF THIS STANDARD.

STANDARD NO.

804S-5

12 OF 13

| D, | 13. ALL PERSONS WORKING WITHIN THE RIGHT-OF-WAY SHALL WEAR A BRIGHTLY COLORED SAFETY VEST. FO |
|----|---|
| IS | NIGHTTIME WORK THE VEST SHALL BE RETRO-REFLECTIVE. |

- 14. WHEN AN INTERSECTION IS CLOSED FOR CONSTRUCTION, THE CONTRACTOR SHALL PROCEED WITH
- 15. THE CONTRACTOR SHALL NOTIFY THE CAPITAL METRO DISPATCHER AT 385-4295 ONE (1) WEEK PRIOR TO

WORK DURATION IS A MAJOR FACTOR IN DETERMINING THE NUMBER AND TYPES OF DEVICES USED IN TEMPORARY TRAFFIC ZONES. THE FIVE (5) CATEGORIES OF WORK DURATION AND THEIR TIME AT A LOCATION

- INTERMEDIATE-TERM STATIONARY-WORK THAT OCCUPIES A LOCATION FROM OVERNIGHT TO 3 DAYS.
- SHORT-TERM STATIONARY-DAYTIME WORK THAT OCCUPIES A LOCATION FROM 1 TO 12 HOURS.

| Typical Transition Lengths and Suggested Maximum Spacing of Devices | | | | | | | | |
|---|------------------------|-------------------|---------------------------------------|---------------------------------------|---------------------------------------|-----------------------------------|-------------------------------------|--|
| | | | Taper | ım Desirat Lengths (L (Feet) | | Suggest Device S | | Suggested Sign Spacing Meters (Feet) |
| Speed KMPH | Posted Speed MPH | Formula | 3.0(10) Offset Meters (feet) | 3.3(11) Offset Meters (feet) | 3.6(12) Offset Meters (feet) | On a taper Meters (feet) | On a tangent Meters (feet) | "X" Dimension |
| 50 | 30 | | 45 (150) | 50 (165) | 55 (180) | 9 (30) | 15-20 (50-65) | 40 (120) |
| 55 | 35 | L=\frac{WS}{60}^2 | 65 (205) | 70 (225) | 75 (245) | 10 (35) | 20-25 (65-80) | 50 (160) |
| 65 | 40 | | 80 (265) | 90 (295) | 100 (320) | 12 (40) | 25-30 (80-100) | 75 (240) |
| 70 | 45 | | 135 (450) | 150 (495) | 165 (540) | 13 (45) | 25-30 (80-100) | 100 (320) |
| 80 | 50 | | 150 (500) | 165 (550) | 180 (600) | 15 (50) | 30-35 (100-110) | 120 (400) |
| 90 | 55 | 1 = \\/6 | 165 (550) | 185 (605) | 200 (660) | 16 (55) | 35-40 (110-130) | 150 (500) |
| 95 | 60 | L=WS | 180 (600) | 200 (660) | 220 (720) | 18 (60) | 40-45 (130-150) | 180 (600) |
| 105 | 65 | | 195 (650) | 215 (715) | 235 (780) | 19 (65) | 45-50 (150-165) | 210 (700) |
| | | 1 | 215 | 225 | 255 | 24 | EO EE | |

| CITY OF AUSTIN DEPARTMENT OF PUBLIC W | ORKS | GENERAL TRAFFIC CONTI | ROL NOTES |
|--|---------------------|---|---|
| RECORD COPY SIGNED BY SAM ANGOORI | 01/04/10 ADOPTED | THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. | STANDARD NO. 804S-5 13 OF 13 |

KEVIN SWEAT THE SEAL APPEARING ON THIS

DOCUMENT WAS AUTHORIZED BY


KEVIN SWEAT

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

> 0 0 9

CON


STIN, TEXAS S DEPARTMENT ERVICES DIVISION



| NOTES | NAME | DAT |
|-------------|------|-----|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |



Engineering Services DIVISION GP-2020-____.PWD CT506 | 36 of <u>46</u>



ADOPTED

DEPARTMENT OF PUBLIC WORKS

RECORD COPY SIGNED

BY SAM ANGOORI

STANDARD NO.


804S-5

11 OF 13

THE ARCHITECT/ENGINEER ASSUMES

RESPONSIBILITY FOR APPROPRIATE

USE OF THIS STANDARD.



KEVIN SWEAT THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023 I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL. 10) OF (SHEE RED RIVER ENHANCEMENT DE CON

NOTE

- MINIMUM TRAVEL LANE WIDTH FOR A SINGLE DIRECTION OF TRAVEL, SHALL BE 11' FOR TWO-WAY TRAVEL, MINIMUM PAVEMENT WIDTH SHALL BE 23', MEASURED FROM FACE OF CURB TO FACE OF CURB.
- 2. PEDESTRIAN DETOUR IS ONLY APPLICABLE IF ADA CROSSWALKS ARE PRESENT.

| SURVEY BY | | |
|-------------|-----|--|
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |


NOTES | NAME | DATE





Engineering Services
D | V | S | O N


| GP-2020 | PWD |
|---------|-----|
| | |


CT507 37 OF 4














KEVIN SWEAT

92023

CENSE

ON AL END

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY

KEVIN SWEAT

LIC. # 92023

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

ORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

CITY OF AUSTIN, TEXAS
PUBLIC WORKS DEPARTMENT
ENGINEERING SERVICES DIVISION
RED RIVER

TE AUTOMOBINATION OF THE PROPERTY OF THE PROPE

0

NOTES NAME DATE

SURVEY BY

DRAWN BY DS

DESIGNED BY CN

CHECKED BY ESD


REVIEWED BY KS





Engineering Services
D | V | S | O N

GP-2020-___.PWD

21509 | <u>39</u> of <u>4</u>







GP-2020-

.PWD

LANDSCAPE PLANTING NOTES

- 1. INFORMATION PROVIDED ON THIS PLAN IS GENERAL IN NATURE. DIMENSIONS, LOCATIONS, AND AREAS ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED BEFORE INSTALLATION.
- 2. INSTALLED QUANTITIES OF PLANT MATERIALS MAY VARY FROM THOSE SHOWN ON THE PLAN AND SHOULD BE FIELD DETERMINED ACCORDING TO APPROPRIATE PLANT SPACING AND FIELD CONDITIONS. DISCREPANCIES BETWEEN THE FIELD CONDITIONS AND THE PLAN WHICH LIMIT THE CONTRACTOR SHOULD BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT OR PROJECT LANDSCAPE REPRESENTATIVE BEFORE INSTALLATION OF THE AREA IN QUESTION IS COMPLETE.
- 3. SUBSTITUTION OF PLANT SPECIES, SIZES, OR OTHER SPECIFIED MATERIALS WILL NOT BE ALLOWED WITHOUT PRIOR APPROVAL BY THE LANDSCAPE ARCHITECT OR PROJECT LANDSCAPE REPRESENTATIVE.
- 4. ALL PLANT MATERIAL MUST CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARD FOR NURSERY STOCK, PUBLISHED BY THE AMERICAN HORTICULTURE INDUSTRY ASSOCIATION OR EQUIVALENT
- 5. ALL PLANT MATERIAL MUST BE APPROVED BY THE LANDSCAPE ARCHITECT OR PROJECT LANDSCAPE REPRESENTATIVE PRIOR TO PLANTING.
- 6. INSTALLATION OF ALL LANDSCAPING MUST BE COORDINATED WITH THE INSTALLATION OF RELATED IRRIGATION, SITE WORK, AND GRADING.
- 7. EXISTING TREES TO BE SAVED MUST BE PROTECTED BEFORE CONSTRUCTION BEGINS. SEE "TREE PROTECTION AND ENVIRONMENTAL NOTES" SHEET FOR TREE PROTECTION LOCATIONS AND TREE PROTECTION DETAILS. NO EQUIPMENT OR MATERIALS SHALL BE STORED OR OPERATED WITHIN THE FENCED AREAS.
- 8. LANDSCAPE ARCHITECT OR PROJECT LANDSCAPE REPRESENTATIVE CAN BE CONTACTED AT 512.974.7006 OR KIMBERLY.GILBERTSON@AUSTNITEXAS.GOV.

TREES - SPECIAL CONSTRUCTION TECHNIQUES

- 9. BEFORE EXCAVATION WITHIN TREE DRIP LINES OR THE REMOVAL OF TREES NEXT TO OTHER TREES THAT ARE TO REMAIN, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT TO MINIMIZE ROOT DAMAGE.
- 10. CRITICAL ROOT ZONE AREAS THAT CANNOT BE PROTECTED DURING CONSTRUCTION WITH FENCING AND WHERE HEAVY VEHICULAR TRAFFIC IS ANTICIPATED MUST BE COVERED WITH A MINIMUM OF 12 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION. IN AREAS WITH HIGH SOIL PLASTICITY, PLACE GEOTEXTILE FABRIC (PER STANDARD SPEC. 620S) UNDER THE MULCH TO PREVENT EXCESSIVE MIXING OF THE SOIL AND MULCH. ADDITIONAL MATERIALS SUCH AS PLYWOOD MAY BE REQUIRED BY THE CITY ARBORIST TO MINIMIZE ROOT IMPACTS FROM HEAVY EQUIPMENT. ONCE THE PROJECT IS COMPLETE. SUPPLEMENTAL ROOT-PROTECTION MATERIALS SHOULD BE REMOVED AND MULCH COVER REDUCED FROM 12 TO 3 INCHES
- 11. PERFORM ALL GRADING WITHIN CRITICAL ROOT ZONE AREAS BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE.
- 12. WATER ALL TREES IMPACTED BY CONSTRUCTION ACTIVITIES DEEPLY ONCE A WEEK DURING PERIOD OF HOT, DRY WEATHER. SPRAY TREE CROWNS WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION
- 13. WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, USE A PLASTIC VAPOR BARRIER BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO THE SOIL.

TREES - FERTILIZER

 HUMATE/NUTRIENT SOLUTIONS WITH MYCORRHIZAE COMPONENTS OR SOIL INJECTION AT RECOMMENDED RATES ARE TO BE USED WHEN APPROPRIATE. CONSTRUCTION WHICH WILL BE COMPLETED IN LESS THAN 90 DAYS MAY USE MATERIAL AT HALF THE RECOMMENDED RATES. ALTERNATIVE ORGANIC FERTILIZER MATERIALS ARE ACCEPTABLE WHEN APPROVED BY THE CITY ARBORIST.

TREES - TREE PROTECTION SIGNAGE

15. A LAMINATED SIGN (MIN. SIZE 8.5 x 11 INCHES) SHALL BE POSTED ON EACH TREE PROTECTIVE DEVICE AND AT LEAST EVERY 100 LINEAR FEET ON PROTECTIVE FENCING, IDENTIFYING THE FOLLOWING: TREE & ROOT PROTECTION ZONE. PER CITY OF AUSTIN CODE (CHAPTER 25-8. SUBCHAPTER B. ARTICLE 1). TREE PROTECTION AND SIGNAGE IS TO REMAIN IN PLACE FOR THE ENTIRETY OF THE CONSTRUCTION. SEE THIS SHEET FOR SIGN EXAMPLE

SEQUENCE OF TREE CARE NOTES

- 1. ANALYSIS (SOIL, FOLIAR, PRUNING, NUTRIENT, ETC.) AND REVIEW OF EACH TREE IMPACTED BY CONSTRUCTION BY CERTIFIED ARBORIST.
- 2. COORDINATE RECOMMENDATIONS WITH GENERAL PERMIT OFFICE. COORDINATE ALL PRECONSTRUCTION ACTIVITIES (INCLUDING PRUNING) WITH GENERAL PERMIT OFFICE.
- 3. PRUNE TREES AND APPLY PRECONSTRUCTION NUTRIENTS
- 4. INSTALL TREE PROTECTION (FENCING, BOARDING, ETC.)
- 5. MONITOR CONDITION OF TREES DURING CONSTRUCTION. COORDINATE ANY RECOMMENDATIONS AND IMPLEMENTATION FOR TREE CARE WITH GENERAL PERMIT OFFICE DURING CONSTRUCTION PERIOD (E.G. WATER, ADDITIONAL PRUNING, NUTRIENTS, TREE PROTECTION).
- 6. FOLLOWING CONSTRUCTION, AERATE TREES WITH AIR INJECTION
- 6.1. SUPERSONIC NOZZLE, 90 PSIG, 150 SCFM, OR APPROVED EQUIVALENT
- 6.2. AERATE SOIL TO 6 INCH DEPTH OR GREATER AS RECOMMENDED BY CERTIFIED ARBORIST
- 6.3. REMOVE SOIL AND REPLACE WITH MULCH TO A DEPTH OF 3 INCHES
- 6.4. PROTECT AERATED SOIL AND MULCH UNTIL FINAL ACCEPTANCE. DO NOT ALLOW COMPACTION OF AERATED AREAS OR MULCH
- 7. APPLY POSTCONSTRUCTION FERTILIZATION
- 8. REMOVE TREE PROTECTION
- 9. FOR ANY QUESTIONS: LANDSCAPE ARCHITECT OR PROJECT LANDSCAPE REPRESENTATIVE CAN BE CONTACTED AT 512.974.7006 OR KIMBERLY.GILBERTSON@AUSTINTEXAS.GOV.

NOTE: ALL TREE CARE INCLUDING PRUNING, AERATION, AND FERTILIZATION MUST BE COMPLETED BY A CERTIFIED ARBORIST.

TO PREVENT OAK WILT TRANSMISSION, AVOID PRUNING LIVE AND RED OAKS FEB 1 - JUNE 30. ALWAYS PAINT FRESH WOUNDS ON OAKS WITH WOUND DRESSING OR LATEX PAINT IMMEDIATELY AFTER PRUNING.

ECM 3.5.4 D. SPECIAL CONSTRUCTION TECHNIQUES

IN CONJUNCTION WITH REMEDIAL CARE, MITIGATION FOR TREES REMOVED MAY INCLUDE SPECIAL CONSTRUCTION TECHNIQUES NOT NORMALLY REQUIRED IN STANDARD SPECIFICATIONS. SOME OF THESE TECHNIQUES INCLUDE THE FOLLOWING:

- 1. PRIOR TO EXCAVATION WITHIN TREE DRIPLINES OR THE REMOVAL OF TREES ADJACENT TO OTHER TREES THAT ARE TO REMAIN, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT TO MINIMIZE ROOT DAMAGE.
- 2. IN CRITICAL ROOT ZONE AREAS THAT CANNOT BE PROTECTED DURING CONSTRUCTION WITH FENCING AND WHERE HEAVY VEHICULAR TRAFFIC IS ANTICIPATED, COVER THOSE AREAS WITH A MINIMUM OF 12 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION. IN AREAS WITH HIGH SOIL PLASTICITY GEOTEXTILE FABRIC, PER STANDARD SPECIFICATION 620S, SHOULD BE PLACED UNDER THE MULCH TO PREVENT EXCESSIVE MIXING OF THE SOIL AND MULCH. ADDITIONALLY, MATERIAL SUCH AS PLYWOOD AND METAL SHEETS COULD BE REQUIRED BY THE CITY ARBORIST TO MINIMIZE ROOT IMPACTS FROM HEAVY EQUIPMENT. ONCE THE PROJECT IS COMPLETED, ALL MATERIALS SHOULD BE REMOVED, AND THE MULCH SHOULD BE REDUCED TO A DEPTH OF 3 INCHES.
- 3. PERFORM ALL GRADING WITHIN CRITICAL ROOT ZONE AREAS BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE.
- 4. WATER ALL TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. SPRAY TREE CROWNS WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- 5. WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, USE A PLASTIC VAPOR BARRIER BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO THE SOIL.

APPENDIX P-6: REMEDIAL TREE CARE NOTES AERATION AND SUPPLEMENTAL NUTRIENT REQUIREMENTS FOR TREES WITHIN CONSTRUCTION ZONES

AS A COMPONENT OF AN EFFECTIVE REMEDIAL TREE CARE PROGRAM PER ENVIRONMENTAL CRITERIA MANUAL SECTION 3.5.4, PRESERVED TREES WITHIN THE LIMITS OF CONSTRUCTION MAY REQUIRE SOIL AERATION AND SUPPLEMENTAL NUTRIENTS. SOIL AND/OR FOLIAR ANALYSIS SHOULD BE USED TO DETERMINE THE NEED FOR SUPPLEMENTAL NUTRIENTS. THE CITY ARBORIST MAY REQUIRE THESE ANALYSES AS PART OF A COMPREHENSIVE TREE CARE PLAN. SOIL PH SHALL BE CONSIDERED WHEN DETERMINING THE FERTILIZATION COMPOSITION AS SOIL PH INFLUENCES THE TREE'S ABILITY TO UPTAKE NUTRIENTS FROM THE SOIL. IF ANALYSES INDICATE THE NEED FOR SUPPLEMENTAL NUTRIENTS, THEN HUMATE/NUTRIENT SOLUTIONS WITH MYCORRHIZAE COMPONENTS ARE HIGHLY RECOMMENDED. IN ADDITION, SOIL ANALYSIS MAY BE NEEDED TO DETERMINE IF ORGANIC MATERIAL OR BENEFICIAL MICROORGANISMS ARE NEEDED TO IMPROVE SOIL HEALTH. MATERIALS AND METHODS ARE TO BE APPROVED BY THE CITY ARBORIST (512-974-2755) PRIOR TO APPLICATION. THE OWNER OR GENERAL CONTRACTOR SHALL SELECT A FERTILIZATION CONTRACTOR AND ENSURE COORDINATION WITH THE CITY ARBORIST.

PRE-CONSTRUCTION TREATMENT SHOULD BE APPLIED IN THE APPROPRIATE SEASON, IDEALLY THE SEASON PRECEDING THE PROPOSED CONSTRUCTION. MINIMALLY, AREAS TO BE TREATED INCLUDE THE ENTIRE CRITICAL ROOT ZONE OF TREES AS DEPICTED ON THE CITY APPROVED PLANS. TREATMENT SHOULD INCLUDE, BUT NOT BE LIMITED TO, FERTILIZATION, SOIL TREATMENT, MULCHING, AND PROPER PRUNING.

POST-CONSTRUCTION TREATMENT SHOULD OCCUR DURING FINAL REVEGETATION OR AS DETERMINED BY A QUALIFIED ARBORIST AFTER CONSTRUCTION. CONSTRUCTION ACTIVITIES OFTEN RESULT IN A REDUCTION IN SOIL MACRO AND MICRO PORES AND AN INCREASE IN SOIL BULK DENSITY. TO AMELIORATE THE DEGRADED SOIL CONDITIONS, AERATION VIA WATER AND/OR AIR INJECTED INTO THE SOIL IS NEEDED OR BY OTHER METHODS AS APPROVED BY THE CITY ARBORIST. THE PROPOSED NUTRIENT MIX SPECIFICATIONS AND SOIL AND/OR FOLIAR ANALYSIS RESULTS NEED TO BE PROVIDED TO AND APPROVED BY THE CITY ARBORIST PRIOR TO APPLICATION (FAX # 512-974-3010 OR CITYARBORIST@AUSTINTEXAS.GOV). CONSTRUCTION WHICH WILL BE COMPLETED IN LESS THAN 90 DAYS MAY USE MATERIALS AT ½ RECOMMENDED RATES. ALTERNATIVE ORGANIC FERTILIZER MATERIALS ARE ACCEPTABLE WHEN APPROVED BY THE CITY ARBORIST. WITHIN 7 DAYS AFTER FERTILIZATION IS PERFORMED. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION OF THE WORK PERFORMED TO THE CITY ARBORIST. DEVELOPMENT SERVICES DEPARTMENT. P.O. BOX 1088, AUSTIN, TX 78767. THIS NOTE SHOULD BE REFERENCED AS ITEM #1 IN THE SEQUENCE OF CONSTRUCTION.

APPENDIX O: LANDSCAPE IRRIGATION NOTES

SITE DEVELOPMENT PERMIT - IRRIGATION NOTES

AUTOMATIC IRRIGATION SYSTEMS SHALL COMPLY WITH TCEQ CHAPTER 344, AS WELL AS THE FOLLOWING

- 1. THESE REQUIREMENTS SHALL BE NOTED ON THE SITE DEVELOPMENT PERMIT AND SHALL BE IMPLEMENTED AS PART OF THE LANDSCAPE INSPECTION:
- 1.1. THE SYSTEM MUST PROVIDE A MOISTURE LEVEL ADEQUATE TO SUSTAIN GROWTH OF THE PLANTS MATERIALS;
- 1.2. THE SYSTEM DOES NOT INCLUDE SPRAY IRRIGATION ON AREAS LESS THAN TEN (10) FEET WIDE (SUCH AS MERIDIANS, BUFFER STRIPS, AND PARKING LOT ISLANDS);
- 1.3. CIRCUIT REMOTE CONTROL VALVES HAVE ADJUSTABLE FLOW CONTROLS;
- 1.4. SERVICEABLE IN-HEAD CHECK VALVES AREA ADJACENT TO PAVED AREAS WHERE ELEVATION DIFFERENCES MAY CAUSE LOW HEAD DRAINAGE;
- 1.5. A MASTER VALVE INSTALLED ON THE DISCHARGE SIDE OF THE BACKFLOW PREVENTER;
- ABOVE-GROUND IRRIGATION EMISSION DEVICES ARE SET BACK AT LEAST SIX (6) INCHES FROM IMPERVIOUS SURFACES;
- 1.7. AN AUTOMATIC RAIN SHUT-OFF DEVICE SHUTS OFF THE IRRIGATION SYSTEM AUTOMATICALLY AFTER
- MORE THAN A ONE-HALF INCH $(\frac{1}{2})$ RAINFALL; AND 1.8. NEWLY PLANTED TREES SHALL HAVE PERMANENT IRRIGATION CONSISTING OF DRIP OR BUBBLERS.
- 2. THE IRRIGATION INSTALLER SHALL DEVELOP AND PROVIDE AN AS-BUILT DESIGN PLAN TO THE CITY AT THE TIME THE FINAL IRRIGATION INSPECTION IS PERFORMED;
- 2.1. UNLESS FISCAL SECURITY IS PROVIDED TO THE CITY FOR THE INSTALLATION OF THE SYSTEM, IT MUST BE OPERATIONAL AT THE TIME OF THE FINAL LANDSCAPE INSPECTION. 3. THE IRRIGATION INSTALLER SHALL ALSO PROVIDE EXHIBITS TO BE PERMANENTLY INSTALLED INSIDE OR
- ATTACHED TO THE IRRIGATION CONTROLLER, INCLUDING: 3.1. A LAMINATED COPY OF THE WATER BUDGET CONTAINING ZONE NUMBERS, PRECIPITATION RATE,

GALLONS PER MINUTE AND THE LOCATION OF THE ISOLATION VALVE; AND AN AS BUILT PLAN.

4. THE IRRIGATION INSTALLER SHALL PROVIDE A REPORT TO THE CITY ON A FORM PROVIDED BY AUSTIN WATER CERTIFYING COMPLIANCE WITH SUBSECTION 1. WHEN THE FINAL PLUMBING INSPECTION IS PERFORMED BY THE CITY.

SOURCE: RULE NO. R161-17.09, 5-16-2017; RULE NO. R61-18.01, 3-2-2018.



TREE & ROOT PROTECTION ZONE

Per City of Austin code (Chapter 25-8, Subchapter B, Article 1 this protective device is to remain in place for the entirety of the development project and illegal removal is subject to fines and work suspensions. Additional information can be obtained at the: City Arborist (512-974-1876)


web site (http://www.ci.austin.tx.us/trees).


Zona de Protección del Árbol y las Raícesel dispositivo protector debe quedarse en el lugar para la totalidad del proyecto de la construcción. Para información adicional, contacta la Arborista Municipal (512) 974-1876 o http://www.ci.austin.tx.us/trees/trees_spanish.htm

TREE PROTECTION SIGN

APPENDIX P-2: - CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION

- 1. ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE PROTECTED DURING CONSTRUCTION WITH TEMPORARY FENCING.
- 2. PROTECTIVE FENCES SHALL BE ERECTED ACCORDING TO CITY OF AUSTIN STANDARDS FOR TREE
- 3. PROTECTIVE FENCES SHALL BE INSTALLED PRIOR TO THE START OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR GRADING), AND SHALL BE MAINTAINED THROUGHOUT ALL PHASES OF THE **CONSTRUCTION PROJECT**
- 4. EROSION AND SEDIMENTATION CONTROL BARRIERS SHALL BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILD-UP WITHIN TREE DRIP LINES.
- 5. PROTECTIVE FENCES SHALL SURROUND THE TREES OR GROUP OF TREES, AND WILL BE LOCATED AT THE OUTERMOST LIMIT OF BRANCHES (DRIP LINE), FOR NATURAL AREAS, PROTECTIVE FENCES SHALL FOLLOW THE LIMIT OF CONSTRUCTION LINE, IN ORDER TO PREVENT THE FOLLOWING:
 - A.SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF **EQUIPMENT OR MATERIALS:**
 - B.ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN 6 INCHES CUT OR FILL), OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE CITY ARBORIST;
 - C.WOUNDS TO EXPOSED ROOTS, TRUNK OR LIMBS BY MECHANICAL EQUIPMENT;
 - D.OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING, AND FIRES.
- 6. EXCEPTIONS TO INSTALLING FENCES AT TREE DRIP LINES MAY BE PERMITTED IN THE FOLLOWING CASES:
 - A.WHERE THERE IS TO BE AN APPROVED GRADE CHANGE, IMPERMEABLE PAVING SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE APPROXIMATELY 2 TO 4 FEET BEYOND THE AREA DISTURBED:
 - B.WHERE PERMEABLE PAVING IS TO BE INSTALLED WITHIN A TREE'S DRIP LINE. ERECT THE FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA (PRIOR TO SITE GRADING SO THAT THIS AREA IS GRADED SEPARATELY PRIOR TO PAVING INSTALLATION TO MINIMIZED ROOT DAMAGE);
 - C.WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE TO ALLOW 6 TO 10 FEET OF WORK SPACE BETWEEN THE FENCE AND THE BUILDING;
 - D.WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE, OR OTHER SPECIAL REQUIREMENTS, CONTACT THE CITY ARBORIST AT 974-1876 TO DISCUSS ALTERNATIVES.
 - SPECIAL NOTE: FOR THE PROTECTION OF NATURAL AREAS, NO EXCEPTIONS TO INSTALLING FENCES AT THE LIMIT OF CONSTRUCTION LINE WILL BE PERMITTED.
- 7. WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE BEING CLOSER THAN 4 FEET TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF 8 FT (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING PROVIDED.
- 8. TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.
- 9. ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT AREAS WITH GOOD QUALITY TOP SOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN 2 DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
- 10. ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE.
- 11. NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN THE DRIP LINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
- 12. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE DAMAGE OCCURS (RIPPING OF BRANCHES, ETC.).
- 13. ALL FINISHED PRUNING SHALL BE DONE ACCORDING TO RECOGNIZED, APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES AVAILABLE ON REQUEST FROM THE CITY ARBORIST).
- 14. DEVIATIONS FROM THE ABOVE NOTES MAY BE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NON-COMPLIANCE OR IF A TREE SUSTAINS DAMAGE AS A RESULT






THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT

CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE OR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL

> ᇟ迈 RED Ш




| NOTES | NAME | DAT |
|-------------|------|-----|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |



DIVISION

GP-2020-

.PWD







NOTE: SEE CIVIL SHEETS FOR PROPOSED PLANTER PLACEMENT.

| PLANT & MATERIAL KEY | | | | | |
|----------------------|-------|-------------------------|--|--|--|
| | | I | | | |
| SYMBOL | ABBR. | COMMON NAME | | | |
| £;3 | AG | PARRY AGAVE | | | |
| * | ВІ | BIG MUHLY | | | |
| • | ВР | PRIDE OF BARBADOS RED | | | |
| \odot | CE | CEDAR ELM | | | |
| ફિંફ | ОР | SPINELESS PRICKLY PEAR | | | |
| \odot | RB | TEXAS RED BUD | | | |
| 4003 | TL | TRAILING PURPLE LANTANA | | | |
| | DG | DECOMPOSED GRANITE | | | |
| | НМ | HARDWOOD MULCH | | | |
| | LE | LANDSCAPE EDGING | | | |
| | DE | DECORATIVE METAL EDGING | | | |







KEVIN SWEAT


THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.

| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | KG | |
| DESIGNED BY | KG | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |

| HORIZONTAL SCALE IN FEET |
|--------------------------|
| |


| GP-2020 | PWD |
|---------|-----|
| | 4.0 |



TL 1 (LE)

NOTE: EXISTING BOULDERS (6) TO BE RELOCATED AROUND

NEW PLANTINGS IN BEDS.



KEVIN SWEAT

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY KEVIN SWEAT LIC. # 92023

CERTIFY THAT THESE DRAWINGS ARE


AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.


| NOTES | NAME | DATE | | |
|-------------|------|------|--|--|
| SURVEY BY | | | | |
| DRAWN BY | DS | | | |
| DESIGNED BY | CN | | | |
| CHECKED BY | ESD | | | |
| REVIEWED BY | KS | | | |


LE BI 1 DG

HORIZONTAL SCALE IN FEET


GP-2020-____.PWD L102 | 43 OF <u>46</u>








| PLANTERS KEY | | | | | |
|-------------------------|--|--------------------------|-------------------------|----------|----------|
| PLANT SYMBOL | ANT SYMBOL ABBREVIATION COMMON NAME BOTANICAL NAME | | | | QUANTITY |
| <u>•</u> | DA | DAMIANITA | Chrysactina mexicana | 1 GALLON | 44 |
| * | FE | MEXICAN FEATHER GRASS | Nassella tenuissima | 1 GALLON | 132 |
| \bigcirc | FI | FIRECRACKER FERN | Russelia equisetiformis | 1 GALLON | 22 |
| $\langle \cdot \rangle$ | IP | ICE PLANT | Delosperma cooperi | 1 GALLON | 66 |
| | TY | TWIST LEAF YUCCA (GREEN) | Yucca rupicola | 1 GALLON | 44 |
| LARGE PLANTER | LP | | | 8X3X3 | 22 |
| SMALL PLANTER | SP | | | 8X3X1 | 22 |




── 1" DIAMETER DRAINAGE HOLES PLANTER - SIDE VIEW AT APPROXIMATELY 1' APART TYP.

- PLANTER DIMENSIONS ARE 8'X3'X3' AND 8'X1'X3'. SEE SHEETS CD101-CD106 FOR PLANTER
- PLACEMENT. SEE SS750 FOR PLANTER SPECIFICATIONS.
- DRAINAGE HOLES TO BE INCLUDED. TO BE DRILLED ON STREET FACING SIDE OF PLANTER.
- PLANTER MATERIAL TO BE $\frac{1}{4}$ " MILD STEEL. ROLL OR SPRAY ON WATERPROOFING ON INSIDE OF
- ALL PLANTERS.
- ALL DIMENSIONS AND CALL OUTS APPLY TO BOTH 8X3X3 AND 8X1X3 PLANTERS UNLESS OTHERWISE
- MEASURE EXISTING SLOPES BEFORE BUILDING ALL PLANTERS. ONCE PLACED IN FIELD, FRONT FACE OF PLANTERS TO BE LEVEL VERTICALLY AT 36".



PLANTER FRONT - SECTION





KEVIN SWEAT

THE SEAL APPEARING ON THIS
DOCUMENT WAS AUTHORIZED BY
KEVIN SWEAT
LIC. # 92023

I CERTIFY THAT THESE DRAWINGS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THEIR INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION UNTIL FORMAL CITY APPROVAL.


| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |


|) | 20 | 40 |
|------------|-------------|----|
| | | |
| HORIZONTAL | SCALE IN FE | ΞT |

GP-2020-____.PWD 45 of <u>46</u>

| PLANT SCHEDULE | | | | | | |
|---------------------|--------------|-------------------------|-----------------------------------|-----------|-----------|----------|
| PLANT SYMBOL | ABBREVIATION | COMMON NAME | BOTANICAL NAME | SIZE | SPACING | QUANTITY |
| | AG | PARRY AGAVE | Agave parryi var. parryi | 5 GALLON | PER PLANS | 14 |
| * | ВІ | BIG MUHLY | Muhlenbergia lindheimeri | 5 GALLON | PER PLANS | 20 |
| ▼ | BP | PRIDE OF BARBADOS RED | Caesalpinia pulcherrima | 5 GALLON | PER PLANS | 7 |
| \odot | CE | CEDAR ELM | Ulmus crassifolia | 3" | PER PLANS | 1 |
| 5.55 | ОР | SPINELESS PRICKLY PEAR | Opuntia ellisiana | 5 GALLON | PER PLANS | 9 |
| \odot | RB | TEXAS REDBUD | Cercis canadensis var. 'texensis' | 45 GALLON | PER PLANS | 11 |
| Accorded the second | TL | PURPLE TRAILING LANTANA | Lantana montevidensis | 1 GALLON | PER PLANS | 31 |

| MATERIAL SCHEDULE | | | | | |
|------------------------|--------------|--|----------------------|---|--|
| SYMBOL | ABBREVIATION | MATERIAL | QUANTITY | NOTES | |
| | DG | DECOMPOSED GRANITE | 42 CY | 6" DEEP PER PLANS | |
| HM HARDWOOD MULCH 13 C | | 13 CY | 3" DEEP PER PLANS | | |
| | TS-B | TOP SOIL (PLANTING BEDS, RED BUDS AT 7TH ST/RED RIVER CORNER, AND CEDAR ELM AT STA 14+25) | 28 CY | 6" DEEP PER PLANS | |
| | РМ | PLANTING MIX (PLANTERS) | 40 CY | FILL TOP ½ OF PLANTERS PER PLANS | |
| | LE | LANDSCAPE EDGING | 300 LF | ੀ"X6"X10' PER PLANS | |
| | WG | 1-2" WASHED GRAVEL | 40 CY | FILL BOTTOM ½ OF PLANTERS PER PLANS | |
| | DE | 8" TALL DECORATIVE METAL EDGING | 152 LF | PER PLANS | |





| NOTES | NAME | DATE |
|-------------|------|------|
| SURVEY BY | | |
| DRAWN BY | DS | |
| DESIGNED BY | CN | |
| CHECKED BY | ESD | |
| REVIEWED BY | KS | |
| | | |

0 20 40
HORIZONTAL SCALE IN FEET

GP-2020-___.PWD

L602 46 OF 46