



ADDENDUM
CITY OF AUSTIN, TEXAS

Solicitation: MEA0303

Addendum No: 3

Date of Addendum: July 11, 2016

This addendum is to incorporate the following changes to the above referenced solicitation:

I QUESTIONS:

- Q1: Addendum 2.P.11.3 states "Provide electrical disconnect/reconnect at motor breaker." Does this statement indicate that AE will only provide electrical disconnect/reconnect at the breakers located immediately next to the motors. This would infer that AE will not provide any electrical disconnect/reconnect at the existing junction box or existing transmitters tec. Please clarify.**
- A1: AE will provide electrical disconnect/reconnect at the Motor Control Center breaker. Not located next to the motor.
- Q2: Please clarify how AE defines electrical disconnect/reconnect. Will AE de-terminate wiring and then physically disconnect the flex conduit from the junction boxes, or will AE only determine wires and leave all conduit in place?**
- A2: It is the intent of the work scope for the contractor to provide all disconnect at the skid.
- Q3: Addendum 2.E.4.8 states "...with a local disconnect (for LOTO purposes)". AE is stating that a (one) local disconnect is required. This local disconnect would isolate all power to the skid and therefore isolate both motors. Please confirm this is what AE is requesting.**
- A3: AE is requesting a local disconnect that would isolate power at each motor.
- Q4: Please clarify if Austin Energy will be completing the purging and line breaking of the existing skid tie-points (dilution air inlet, fan discharge, NH3 feed).**
- A4: AE will purge the NH3 feed only.
- Q5: Please provide further clarification to Scope of Work 4.7 "All piping shall be insulated"**
- A5: Correct, all piping shall be insulated either for personnel protection or freeze protection.
- Q6: Please confirm that there will be one waste bin for regular trash and one waste bin for all steel. Please confirm it is not expected that carbon steels and stainless steels are separated. AE's environmental engineer stated the concrete must be separated from the pedestal prior to being placed into the waste bin- please clarify if is is expected the pedestal filled with concrete filled pedestal be separated and disposed in the appropriate waste bins vs placing concrete filled pedestal into trash bin.**
- A6: Only two bins available one waste bin and one scrap metal bin. Scrap metal goes into scrap bin, concrete goes into waste bin or concrete pile.

Q7: Please confirm that excluded from the scope of work is removal, reinstallation, and wiring of the atmospheric air monitor.

A7: Correct the removal, reinstallation and wiring of the atmospheric air monitor are excluded from the Scope of Work.

II. ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.

APPROVED BY: Maria Andrade
Maria Andrade, Buyer II
Purchasing Office, 512-972-9424

7/12/16
Date

ACKNOWLEDGED BY:

Name

Authorized Signature

Date

RETURN ONE COPY OF THIS ADDENDUM TO THE PURCHASING OFFICE, CITY OF AUSTIN, WITH YOUR RESPONSE OR PRIOR TO THE SOLICITATION CLOSING DATE. FAILURE TO DO SO MAY CONSTITUTE GROUNDS FOR REJECTION.